


FRAMING PLAN

Scale: 1/8" = 1'-0"




FOR MASONRY CONTROL JOINT SEE DETAIL 2/S4. COORDINATE WITH ARCHITECTURAL FOR CONTROL JOINT LOCATION.

FOR LOCATIONS OF MECHANICAL OPENINGS IN MASONRY WALL, REFER TO MECHANICAL DRAWINGS. SEE MASONRY LINTEL SCHEDULE FOR BOND BEAM REQUIREMENTS. OPENINGS GREATER THAN 60" WIDE REQUIRE NOTIFICATION TO THE PROJECT ENGINEER FOR SPECIAL ANALYSIS. MECHANICAL OPENINGS SHALL NOT BE LOCATED OVER ANY EXTERIOR DOORS. TOP OF OPENING TO BE LOCATED A MINIMUM 12" BELOW CONTINUOUS LEDGER ANGLES AND 18" BELOW WIND BEAM CENTERLINE.

MASONRY LINTEL SCHEDULE	
	0'-0" TO 5'-0" MASONRY OPENING: 8" DEEP LINTEL BLOCK WITH (2) #5's CONTINUOUS AS SHOWN. LINTEL BLOCK TO EXTEND 32" BEYOND OPENINGS, SEE WALL ELEVATION 1/S4 & 2/S4
	5'-1" TO 8'-0" MASONRY OPENING: 16" DEEP LINTEL BLOCK WITH (4) #5's CONTINUOUS AS SHOWN. LINTEL BLOCK TO EXTEND 32" BEYOND OPENINGS, SEE WALL ELEVATION 1/S4 & 2/S4


KEYNOTES

- STEEL COLUMN AND FRAME BY PRE-ENGINEERED METAL BUILDING MANUFACTURER. HOLD FRAME DRIFT TO H/150.
- ROOF PURLINS BY PRE-ENGINEERED METAL BUILDING MANUFACTURER. REFER TO SECTION 8/SS.2 FOR SPECIAL CONNECTION OF ROOF PURLINS AT MASONRY WALL FOR PURLINS SUPPORTING RTU LOADS.
- SPANDREL BEAM BY PRE-ENGINEERED METAL BUILDING MANUFACTURER. HOLD DEFLECTION TO L/240.
- MASONRY LINTEL OVER DOOR OPENINGS, SEE MASONRY LINTEL SCHEDULE.
- PROVIDE JOINT IN GYP BOARD AT TRANSITION BETWEEN FLOOR SUPPORTED FULL-HEIGHT WALL AND SUSPENDED HEADER WALL TO ALLOW FOR DIFFERENTIAL MOVEMENT. REFER TO ARCHITECTURAL DRAWING FOR MORE INFORMATION.
- PROVIDE 16ga COLD-FORMED STEEL FRAMING AT ENTRY LOCATION. WHERE APPLICABLE SIGN FRAMING MEMBERS WITH METAL STUDS OVER STOREFRONT (SPACING NOT TO EXCEED 24" O.C.) ALL COLD-FORMED STEEL & COLD-FORMED STEEL CONNECTIONS TO BE A MINIMUM OF (3) #8 SDS. REFER TO ARCHITECTURAL SECTIONS FOR FRAMING PROFILES AND MEMBER DEPTHS.
- FILL ALL CELLS IN MASONRY WALL A MINIMUM 4'-8" IN EACH DIRECTION FROM CORNER. ALLOW FOR METAL BUILDING CONNECTIONS.
- PREFABRICATED METAL CANOPY, SEE SECTION 9/SS.2 AND 10/SS.2. SUPPORT STRUCTURE PROVIDED FOR ATTACHMENT. REFER TO CANOPY SUPPLIER SHOP DRAWINGS AND ARCHITECTURAL FOR ATTACHMENT AND ADDITIONAL REQUIREMENTS.




1 MASONRY WALL OPENINGS

S4 SCALE: NONE



2 TYPICAL MASONRY LINTEL DETAIL

S4 SCALE: NONE



3 PLAN VIEW OF TYPICAL MASONRY BOND BEAM

S4 SCALE: 1/8" = 1'-0"

Jeffrey S. Smith, P.E.
 Jeffrey S. Smith P.E. 019070
 1801 W 32nd St. Bldg B Ste 104 * JOPLIN, MISSOURI 64804
 P.O. Box 8102 * JOPLIN, MISSOURI 64802
 PHONE: 417-624-0444 * FAX: 417-624-0430



CRAIG A. SCHNEIDER, AIA
ARCHITECT
 1736 Earl Sunshine, Suite 417
 Springfield, Missouri 65804
 417.862.0558
 417.862.3265
 e-mail: architect@ctelectrictelnet.com

PROJECT:
NEW O'REILLY AUTO PARTS STORE
U.S. HIGHWAY 11
STRASBURG, VA
FRAMING PLAN

O'Reilly AUTO PARTS
 CORPORATE OFFICES
 235 SOUTH PATTERSON
 SPRINGFIELD, MISSOURI 65802
 (417) 862-2674 TELEPHONE

COMM #	4253
DATE:	11-2-18
REVISION	1-21-2020
DATE:	