# O'Reilly AUTO PARTS

## New O'Reilly Auto Parts Store
## 290 DEACON ROAD
## FREDERICKSBURG, VA #4

### QUALITY CONTROL

1. REFER TO PROJECT MANUAL, SECTION 01 45 16 - QUALITY CONTROL PROCEDURES, FOR ADDITIONAL REQUIREMENTS.

2. REFER TO STRUCTURAL DRAWINGS FOR SCHEDULE OF SPECIAL INSPECTIONS, IF INDICATED.

3. WHERE REQUIRED, THE OWNER SHALL PROVIDE THE SERVICES OF AN INDEPENDENT TESTING LABORATORY TO PERFORM TESTING AND SPECIAL INSPECTIONS INDICATED.

### ABBREVIATIONS LEGEND

| | |
|---|---|
| AFF | ABOVE FINISHED FLOOR |
| AC | ACOUSTICAL |
| A/C | AIR CONDITIONING |
| ALT | ALTERNATE |
| AL | ALUMINUM |
| ALUM | ALUMINUM |
| AB | ANCHOR BOLT |
| ARCH | ARCHITECT (URAL) |
| BSMT | BASEMENT |
| BRG | BEARING |
| BM | BENCH MARK |
| BEL | BELOW |
| BLK | BLOCK |
| BLKG | BLOCKING |
| BD | BOARD |
| BW | BOTH WAYS |
| BOT | BOTTOM |
| BF | BOTTOM OF FOOTING |
| BOF | BOTTOM OF FOOTING |
| BRK | BRICK |
| BLDG | BUILDING |
| BUR | BUILT-UP ROOFING |
| CAB | CABINET |
| CLG | CEILING |
| CL | CENTER LINE |
| C/O | CENTER OF |
| CC | CENTER TO CENTER |
| CLR | CLEAR |
| COL | COLUMN |
| CONC | CONCRETE |
| CMU | CONCRETE MASONRY UNIT |
| CONST | CONSTRUCTION |
| CONTR | CONTRACTOR |
| CONT | CONTINUOUS |
| CNTR | COUNTER |
| CFL | COUNTER FLASHING |
| CSNK | COUNTERSINK |
| CRS | COURSE(S) |
| CF | CUBIC FOOT |
| CY | CUBIC YARD |
| DL | DEAD LOAD |
| DEM | DEMOLISH, DEMOLITION |
| DTL | DETAIL |
| DIAG | DIAGONAL |
| DIAM | DIAMETER |
| DIM | DIMENSION |
| DR | DOOR |
| DS | DOWN SPOUT |
| D | DRAIN |
| DWG | DRAWING |
| DF | DRINKING FOUNTAIN |
| E | EAST |
| EIFS | EXTERIOR INSULATION AND FINISH SYSTEM |
| ELEC | ELECTRIC(AL) |
| EWC | ELECTRIC WATER COOLER |
| EL | ELEVATION |
| ELEV | ELEVATION |
| ELEV | ELEVATOR |
| EMER | EMERGENCY |
| EQ | EQUAL |
| EXG | EXISTING |
| EXIST | EXISTING |
| EXP | EXPOSED |
| EXT | EXTERIOR |
| FOF | FACE OF FINISH |
| FO | FACE OF |
| FOM | FACE OF MASONRY |
| FOS | FACE OF STUDS |
| FIN | FINISH(ED) |
| FFE | FINISHED FLOOR ELEV. |
| FFL | FINISHED FLOOR LINE |
| FE | FIRE EXTINGUISHER |
| FEC | FIRE EXTINGUISHER CABINET |
| FT | FIRE TREATED |
| FLG | FLASHING |
| FLR | FLOOR |
| FD | FLOOR DRAIN |
| FTG | FOOTING |
| FDN | FOUNDATION |
| FNDN | FOUNDATION |
| FUR | FURRED(ING) |
| GA | GAGE, GAUGE |
| GV | GALVANIZED |
| GALV | GALVANIZED |
| GC | GENERAL CONTRACT(OR) |
| GL | GLASS, GLAZING |
| GP | GYPSUM |
| GYP | GYPSUM |
| GWB | GYPSUM WALL BOARD |
| HTG | HEATING |
| HVAC | HEATING/VENTILATING/AIR COND. |
| HT | HEIGHT |
| HC | HOLLOW CORE |
| HM | HOLLOW METAL |
| HK | HOOK(S) |
| HOR | HORIZONTAL |
| HB | HOSE BIBB |
| INS | INSULATE(D), (ION) |
| INSUL | INSULATE |
| INT | INTERIOR |
| JST | JOIST |
| JT | JOINT |
| JNT | JOINT |
| KIT | KITCHEN |
| LH | LEFT HAND |
| LF | LINEAL FOOT |
| LTL | LENGTH |
| L | LINTEL |
| LL | LIVE LOAD |
| MACH | MACHINE |
| MH | MANHOLE |
| MFR | MANUFACTURER |
| MAS | MASONRY |
| MO | MASONRY OPENING |
| MAX | MAXIMUM |
| MECH | MECHANIC(AL) |
| MED | MEDIUM |
| MBR | MODIFIED BITUMEN ROOFING |
| MET | METAL |
| MTL | METAL |
| M | METER(S) |
| MWK | MILLWORK |
| MIN | MINIMUM |
| MISC | MISCELLANEOUS |
| MT | MOUNT(ED), (ING) |
| NOM | NOMINAL |
| N | NORTH |
| NIC | NOT IN CONTRACT |
| NTS | NOT TO SCALE |
| OC | ON CENTER(S) |
| OPG | OPENING |
| OPH | OPPOSITE HAND |
| OD | OUTSIDE DIAMETER |
| OO | OUT TO OUT |
| OA | OVERALL |
| OH | OVERHEAD |
| PC | PIECE |
| PNT | PAINT(ED) |
| PTD | PAINT(ED) |
| PKG | PARKING |
| PLAM | PLASTIC LAMINATE |
| PL | PLATE |
| PWD | PLYWOOD |
| PVC | POLYVINYL CHLORIDE |
| PSF | POUNDS PER SQUARE FT. |
| PSI | POUNDS PER SQUARE IN. |
| PT | PRESSURE TREATED |
| PL | PROPERTY LINE |
| REM | REMOVE |
| RET | RETURN |
| RH | RIGHT HAND |
| RD | ROOF DRAIN |
| RFG | ROOFING |
| RM | ROOM |
| RO | ROUGH OPENING |
| SNT | SEALANT |
| SLNT | SEALANT |
| SEC | SECTION |
| SECT | SECTION |
| SHTHG | SHEATHING |
| SHT | SHEET |
| SIM | SIMILAR |
| SC | SOLID CORE |
| S | SOUTH |
| SF | SQUARE FOOT |
| SI | SQUARE INCH |
| SY | SQUARE YARD |
| STD | STANDARD |
| STG | STORAGE |
| SUS | SUSPENDED |
| SYM | SYMMETRY, (ICAL) |
| TEL | TELEPHONE |
| TV | TELEVISION |
| THK | THICK(NESS) |
| T&G | TONGUE & GROOVE |
| TM | TOP OF MASONRY |
| TOM | TOP OF MASONRY |
| TS | TOP OF STEEL |
| TOS | TOP OF STEEL |
| TW | TOP OF WALL |
| TOW | TOP OF WALL |
| TYP | TYPICAL(LY) |
| UON | UNLESS OTHERWISE NOTED |
| UNO | UNLESS NOTED OTHERWISE |
| VERT | VERTICAL |
| VT | VINYL TILE |
| W | WASHER |
| W/ | WITH |
| WC | WATER CLOSET |
| WW | WELDED WIRE FABRIC |
| W | WEST |
| W | WIDTH, WIDE |
| WIN | WINDOW |
| W/O | WITHOUT |
| WO | WITHOUT |
| WD | WOOD |

### SYMBOLS LEGEND




### OWNER OR TENANT

O'REILLY AUTOMOTIVE STORES, INC.
CORPORATE OFFICES
233 SOUTH PATTERSON
SPRINGFIELD, MISSOURI 65802
417-862-2674 PHONE

BIDDING INFORMATION:
REFER TO OWNER'S WEB SITE:
HTTP://WWW.OREILLYPLANROOM.COM

NOTE: REFER TO CURRENT PROJECTS LIST, LOCATED AT BOTTOM OF SIGN IN PAGE, FOR INVITED GENERAL CONTRACTORS.

ALL SUB-CONTRACTOR BIDS TO BE SUBMITTED TO INVITED GENERAL CONTRACTORS ONLY.

CONTACT OWNER'S DESIGNATED REPRESENTATIVE FOR ADDITIONAL PROJECT INFORMATION.

### ARCHITECT


CRAIG A. SCHNEIDER, AIA
ARCHITECT
1736 East Sunshine, Suite 417
Springfield, Missouri 65804
417.862.0558
Fax: 417.862.3265
e-mail: architect@estesfyschneider.com


### MECH. / ELEC. ENGINEER


SGE ENGINEERING, INC.
3855 S. JEFFERSON AVE. SPRINGFIELD, MO 65807
P: 417-882-3200
F: 417-882-1188
WWW.SMITHDTH.COM


### STRUCTURAL ENGINEER


Jeffrey S. Smith, P.E.
Jeffrey S. Smith P.E. 018070
1001 W 32nd Street, Suite 104 * JOPLIN, MISSOURI 64804
PHONE: 417-624-0444 * FAX: 417-624-0430


### CIVIL ENGINEER


BOHLER ENGINEERING
CIVIL & CONSULTING ENGINEERS
SURVEYORS
PROJECT MANAGERS
ENVIRONMENTAL CONSULTANTS
LANDSCAPE ARCHITECTS
CORPORATE OFFICE:
♦ WARREN, NJ
OFFICES:
♦ SOUTHBOROUGH, MA
♦ ALBANY, NY
♦ RONKONKOMA, NY
♦ CHALFONT, PA
♦ CENTER VALLEY, PA
♦ BOWIE, MD
♦ TOWSON, MD
♦ STERLING, VA
♦ WARRENTON, VA
♦ FORT LAUDERDALE, FL
♦ PHILADELPHIA, PA
♦ TAMPA, FL


THE INFORMATION, DESIGNS AND CONCEPTS OF THE PLANS ARE PROPRIETARY AND SHALL NOT BE COPIED OR USED FOR ANY PURPOSE WITHOUT PRIOR WRITTEN AUTHORIZATION FROM BOHLER ENGINEERING. ONLY FINISHED, SIGNED, AND SEALED PLANS SHALL BE UTILIZED FOR CONSTRUCTION PURPOSES © 2015 BOHLER ENGINEERING


### SEISMIC ENGINEER - SHELVING


SEIZMIC
EST. 1985
SEIZMIC ENGINEERING, INC.
1130 E. Cypress St.
Covina, California 91724
Tel.(909)869-0989 Fax.(909)869-0981


### GENERAL NOTES

A. CONTRACT ADMINISTRATION (LIMITED SERVICE): THE ARCHITECT AND/OR ENGINEER OF RECORD INDICATED HEREIN ARE PROVIDING A LIMITED SERVICE AND NOT PROVIDING CONTRACT ADMINISTRATION SERVICES FOR THIS PROJECT WHICH IS THE RESPONSIBILITY OF OTHERS. THE ARCHITECT AND/OR ENGINEER ARE NOT RESPONSIBLE FOR FIELD ACTIVITIES ON THIS PROJECT WITHOUT DIRECT INSPECTION OF THE WORK IN PROGRESS. IF FIELD CONDITIONS ARE UNCOVERED THAT REQUIRE A CHANGE OR ADDITIONAL INFORMATION, THE ARCHITECT AND/OR ENGINEER DOES NOT DELEGATE AUTHORITY TO ANYONE ELSE FOR DETERMINING THE MEANING OF PLANS OR SPECIFICATIONS AS AUTHENTICATED HEREIN.

B. QUALITY STANDARDS AND BUILDING CODES: CONTRACTORS SHALL BE RESPONSIBLE FOR KNOWING THE QUALITY AND PUBLIC SAFETY REGULATIONS SET FORTH IN THE GOVERNING CODES AND OTHER APPLICABLE REGULATIONS OF LOCAL AND STATE AGENCIES HAVING JURISDICTION WHICH GOVERN EACH CONTRACTOR'S WORK.

C. EXISTING CONDITIONS: FIELD VERIFY EXISTING CONDITIONS BY DETAILED INSPECTION PRIOR TO SUBMITTING BID AND BEGINNING WORK. NOTIFY THE ARCHITECT AND/OR ENGINEER OF RECORD IF EXISTING CONDITIONS DEVIATE SUBSTANTIALLY FROM THOSE INDICATED HEREIN.

### SHEET INDEX

| SHEET NUMBER | SHEET NAME |
|---|---|
| T1.1 | COVER SHEET |
| T1.2 | SCOPE OF WORK SCHEDULE |
| | |
| C1 | CODE SUMMARY PLAN |
| | |
| SV | SITE SURVEY (FOR REFERENCE ONLY) |
| CT1.0 | COVER SHEET |
| CT2.0 | GENERAL NOTES & LEGEND |
| CT3.0 | GENERAL NOTES & LEGEND |
| D1.1 | SITE DEMOLITION PLAN |
| C1.1 | SITE GRADING PLAN |
| C2.1 | SITE DEVELOPMENT PLAN |
| C2.2 | SITE DETAILS |
| C2.3 | SITE DETAILS |
| C3.1 | EROSION CONTROL PLAN |
| C3.2 | EROSION CONTROL NARRATIVE |
| C3.3 | EROSION CONTROL DETAIL |
| C3.4 | SWM/BMP PLAN |
| C3.5 | SWM/BMP DETAILS |
| C3.6 | SWM/BMP DETAILS |
| C3.7 | SWM/BMP DETAILS |
| C4.1 | SITE UTILITY PLAN |
| C4.2 | UTILITY DETAILS |
| C4.3 | STORM PROFILES |
| C5.1 | FIRELANE STRIPING PLAN |
| | |
| L1.1 | LANDSCAPE PLAN |
| L1.2 | LANDSCAPE DETAILS |
| L1.3 | LANDSCAPE NOTES |
| L2.1 | IRRIGATION PLAN |
| | |
| S1.1 | STRUCTURAL NOTES |
| S1.2 | SITE SIGNAGE DETAILS |
| S2 | FOUNDATION PLAN |
| S3.1 | FOUNDATION DETAILS |
| S3.2 | FOUNDATION DETAILS |
| S4 | FRAMING DETAILS |
| S5 | FRAMING DETAILS |
| | |
| A1.1 | FLOOR PLAN |
| A1.2 | INTERIOR FINISH PLAN |
| A2.1 | EXTERIOR ELEVATIONS |
| A3.1 | WALL SECTIONS |
| A3.2 | WALL SECTIONS |
| A4.1 | INTERIOR ELEVATIONS |
| A4.2 | INTERIOR SECTIONS AND DETAILS |
| A5.1 | DOOR SCHEDULE |
| A5.2 | WINDOW SCHEDULE |
| A6.1 | EXTERIOR DETAILS |

### SHEET INDEX

| SHEET NUMBER | SHEET NAME |
|---|---|
| US1 | UTILITIES SITE PLAN |
| SP1 | SITE LIGHTING PHOTOMETRICS |
| SP2 | SITE LIGHTING DETAILS |
| SP3 | SITE LIGHTING DETAILS |
| | |
| P1 | PLUMBING PLAN |
| P2 | PLUMBING DETAILS |
| | |
| M1 | HVAC PLAN |
| M2 | HVAC SCHEDULES |
| M3 | HVAC DETAILS |
| | |
| E1 | LIGHTING PLAN |
| E2 | POWER PLAN |
| E3 | ELECTRICAL SCHEDULES |
| E4 | ELECTRICAL SCHEDULES |
| | |
| EM1.0 | GRIDPOINT EMS |
| EM1.1 | GRIDPOINT EMS |
| EM1.2 | GRIDPOINT EMS |
| | |
| SG1.1 | SITE SIGNAGE PLAN |
| SG1.2 | SITE SIGNAGE DETAILS |
| SG2.1 | BUILDING EXTERIOR SIGNAGE |
| | |
| 18-2387-A | LIGHT DUTY STORAGE (FIXTURE #1A) |
| 18-2387-B | LIGHT DUTY GONDOLA (FIXTURE #2A) |
| 18-2387-C | GRAVITY RACK (FIXTURE #3A) |
| 18-2387-D | LAYOUT |


Order Plans @ NEWLDLine.com



CRAIG A. SCHNEIDER, AIA
ARCHITECT
1736 East Sunshine, Suite 417
Springfield, Missouri 65804
417.862.0558
Fax: 417.862.3265
e-mail: architect@estesfyschneider.com


PROJECT:
NEW O'REILLY AUTO PARTS STORE
290 DEACON ROAD
FREDERICKSBURG, VA #4

COVER SHEET

O'Reilly AUTO PARTS
CORPORATE OFFICES
233 SOUTH PATTERSON
SPRINGFIELD, MISSOURI 65802
(417) 862-2674 TELEPHONE

| | |
|---|---|
| COMM # | 4251 |
| DATE: | 11-2-18 |
| REVISION DATE: | 3-25-19 |
| | 6-28-19 |

T1.1