

3. PROVIDE 1/4" LAMINATED GLASS AS INDICATED ON THESE DRAWINGS WITH POLYVINYL BUTYRAL INTERLAYER TO COMPLY WITH INTERLAYER MANUFACTURER'S WRITTEN INSTRUCTIONS.
- DIVISION 09 - FINISHES**
SECTION 09.29.00 - GYPSUM BOARD
1. PROVIDE AND INSTALL GYPSUM DRYWALL AS INDICATED ON THESE DRAWINGS, AND PER ASTM C11 OR GA-905 BY THE GYPSUM ASSOCIATION.
 2. PROVIDE 5/8" GYPSUM BOARD AS INDICATED ON THESE DRAWINGS, AS MANUFACTURED BY DOMTAR GYPSUM AMERICA, INC., GOLD BOND BLDG. PRODUCTS, AND US GYPSUM CO.
 3. GYPSUM BOARD INSTALLATION WILL BE ON METAL STUDS OR FURRING @ 16" ON CENTER UNLESS OTHERWISE NOTED. ADJUST GAUGE AS REQUIRED FOR UNSUPPORTED LENGTH PER 5 PSF. FOR LOADING REFER TO THE DRAWINGS FOR MINIMUM GAUGE.
 4. INSTALL WATER RESISTANT GYPSUM BOARD, PER ASTM C30 AT TOILETS, SERVICE SINK, ALL SINKS AND FLOOR DRAIN AREAS.
 5. PROVIDE MANUFACTURER'S STANDARD TRIM ACCESSORIES, INCLUDING BUT NOT LIMITED TO CORNER BEAD, L TYPE EDGES, TRIM BEDS, U TYPE EDGE TRIM BEAD, SPECIAL L CURVED TYPE EDGE TRIM BEAD AND ONE PIECE CONTROL JOINT BEAD.
 6. PROVIDE CONTROL JOINTS IN WALLS AT NOT MORE THAN 30' SPACING AND IN SOFFITS NOT EXCEEDING 50' SPACING, OR AS INDICATED ON THE DRAWINGS.
 7. APPLY TREATMENT AT GYPSUM BOARD JOINTS, INCLUDING JOINT TAPE AT ALL JOINTS BETWEEN GYPSUM BOARDS AND MIN. 2 COATS GYPSUM JOINT COMPOUND (OMIT THIRD COAT AND SANDING ON CONCEALED DRYWALL WORK)
 8. EXTERIOR GYPSUM SHEATHING - 5/8" DENS-GLOSS GLASS PER ASTM C79.
 9. USE METAL CORNER BEADS ON ALL GYPSUM BOARD EXTERIOR CORNERS.
 10. INSTALL METAL TRIM ON ALL GYPSUM BOARD EDGES ABUTTING OTHER MATERIALS OR STOPPING SHORT OF OTHER MATERIALS TO FORM A REVEAL OR RECESS.

- SECTION 10 - SPECIALTIES**
SECTION 10.14.00 - EXTERIOR SIGNS
1. CVS/PHARMACY HAS ENTERED INTO A NATIONAL ACCOUNT AGREEMENT WITH THE MANUFACTURERS BELOW FOR FURNISHING THE PYLON SIGN, MONUMENT SIGN, DRIVE-THRU SIGNS, AND BUILDING SIGNS AS SPECIFIED IN THIS SECTION. COMPLETE INSTALLATION SHALL BE BY THE CONTRACTOR. FOR PRICING QUOTATIONS, PLACING ORDERS, AND FURTHER INFORMATION, PLEASE CALL THE APPROPRIATE MANUFACTURER FOR THE AREA THE STORE IS LOCATED IN.
 - ATLAS SIGNS AT (561) 863-6659, CONTACT ANNETTE SOUTHERN AREAS: AL, IN, KY, MI, MS, OH, TN, WV CHANDLER AT (214) 902-2000 EXT. 6528, CONTACT WALTER FINNINGER OR DOUG HALLAM AREAS: AR, KS, LA, MO, OK, TX COAST SIGNS AT (714) 915-3141, CONTACT ERNIE RIVAS AREAS: CENTRAL CA FLOURESCO LIGHTING & SIGNS AT (909) 647-8588, CONTACT RON HILL AREAS: AZ, SOUTHERN CA, NV ICON IDENTITY SOLUTIONS AT (727) 373-2033, CONTACT JON ALLEN AREAS: NORTHERN CA, CO, HI, IA, ID, IL, MN, MI, MO, ND, NE, NM, OR, SD, UT, WA, WI, WY IMAGE ONE AT (215) 826-0880, CONTACT PAUL SILVER AREAS: NJ POYANT SIGNS AT (508) 995-1777 EXT. 133, CONTACT NATALIA PELLETER AREAS: CT, MA, ME, NH, RI, VT SERVICE NEON AT (703) 354-3000, CONTACT RICK PEPPER AREAS: DC, DE, MD, SC, VA SIGN ENGINEERING AT (787) 790-1330, CONTACT IMA RIOS AT EXT. 235 AREAS: PR ULTIMATE SIGNS AT (516) 481-0800, CONTACT ARLINE MELI AREAS: NY ONLY WALTON SIGNS AT (210) 906-5986, CONTACT MARISOL JUAREZ AREAS: AK, NORTHERN FL, GA
 2. CONTRACTOR SHALL ENTER INTO A CONTRACT WITH THE SIGN COMPANY CHOSEN BY THE OWNER FOR INSTALLATION OF PYLON SIGN, DRIVE-THRU SIGNS, AND BUILDING SIGNS.
 3. SIGN TYPES AND ACCESSORIES WHERE INDICATED OR REQUIRED, USING MOUNTING METHODS COMPLYING WITH MANUFACTURER'S WRITTEN INSTRUCTIONS.

- SECTION 10.21.13 - TOILET COMPARTMENTS**
1. MANUFACTURER: GLOBAL PARTITIONS.
 2. TYPE: STEEL SHEETS WITH POWDER-COATED FINISH: MILL-PHOSPHATIZED, CORROSION RESISTANT STEEL SHEET; STRETCHER-LEVELED FLATNESS, ASTM A 591/A 591M, CLASS C, OR ASTM A 653/A 653; WITH MFR STANDARD POWDER-COATED FINISH. COLOR-GREY 2125.
 3. COMPARTMENT STYLE: OVERHEAD BRACED AND FLOOR ANCHORED. URINAL SCREEN: FLOOR ANCHORED.
 4. DOORS: MIN 24" WIDE FOR STANDARD TOILET COMPARTMENTS AND 32" CLEAR OPENING COMPARTMENTS FOR ACCESSIBLE STALLS.
 5. DOOR HARDWARE: CLEAR ANODIC ALUMINUM OR CAST-ZINC ALLOY. PROVIDE UNITS THAT COMPLY WITH ACCESSIBILITY REQUIREMENTS OF AUTHORITIES HAVING JURISDICTION. PROVIDE U-SHAPED DOOR PULL HARDWARE ON BOTH OUT-SWING AND IN-SWING SIDE OF THE ACCESSIBLE COMPARTMENT DOOR. MOUNT ALL OPERATING HARDWARE NO HIGHER THAN 40" AFF.
 6. SELF-CLOSING HINGES: ADJUSTABLE TO HOLD DOOR OPEN AT ANY ANGLE UP TO 90 DEGREES.
 7. LATCHES: CONCEALED WITH DESIGNED FOR EMERGENCY ACCESS AND ADA LEVER HANDLE.
 8. ACCESSORIES: PROVIDE BRACKETS, PLASTER SHOES, BRACING, AND OTHER COMPONENTS REQUIRED FOR A COMPLETE INSTALLATION.
 9. CONTRACTOR TO PROVIDE SHOP DRAWINGS FOR REVIEW/APPROVAL.

- SECTION 09.65.19 - LUXURY VINYL TILE FLOORING**
1. GC TO PROVIDE LUXURY VINYL TILE AS SCHEDULED PER DRAWINGS. INSTALL PER MFR REQUIREMENTS. SEE ROOM FINISH SCHEDULE FOR SPECIFIC SIZE/FINISH MATERIAL SPEC.
 2. RUBBER WALL BASE AS SCHEDULED. INSTALL PER MFR REQUIREMENTS.
 3. GC TO CONDUCT RH MOISTURE TEST ON NEW AND EXISTING LUXURY VINYL TILE.

- SECTIONS 09.68.13 - TILE CARPETING**
1. CARPET TILE SHALL BE INTERFACE GRAPHLAR TILE - NEEDLEPUNCH CONSTRUCTION. INSTALL IN 1/4 TURN PATTERN.
 2. FOAM BACKER CARPET TILE SHALL BE INTERFACE CUSHIONBAC PLUS TILE - TUFTED TEXTURED LOOP
 3. INSTALL ALL CARPET MATERIALS PER MFR REQUIREMENTS

- SECTION 09.71.00 - WATERPROOF WALL PANELS**
1. PROVIDE WATERPROOF WALL PANELS WHERE SHOWN ON THE DRAWINGS AND AS NEEDED FOR COMPLETE AND PROPER INSTALLATION.
 2. MANUFACTURER: MARLITE: 202 HARGER STREET, DOVER, OH 44622, ASD TEL: (330) 343-6621, FAX: (330) 343-7296

- SECTION 09.72.00 - WALL COVERINGS**
1. INSTALL ALL WALL COVERINGS AS SHOWN ON DRAWINGS AND AS NEEDED FOR COMPLETE AND PROPER INSTALLATION PER MFR REQUIREMENTS
 2. SEE FINISH SCHEDULE FOR MATERIAL/MANUFACTURER INFORMATION
- SECTION 09.90.00 - PAINTING**
1. PAINT ALL WALL SURFACES, DOOR FRAMES, BULKHEADS AND CEILINGS IN ROOMS WHERE INDICATED ON ROOM FINISH SCHEDULE. PAINT BEHIND ALL MOVEABLE ITEMS ADJACENT TO WALLS RECEIVING PAINT AND RELOCATE ITEMS.
 2. PROVIDE ALL LABOR AND MATERIALS AS NECESSARY FOR FINISHES AS INDICATED IN THESE

- SECTION 12.24.00 - ROLLER WINDOW SHADES**
1. ENVIRONMENTAL LIMITATIONS: DO NOT INSTALL ROLLER SHADES UNTIL CONSTRUCTION AND FINISH WORK IN SPACES, INCLUDING PAINTING, IS COMPLETE AND DRY AND AMBIENT TEMPERATURE AND HUMIDITY CONDITIONS ARE MAINTAINED AT THE LEVELS INDICATED FOR PROJECT WHEN OCCUPIED FOR ITS INTENDED USE.
 2. FIELD MEASUREMENTS: WHERE ROLLER SHADES ARE INDICATED TO FIT TO OTHER CONSTRUCTION, VERIFY DIMENSIONS OF OTHER CONSTRUCTION BY FIELD MEASUREMENTS BEFORE FABRICATION AND INDICATE MEASUREMENTS ON SHOP DRAWINGS. ALLOW CLEARANCES FOR OPERATING HARDWARE OF OPERABLE GLAZED UNITS THROUGH ENTIRE OPERATING RANGE. NOTIFY ARCHITECT OF INSTALLATION CONDITIONS THAT VARY FROM DRAWINGS. COORDINATE FABRICATION SCHEDULE WITH CONSTRUCTION PROGRESS TO AVOID DELAYING THE WORK.
 3. BASIS OF DESIGN: ROLL-A-SHADE.
 - A. RAS-1: MOTORIZED INTERIOR SUNSCREEN ROLLER SHADES AT RETAIL SECTION.
 - B. RAS-2: MANUAL INTERIOR SUNSCREEN ROLLER SHADES AT VESTIBULE.
 4. ACCESSORIES
 - A. SUN SENSOR - ONE PER ELEVATION. SUN SENSOR TO BE PLUG-IN PROVIDED WITH NEMA PLUG. BATTERY OPERATED NOT PERMITTED.
 - B. 3 CHANNEL WALL SWITCH - SEE PLANS FOR LOCATION. WALL SWITCH TO BE PLUG-IN PROVIDED WITH NEMA PLUG. BATTERY OPERATED NOT PERMITTED.
 - C. 5 CHANNEL WIRELESS REMOTE (OPTIONAL).
 5. DO NOT BEGIN INSTALLATION UNTIL SUBSTRATES HAVE BEEN PROPERLY PREPARED. IF SUBSTRATE PREPARATION IS THE RESPONSIBILITY OF ANOTHER INSTALLER, NOTIFY ARCHITECT/CONTRACTOR OF ANY UNSATISFACTORY PREPARATION BEFORE PROCEEDING.
 6. INSTALL ROLLER SHADES LEVEL, PLUMB, AND TRUE. ALLOW PROPER CLEARANCES FOR WINDOW OPERATION HARDWARE.
 7. CONTRACTOR SHALL PROVIDE POWER PANELS AND CIRCUITS OF SUFFICIENT SIZE TO ACCOMMODATE ROLLER SHADE MANUFACTURER'S REQUIREMENTS.
 8. CONTRACTOR SHALL COORDINATE LOCATION OF POWER SUPPLY FOR ROLLER SHADES WITH MANUFACTURER.
 9. CONTRACTOR SHALL SUPPLY ONE (1) SURFACE MOUNTED DUPLEX AT UNDERSIDE OF SOFFIT FOR EACH ELEVATION WITHIN 6' OF WINDOW SIDES.
 10. ADJUST AND BALANCE ROLLER SHADES TO OPERATE SMOOTHLY, EASILY AND FREE FROM BINDING.
 11. CLEAN ROLLER SHADE SURFACES AFTER INSTALLATION, ACCORDING TO MANUFACTURER'S WRITTEN INSTRUCTIONS.
 12. GROUND INSTALLER TO TRAIN OWNER'S MAINTENANCE PERSONNEL TO ADJUST, OPERATE AND MAINTAIN ROLLER SHADE SYSTEMS.
 13. H. PROTECT INSTALLED PRODUCTS UNTIL COMPLETION OF PROJECT.
 14. I. TOUCH-UP REPAIR AND/OR REPLACE ANY DAMAGED PRODUCTS BEFORE SUBSTANTIAL COMPLETION.

- DIVISION 11 - EQUIPMENT - NOT USED**
- DIVISION 12 - FURNISHINGS**
- SECTION 12.24.00 - ROLLER WINDOW SHADES**
1. CVS/PHARMACY HAS ENTERED INTO A NATIONAL ACCOUNT AGREEMENT WITH THE MANUFACTURERS LISTED BELOW TO FURNISH AND INSTALL THE FIRE ALARM SYSTEM SPECIFIED IN THIS SECTION. COMPLETE INSTALLATION SHALL BE BY THE NATIONAL ACCOUNT SUPPLIER. THE GENERAL CONTRACTOR IS RESPONSIBLE FOR CONTACTING THE MANUFACTURER FOR PRICING QUOTATIONS, PLACING ORDERS, AND FURTHER INFORMATION, PLEASE CALL THE APPROPRIATE MANUFACTURER FOR THE AREA THE STORE IS LOCATED IN.
 - BASS SECURITY AT (888) 774-3400 AT EXT. 1950 AREAS: IL, IN, MI, OH
 - AFA PROTECTIVE SYSTEM AT (781) 848-6200 AREAS: AL, FL, GA, MA, ME, NC, NH, NY, PA, RI, SC, VT
 - TECHNOQUALITY AT (646) 723-4410 AREAS: CT, DC, DE, MD
 - INTEGRATED SECURITY SOLUTIONS AT (800) 505-0868 AREA: NJ
 - VECTOR SECURITY AT (703) 468 8100 AT EXT. 51126 AREA: AK, CA, CO, HI, ID, IL, IN, KY, MI, MT, NM, NV, OH, OR, PR, TN, UT, VA, WA, WI, WY
 - ADVANCED PROJECT SOLUTIONS, LLC AT (608) 204-8640 AREA: AR, IA, KS, MO, MS, ND, NE, OK, SD, WI
 2. GENERAL: NONCODED, ZONED SYSTEM WITH MANUAL AND AUTOMATIC ALARM INITIATION; AND HARD-WIRED FOR SIGNAL TRANSMISSION, USING SEPARATE INDIVIDUAL CIRCUITS FOR EACH ZONE OF ALARM INITIATION AND NOTIFICATION APPLIANCES.
 3. INSTALLER QUALIFICATIONS: AN EXPERIENCED INSTALLER WHO IS AN AUTHORIZED REPRESENTATIVE OF THE FACP MANUFACTURER FOR BOTH INSTALLATION AND MAINTENANCE OF UNITS REQUIRED FOR THIS PROJECT.
 4. MANUFACTURER QUALIFICATIONS: A FIRM EXPERIENCED IN MANUFACTURING SYSTEMS SIMILAR TO THOSE INDICATED FOR THIS PROJECT AND WITH A RECORD OF SUCCESSFUL IN-SERVICE PERFORMANCE.
 5. COMPLIANCE WITH LOCAL REQUIREMENTS: COMPLY WITH APPLICABLE BUILDING CODE, LOCAL ORDINANCES AND REGULATIONS, AND REQUIREMENTS OF AUTHORITIES HAVING JURISDICTION.
 6. COMPLY WITH NFPA 72.
 7. FURNISH EXTRA MATERIALS DESCRIBED BELOW THAT MATCH PRODUCTS INSTALLED AND THAT ARE PACKAGED WITH PROTECTIVE COVERING FOR STORAGE AND IDENTIFIED WITH LABELS DESCRIBING CONTENTS.
 - A. SMOKE DETECTORS, FIRE DETECTORS, AND FLAME DETECTORS: QUANTITY EQUAL TO 10 PERCENT OF AMOUNT OF EACH TYPE INSTALLED, BUT NOT LESS THAN ONE UNIT OF EACH TYPE.
 - B. DETECTOR BASES: QUANTITY EQUAL TO 2 PERCENT OF AMOUNT OF EACH TYPE INSTALLED, BUT NOT LESS THAN ONE UNIT OF EACH TYPE.
 - C. KEYS AND TOOLS: ONE EXTRA SET FOR ACCESS TO LOCKED AND TAMPERPROOFED COMPONENTS.
 8. EQUIPMENT INSTALLATION:
 - A. CONNECT THE FACP WITH A CIRCUIT BREAKER WITH LOOKABLE HANDLE OR COVER.
 - B. MANUAL PULL STATIONS: MOUNT SEMIFLUSH IN RECESSED BACK BOXES.
 - C. WATER-FLOW DETECTORS AND VALVE SUPERVISORY SWITCHES: CONNECT FOR EACH SPRINKLER VALVE STATION REQUIRED TO BE SUPERVISED. SUPPLIED AND INSTALLED BY SPRINKLER CONTRACTOR.

- SECTION 12.30.00 - STEEL GONDOLAS (IF NO STORE SET-UP)**
1. CVS/PHARMACY HAS ENTERED INTO A NATIONAL ACCOUNT AGREEMENT WITH THE MANUFACTURERS BELOW FOR FURNISHING THE STEEL GONDOLAS IN THIS SECTION. COMPLETE INSTALLATION SHALL BE BY THE CONTRACTOR. FOR PRICING QUOTATIONS, PLACING ORDERS, AND FURTHER INFORMATION, PLEASE CALL THE APPROPRIATE MANUFACTURER FOR THE AREA THE STORE IS LOCATED IN.
 - LOZER STORE FIXTURE INC. AT (574) 825-9561. AREAS: AL, AR, IA, IL, IN, KY, LA, MD, MI, MN, MO, MS, OH, SD, TN, VA, WI, WV MADIX STORE FIXTURES INC. AT (203) 975-7403. AREAS: AK, AR, AZ, CA, HI, IA, ID, LA, MN, MT, ND, NM, NV, SD, TN, WI
 2. INSTALLER QUALIFICATIONS: ENGAGE AN EXPERIENCED INSTALLER WHO IS AN AUTHORIZED REPRESENTATIVE OF THE MANUFACTURER FOR INSTALLATION OF THE TYPE OF STEEL GONDOLAS WALLS REQUIRED FOR THIS PROJECT.
 3. FIELD MEASUREMENTS: VERIFY FIELD MEASUREMENTS BEFORE FABRICATION TO ENSURE PROPER FITTINGS. COORDINATE FABRICATION SCHEDULE WITH CONSTRUCTION PROGRESS TO AVOID DELAYING THE WORK.
 4. PROVIDE PANELS, RETAINERS, CHANNEL AND TUBE STYLE LEGS, WEDGE LOCK, SWIVEL BARS, SPACERS AND HARDWARE AS STANDARD WITH THE MANUFACTURER FOR THE OWNER FOR A COMPLETE INSTALLATION.
 5. INSTALL STEEL GONDOLAS IN ACCORDANCE WITH MANUFACTURER'S INSTALLATION INSTRUCTIONS. LEVEL, PLUMB, TRUE, AND ALIGNED WITH ADJACENT MATERIALS. USE CONSTRUCTION SHIMS WHERE NECESSARY FOR ALIGNMENT.
 6. INSTALL STEEL GONDOLAS PER FINAL MERCHANT SPEC PLAN.
 7. INSTALL TO TOLERANCES AS REQUIRED BY THE MANUFACTURER.
 8. COORDINATE STEEL GONDOLAS WITH OTHER SYSTEMS IN OR ADJACENT TO IT. PROVIDE CUTOUTS FOR ELECTRICAL ITEMS AND PENETRATE WALL SYSTEM. REPLACE VISUAL DISPLAY WALL THAT IS DAMAGED OR DOES NOT COMPLY WITH REQUIREMENTS. WALL SYSTEM MAY BE REPAIRED OR REFINISHED IF WORK COMPLES WITH REQUIREMENTS AND SHOWS NO EVIDENCE OF REPAIR OR REFINISHING. ADJUST JOINTS FOR UNIFORM APPEARANCE. CLEAN STEEL GONDOLAS ON EXPOSED AND SEMIEXPOSED SURFACES. TOUCH UP FACTORY-APPLIED FINISHES TO RESTORE DAMAGED OR SOILED AREAS.

- DIVISION 12 - SPECIAL CONSTRUCTION - NOT USED**
- SECTION 10.14.00 - FIRE PROTECTION**
1. CVS/PHARMACY HAS ENTERED INTO A NATIONAL ACCOUNT AGREEMENT WITH THE MANUFACTURERS LISTED BELOW TO FURNISH AND INSTALL THE FIRE ALARM SYSTEM SPECIFIED IN THIS SECTION. COMPLETE INSTALLATION SHALL BE BY THE NATIONAL ACCOUNT SUPPLIER. THE GENERAL CONTRACTOR IS RESPONSIBLE FOR CONTACTING THE MANUFACTURER FOR PRICING QUOTATIONS, PLACING ORDERS, AND FURTHER INFORMATION, PLEASE CALL THE APPROPRIATE MANUFACTURER FOR THE AREA THE STORE IS LOCATED IN.
 - BASS SECURITY AT (888) 774-3400 AT EXT. 1950 AREAS: IL, IN, MI, OH
 - AFA PROTECTIVE SYSTEM AT (781) 848-6200 AREAS: AL, FL, GA, MA, ME, NC, NH, NY, PA, RI, SC, VT
 - TECHNOQUALITY AT (646) 723-4410 AREAS: CT, DC, DE, MD
 - INTEGRATED SECURITY SOLUTIONS AT (800) 505-0868 AREA: NJ
 - VECTOR SECURITY AT (703) 468 8100 AT EXT. 51126 AREA: AK, CA, CO, HI, ID, IL, IN, KY, MI, MT, NM, NV, OH, OR, PR, TN, UT, VA, WA, WI, WY
 - ADVANCED PROJECT SOLUTIONS, LLC AT (608) 204-8640 AREA: AR, IA, KS, MO, MS, ND, NE, OK, SD, WI
 2. GENERAL: NONCODED, ZONED SYSTEM WITH MANUAL AND AUTOMATIC ALARM INITIATION; AND HARD-WIRED FOR SIGNAL TRANSMISSION, USING SEPARATE INDIVIDUAL CIRCUITS FOR EACH ZONE OF ALARM INITIATION AND NOTIFICATION APPLIANCES.
 3. INSTALLER QUALIFICATIONS: AN EXPERIENCED INSTALLER WHO IS AN AUTHORIZED REPRESENTATIVE OF THE FACP MANUFACTURER FOR BOTH INSTALLATION AND MAINTENANCE OF UNITS REQUIRED FOR THIS PROJECT.
 4. MANUFACTURER QUALIFICATIONS: A FIRM EXPERIENCED IN MANUFACTURING SYSTEMS SIMILAR TO THOSE INDICATED FOR THIS PROJECT AND WITH A RECORD OF SUCCESSFUL IN-SERVICE PERFORMANCE.
 5. COMPLIANCE WITH LOCAL REQUIREMENTS: COMPLY WITH APPLICABLE BUILDING CODE, LOCAL ORDINANCES AND REGULATIONS, AND REQUIREMENTS OF AUTHORITIES HAVING JURISDICTION.
 6. COMPLY WITH NFPA 72.
 7. FURNISH EXTRA MATERIALS DESCRIBED BELOW THAT MATCH PRODUCTS INSTALLED AND THAT ARE PACKAGED WITH PROTECTIVE COVERING FOR STORAGE AND IDENTIFIED WITH LABELS DESCRIBING CONTENTS.
 - A. SMOKE DETECTORS, FIRE DETECTORS, AND FLAME DETECTORS: QUANTITY EQUAL TO 10 PERCENT OF AMOUNT OF EACH TYPE INSTALLED, BUT NOT LESS THAN ONE UNIT OF EACH TYPE.
 - B. DETECTOR BASES: QUANTITY EQUAL TO 2 PERCENT OF AMOUNT OF EACH TYPE INSTALLED, BUT NOT LESS THAN ONE UNIT OF EACH TYPE.
 - C. KEYS AND TOOLS: ONE EXTRA SET FOR ACCESS TO LOCKED AND TAMPERPROOFED COMPONENTS.
 8. EQUIPMENT INSTALLATION:
 - A. CONNECT THE FACP WITH A CIRCUIT BREAKER WITH LOOKABLE HANDLE OR COVER.
 - B. MANUAL PULL STATIONS: MOUNT SEMIFLUSH IN RECESSED BACK BOXES.
 - C. WATER-FLOW DETECTORS AND VALVE SUPERVISORY SWITCHES: CONNECT FOR EACH SPRINKLER VALVE STATION REQUIRED TO BE SUPERVISED. SUPPLIED AND INSTALLED BY SPRINKLER CONTRACTOR.

- SECTION 12.24.00 - ROLLER WINDOW SHADES**
1. ENVIRONMENTAL LIMITATIONS: DO NOT INSTALL ROLLER SHADES UNTIL CONSTRUCTION AND FINISH WORK IN SPACES, INCLUDING PAINTING, IS COMPLETE AND DRY AND AMBIENT TEMPERATURE AND HUMIDITY CONDITIONS ARE MAINTAINED AT THE LEVELS INDICATED FOR PROJECT WHEN OCCUPIED FOR ITS INTENDED USE.
 2. FIELD MEASUREMENTS: WHERE ROLLER SHADES ARE INDICATED TO FIT TO OTHER CONSTRUCTION, VERIFY DIMENSIONS OF OTHER CONSTRUCTION BY FIELD MEASUREMENTS BEFORE FABRICATION AND INDICATE MEASUREMENTS ON SHOP DRAWINGS. ALLOW CLEARANCES FOR OPERATING HARDWARE OF OPERABLE GLAZED UNITS THROUGH ENTIRE OPERATING RANGE. NOTIFY ARCHITECT OF INSTALLATION CONDITIONS THAT VARY FROM DRAWINGS. COORDINATE FABRICATION SCHEDULE WITH CONSTRUCTION PROGRESS TO AVOID DELAYING THE WORK.
 3. BASIS OF DESIGN: ROLL-A-SHADE.
 - A. RAS-1: MOTORIZED INTERIOR SUNSCREEN ROLLER SHADES AT RETAIL SECTION.
 - B. RAS-2: MANUAL INTERIOR SUNSCREEN ROLLER SHADES AT VESTIBULE.
 4. ACCESSORIES
 - A. SUN SENSOR - ONE PER ELEVATION. SUN SENSOR TO BE PLUG-IN PROVIDED WITH NEMA PLUG. BATTERY OPERATED NOT PERMITTED.
 - B. 3 CHANNEL WALL SWITCH - SEE PLANS FOR LOCATION. WALL SWITCH TO BE PLUG-IN PROVIDED WITH NEMA PLUG. BATTERY OPERATED NOT PERMITTED.
 - C. 5 CHANNEL WIRELESS REMOTE (OPTIONAL).
 5. DO NOT BEGIN INSTALLATION UNTIL SUBSTRATES HAVE BEEN PROPERLY PREPARED. IF SUBSTRATE PREPARATION IS THE RESPONSIBILITY OF ANOTHER INSTALLER, NOTIFY ARCHITECT/CONTRACTOR OF ANY UNSATISFACTORY PREPARATION BEFORE PROCEEDING.
 6. INSTALL ROLLER SHADES LEVEL, PLUMB, AND TRUE. ALLOW PROPER CLEARANCES FOR WINDOW OPERATION HARDWARE.
 7. CONTRACTOR SHALL PROVIDE POWER PANELS AND CIRCUITS OF SUFFICIENT SIZE TO ACCOMMODATE ROLLER SHADE MANUFACTURER'S REQUIREMENTS.
 8. CONTRACTOR SHALL COORDINATE LOCATION OF POWER SUPPLY FOR ROLLER SHADES WITH MANUFACTURER.
 9. CONTRACTOR SHALL SUPPLY ONE (1) SURFACE MOUNTED DUPLEX AT UNDERSIDE OF SOFFIT FOR EACH ELEVATION WITHIN 6' OF WINDOW SIDES.
 10. ADJUST AND BALANCE ROLLER SHADES TO OPERATE SMOOTHLY, EASILY AND FREE FROM BINDING.
 11. CLEAN ROLLER SHADE SURFACES AFTER INSTALLATION, ACCORDING TO MANUFACTURER'S WRITTEN INSTRUCTIONS.
 12. GROUND INSTALLER TO TRAIN OWNER'S MAINTENANCE PERSONNEL TO ADJUST, OPERATE AND MAINTAIN ROLLER SHADE SYSTEMS.
 13. H. PROTECT INSTALLED PRODUCTS UNTIL COMPLETION OF PROJECT.
 14. I. TOUCH-UP REPAIR AND/OR REPLACE ANY DAMAGED PRODUCTS BEFORE SUBSTANTIAL COMPLETION.

- DIVISION 11 - EQUIPMENT - NOT USED**
- DIVISION 12 - FURNISHINGS**
- SECTION 12.24.00 - ROLLER WINDOW SHADES**
1. CVS/PHARMACY HAS ENTERED INTO A NATIONAL ACCOUNT AGREEMENT WITH THE MANUFACTURERS LISTED BELOW TO FURNISH AND INSTALL THE FIRE ALARM SYSTEM SPECIFIED IN THIS SECTION. COMPLETE INSTALLATION SHALL BE BY THE NATIONAL ACCOUNT SUPPLIER. THE GENERAL CONTRACTOR IS RESPONSIBLE FOR CONTACTING THE MANUFACTURER FOR PRICING QUOTATIONS, PLACING ORDERS, AND FURTHER INFORMATION, PLEASE CALL THE APPROPRIATE MANUFACTURER FOR THE AREA THE STORE IS LOCATED IN.
 - BASS SECURITY AT (888) 774-3400 AT EXT. 1950 AREAS: IL, IN, MI, OH
 - AFA PROTECTIVE SYSTEM AT (781) 848-6200 AREAS: AL, FL, GA, MA, ME, NC, NH, NY, PA, RI, SC, VT
 - TECHNOQUALITY AT (646) 723-4410 AREAS: CT, DC, DE, MD
 - INTEGRATED SECURITY SOLUTIONS AT (800) 505-0868 AREA: NJ
 - VECTOR SECURITY AT (703) 468 8100 AT EXT. 51126 AREA: AK, CA, CO, HI, ID, IL, IN, KY, MI, MT, NM, NV, OH, OR, PR, TN, UT, VA, WA, WI, WY
 - ADVANCED PROJECT SOLUTIONS, LLC AT (608) 204-8640 AREA: AR, IA, KS, MO, MS, ND, NE, OK, SD, WI
 2. GENERAL: NONCODED, ZONED SYSTEM WITH MANUAL AND AUTOMATIC ALARM INITIATION; AND HARD-WIRED FOR SIGNAL TRANSMISSION, USING SEPARATE INDIVIDUAL CIRCUITS FOR EACH ZONE OF ALARM INITIATION AND NOTIFICATION APPLIANCES.
 3. INSTALLER QUALIFICATIONS: AN EXPERIENCED INSTALLER WHO IS AN AUTHORIZED REPRESENTATIVE OF THE FACP MANUFACTURER FOR BOTH INSTALLATION AND MAINTENANCE OF UNITS REQUIRED FOR THIS PROJECT.
 4. MANUFACTURER QUALIFICATIONS: A FIRM EXPERIENCED IN MANUFACTURING SYSTEMS SIMILAR TO THOSE INDICATED FOR THIS PROJECT AND WITH A RECORD OF SUCCESSFUL IN-SERVICE PERFORMANCE.
 5. COMPLIANCE WITH LOCAL REQUIREMENTS: COMPLY WITH APPLICABLE BUILDING CODE, LOCAL ORDINANCES AND REGULATIONS, AND REQUIREMENTS OF AUTHORITIES HAVING JURISDICTION.
 6. COMPLY WITH NFPA 72.
 7. FURNISH EXTRA MATERIALS DESCRIBED BELOW THAT MATCH PRODUCTS INSTALLED AND THAT ARE PACKAGED WITH PROTECTIVE COVERING FOR STORAGE AND IDENTIFIED WITH LABELS DESCRIBING CONTENTS.
 - A. SMOKE DETECTORS, FIRE DETECTORS, AND FLAME DETECTORS: QUANTITY EQUAL TO 10 PERCENT OF AMOUNT OF EACH TYPE INSTALLED, BUT NOT LESS THAN ONE UNIT OF EACH TYPE.
 - B. DETECTOR BASES: QUANTITY EQUAL TO 2 PERCENT OF AMOUNT OF EACH TYPE INSTALLED, BUT NOT LESS THAN ONE UNIT OF EACH TYPE.
 - C. KEYS AND TOOLS: ONE EXTRA SET FOR ACCESS TO LOCKED AND TAMPERPROOFED COMPONENTS.
 8. EQUIPMENT INSTALLATION:
 - A. CONNECT THE FACP WITH A CIRCUIT BREAKER WITH LOOKABLE HANDLE OR COVER.
 - B. MANUAL PULL STATIONS: MOUNT SEMIFLUSH IN RECESSED BACK BOXES.
 - C. WATER-FLOW DETECTORS AND VALVE SUPERVISORY SWITCHES: CONNECT FOR EACH SPRINKLER VALVE STATION REQUIRED TO BE SUPERVISED. SUPPLIED AND INSTALLED BY SPRINKLER CONTRACTOR.

- DIVISION 12 - SPECIAL CONSTRUCTION - NOT USED**
- SECTION 10.14.00 - FIRE PROTECTION**
1. CVS/PHARMACY HAS ENTERED INTO A NATIONAL ACCOUNT AGREEMENT WITH THE MANUFACTURERS LISTED BELOW TO FURNISH AND INSTALL THE FIRE ALARM SYSTEM SPECIFIED IN THIS SECTION. COMPLETE INSTALLATION SHALL BE BY THE NATIONAL ACCOUNT SUPPLIER. THE GENERAL CONTRACTOR IS RESPONSIBLE FOR CONTACTING THE MANUFACTURER FOR PRICING QUOTATIONS, PLACING ORDERS, AND FURTHER INFORMATION, PLEASE CALL THE APPROPRIATE MANUFACTURER FOR THE AREA THE STORE IS LOCATED IN.
 - BASS SECURITY AT (888) 774-3400 AT EXT. 1950 AREAS: IL, IN, MI, OH
 - AFA PROTECTIVE SYSTEM AT (781) 848-6200 AREAS: AL, FL, GA, MA, ME, NC, NH, NY, PA, RI, SC, VT
 - TECHNOQUALITY AT (646) 723-4410 AREAS: CT, DC, DE, MD
 - INTEGRATED SECURITY SOLUTIONS AT (800) 505-0868 AREA: NJ
 - VECTOR SECURITY AT (703) 468 8100 AT EXT. 51126 AREA: AK, CA, CO, HI, ID, IL, IN, KY, MI, MT, NM, NV, OH, OR, PR, TN, UT, VA, WA, WI, WY
 - ADVANCED PROJECT SOLUTIONS, LLC AT (608) 204-8640 AREA: AR, IA, KS, MO, MS, ND, NE, OK, SD, WI
 2. GENERAL: NONCODED, ZONED SYSTEM WITH MANUAL AND AUTOMATIC ALARM INITIATION; AND HARD-WIRED FOR SIGNAL TRANSMISSION, USING SEPARATE INDIVIDUAL CIRCUITS FOR EACH ZONE OF ALARM INITIATION AND NOTIFICATION APPLIANCES.
 3. INSTALLER QUALIFICATIONS: AN EXPERIENCED INSTALLER WHO IS AN AUTHORIZED REPRESENTATIVE OF THE FACP MANUFACTURER FOR BOTH INSTALLATION AND MAINTENANCE OF UNITS REQUIRED FOR THIS PROJECT.
 4. MANUFACTURER QUALIFICATIONS: A FIRM EXPERIENCED IN MANUFACTURING SYSTEMS SIMILAR TO THOSE INDICATED FOR THIS PROJECT AND WITH A RECORD OF SUCCESSFUL IN-SERVICE PERFORMANCE.
 5. COMPLIANCE WITH LOCAL REQUIREMENTS: COMPLY WITH APPLICABLE BUILDING CODE, LOCAL ORDINANCES AND REGULATIONS, AND REQUIREMENTS OF AUTHORITIES HAVING JURISDICTION.
 6. COMPLY WITH NFPA 72.
 7. FURNISH EXTRA MATERIALS DESCRIBED BELOW THAT MATCH PRODUCTS INSTALLED AND THAT ARE PACKAGED WITH PROTECTIVE COVERING FOR STORAGE AND IDENTIFIED WITH LABELS DESCRIBING CONTENTS.
 - A. SMOKE DETECTORS, FIRE DETECTORS, AND FLAME DETECTORS: QUANTITY EQUAL TO 10 PERCENT OF AMOUNT OF EACH TYPE INSTALLED, BUT NOT LESS THAN ONE UNIT OF EACH TYPE.
 - B. DETECTOR BASES: QUANTITY EQUAL TO 2 PERCENT OF AMOUNT OF EACH TYPE INSTALLED, BUT NOT LESS THAN ONE UNIT OF EACH TYPE.
 - C. KEYS AND TOOLS: ONE EXTRA SET FOR ACCESS TO LOCKED AND TAMPERPROOFED COMPONENTS.
 8. EQUIPMENT INSTALLATION:
 - A. CONNECT THE FACP WITH A CIRCUIT BREAKER WITH LOOKABLE HANDLE OR COVER.
 - B. MANUAL PULL STATIONS: MOUNT SEMIFLUSH IN RECESSED BACK BOXES.
 - C. WATER-FLOW DETECTORS AND VALVE SUPERVISORY SWITCHES: CONNECT FOR EACH SPRINKLER VALVE STATION REQUIRED TO BE SUPERVISED. SUPPLIED AND INSTALLED BY SPRINKLER CONTRACTOR.

- DIVISION 12 - SPECIAL CONSTRUCTION - NOT USED**
- SECTION 10.14.00 - FIRE PROTECTION**
1. CVS/PHARMACY HAS ENTERED INTO A NATIONAL ACCOUNT AGREEMENT WITH THE MANUFACTURERS LISTED BELOW TO FURNISH AND INSTALL THE FIRE ALARM SYSTEM SPECIFIED IN THIS SECTION. COMPLETE INSTALLATION SHALL BE BY THE NATIONAL ACCOUNT SUPPLIER. THE GENERAL CONTRACTOR IS RESPONSIBLE FOR CONTACTING THE MANUFACTURER FOR PRICING QUOTATIONS, PLACING ORDERS, AND FURTHER INFORMATION, PLEASE CALL THE APPROPRIATE MANUFACTURER FOR THE AREA THE STORE IS LOCATED IN.
 - BASS SECURITY AT (888) 774-3400 AT EXT. 1950 AREAS: IL, IN, MI, OH
 - AFA PROTECTIVE SYSTEM AT (781) 848-6200 AREAS: AL, FL, GA, MA, ME, NC, NH, NY, PA, RI, SC, VT
 - TECHNOQUALITY AT (646) 723-4410 AREAS: CT, DC, DE, MD
 - INTEGRATED SECURITY SOLUTIONS AT (800) 505-0868 AREA: NJ
 - VECTOR SECURITY AT (703) 468 8100 AT EXT. 51126 AREA: AK, CA, CO, HI, ID, IL, IN, KY, MI, MT, NM, NV, OH, OR, PR, TN, UT, VA, WA, WI, WY
 - ADVANCED PROJECT SOLUTIONS, LLC AT (608) 204-8640 AREA: AR, IA, KS, MO, MS, ND, NE, OK, SD, WI
 2. GENERAL: NONCODED, ZONED SYSTEM WITH MANUAL AND AUTOMATIC ALARM INITIATION; AND HARD-WIRED FOR SIGNAL TRANSMISSION, USING SEPARATE INDIVIDUAL CIRCUITS FOR EACH ZONE OF ALARM INITIATION AND NOTIFICATION APPLIANCES.
 3. INSTALLER QUALIFICATIONS: AN EXPERIENCED INSTALLER WHO IS AN AUTHORIZED REPRESENTATIVE OF THE FACP MANUFACTURER FOR BOTH INSTALLATION AND MAINTENANCE OF UNITS REQUIRED FOR THIS PROJECT.
 4. MANUFACTURER QUALIFICATIONS: A FIRM EXPERIENCED IN MANUFACTURING SYSTEMS SIMILAR TO THOSE INDICATED FOR THIS PROJECT AND WITH A RECORD OF SUCCESSFUL IN-SERVICE PERFORMANCE.
 5. COMPLIANCE WITH LOCAL REQUIREMENTS: COMPLY WITH APPLICABLE BUILDING CODE, LOCAL ORDINANCES AND REGULATIONS, AND REQUIREMENTS OF AUTHORITIES HAVING JURISDICTION.
 6. COMPLY WITH NFPA 72.
 7. FURNISH EXTRA MATERIALS DESCRIBED BELOW THAT MATCH PRODUCTS INSTALLED AND THAT ARE PACKAGED WITH PROTECTIVE COVERING FOR STORAGE AND IDENTIFIED WITH LABELS DESCRIBING CONTENTS.
 - A. SMOKE DETECTORS, FIRE DETECTORS, AND FLAME DETECTORS: QUANTITY EQUAL TO 10 PERCENT OF AMOUNT OF EACH TYPE INSTALLED, BUT NOT LESS THAN ONE UNIT OF EACH TYPE.
 - B. DETECTOR BASES: QUANTITY EQUAL TO 2 PERCENT OF AMOUNT OF EACH TYPE INSTALLED, BUT NOT LESS THAN ONE UNIT OF EACH TYPE.
 - C. KEYS AND TOOLS: ONE EXTRA SET FOR ACCESS TO LOCKED AND TAMPERPROOFED COMPONENTS.
 8. EQUIPMENT INSTALLATION:
 - A. CONNECT THE FACP WITH A CIRCUIT BREAKER WITH LOOKABLE HANDLE OR COVER.
 - B. MANUAL PULL STATIONS: MOUNT SEMIFLUSH IN RECESSED BACK BOXES.
 - C. WATER-FLOW DETECTORS AND VALVE SUPERVISORY SWITCHES: CONNECT FOR EACH SPRINKLER VALVE STATION REQUIRED TO BE SUPERVISED. SUPPLIED AND INSTALLED BY SPRINKLER CONTRACTOR.

- DIVISION 12 - SPECIAL CONSTRUCTION - NOT USED**
- SECTION 10.14.00 - FIRE PROTECTION**
1. CVS/PHARMACY HAS ENTERED INTO A NATIONAL ACCOUNT AGREEMENT WITH THE MANUFACTURERS LISTED BELOW TO FURNISH AND INSTALL THE FIRE ALARM SYSTEM SPECIFIED IN THIS SECTION. COMPLETE INSTALLATION SHALL BE BY THE NATIONAL ACCOUNT SUPPLIER. THE GENERAL CONTRACTOR IS RESPONSIBLE FOR CONTACTING THE MANUFACTURER FOR PRICING QUOTATIONS, PLACING ORDERS, AND FURTHER INFORMATION, PLEASE CALL THE APPROPRIATE MANUFACTURER FOR THE AREA THE STORE IS LOCATED IN.
 - BASS SECURITY AT (888) 774-3400 AT EXT. 1950 AREAS: IL, IN, MI, OH
 - AFA PROTECTIVE SYSTEM AT (781) 848-6200 AREAS: AL, FL, GA, MA, ME, NC, NH, NY, PA, RI, SC, VT
 - TECHNOQUALITY AT (646) 723-4410 AREAS: CT, DC, DE, MD
 - INTEGRATED SECURITY SOLUTIONS AT (800) 505-0868 AREA: NJ
 - VECTOR SECURITY AT (703) 468 8100 AT EXT. 51126 AREA: AK, CA, CO, HI, ID, IL, IN, KY, MI, MT, NM, NV, OH, OR, PR, TN, UT, VA, WA, WI, WY
 - ADVANCED PROJECT SOLUTIONS, LLC AT (608) 204-8640 AREA: AR, IA, KS, MO, MS, ND, NE, OK, SD, WI
 2. GENERAL: NONCODED, ZONED SYSTEM WITH MANUAL AND AUTOMATIC ALARM INITIATION; AND HARD-WIRED FOR SIGNAL TRANSMISSION, USING SEPARATE INDIVIDUAL CIRCUITS FOR EACH ZONE OF ALARM INITIATION AND NOTIFICATION APPLIANCES.
 3. INSTALLER QUALIFICATIONS: AN EXPERIENCED INSTALLER WHO IS AN AUTHORIZED REPRESENTATIVE OF THE FACP MANUFACTURER FOR BOTH INSTALLATION AND MAINTENANCE OF UNITS REQUIRED FOR THIS PROJECT.
 4. MANUFACTURER QUALIFICATIONS: A FIRM EXPERIENCED IN MANUFACTURING SYSTEMS SIMILAR TO THOSE INDICATED FOR THIS PROJECT AND WITH A RECORD OF SUCCESSFUL IN-SERVICE PERFORMANCE.
 5. COMPLIANCE WITH LOCAL REQUIREMENTS: COMPLY WITH APPLICABLE BUILDING CODE, LOCAL ORDINANCES AND REGULATIONS, AND REQUIREMENTS OF AUTHORITIES HAVING JURISDICTION.
 6. COMPLY WITH NFPA 72.
 7. FURNISH EXTRA MATERIALS DESCRIBED BELOW THAT MATCH PRODUCTS INSTALLED AND THAT ARE PACKAGED WITH PROTECTIVE COVERING FOR STORAGE AND IDENTIFIED WITH LABELS DESCRIBING CONTENTS.
 - A. SMOKE DETECTORS, FIRE DETECTORS, AND FLAME DETECTORS: QUANTITY EQUAL TO 10 PERCENT OF AMOUNT OF EACH TYPE INSTALLED, BUT NOT LESS THAN ONE UNIT OF EACH TYPE.
 - B. DETECTOR BASES: QUANTITY EQUAL TO 2 PERCENT OF AMOUNT OF EACH TYPE INSTALLED, BUT NOT LESS THAN ONE UNIT OF EACH TYPE.
 - C. KEYS AND TOOLS: ONE EXTRA SET FOR ACCESS TO LOCKED AND TAMPERPROOFED COMPONENTS.
 8. EQUIPMENT INSTALLATION:
 - A. CONNECT THE FACP WITH A CIRCUIT BREAKER WITH LOOKABLE HANDLE OR COVER.
 - B. MANUAL PULL STATIONS: MOUNT SEMIFLUSH IN RECESSED BACK BOXES.
 - C. WATER-FLOW DETECTORS AND VALVE SUPERVISORY SWITCHES: CONNECT FOR EACH SPRINKLER VALVE STATION REQUIRED TO BE SUPERVISED. SUPPLIED AND INSTALLED BY SPRINKLER CONTRACTOR.

- DIVISION 12 - SPECIAL CONSTRUCTION - NOT USED**
- SECTION 10.14.00 - FIRE PROTECTION**
1. CVS/PHARMACY HAS ENTERED INTO A NATIONAL ACCOUNT AGREEMENT WITH THE MANUFACTURERS LISTED BELOW TO FURNISH AND INSTALL THE FIRE ALARM SYSTEM SPECIFIED IN THIS SECTION. COMPLETE INSTALLATION SHALL BE BY THE NATIONAL ACCOUNT SUPPLIER. THE GENERAL CONTRACTOR IS RESPONSIBLE FOR CONTACTING THE MANUFACTURER FOR PRICING QUOTATIONS, PLACING ORDERS, AND FURTHER INFORMATION, PLEASE CALL THE APPROPRIATE MANUFACTURER FOR THE AREA THE STORE IS LOCATED IN.
 - BASS SECURITY AT (888) 774-3400 AT EXT. 1950 AREAS: IL, IN, MI, OH
 - AFA PROTECTIVE SYSTEM AT (781) 848-6200 AREAS: AL, FL, GA, MA, ME, NC, NH, NY, PA, RI, SC, VT
 - TECHNOQUALITY AT (646) 723-4410 AREAS: CT, DC, DE, MD
 - INTEGRATED SECURITY SOLUTIONS AT (800) 505-0868 AREA: NJ
 - VECTOR SECURITY AT (703) 468 8100 AT EXT. 51126 AREA: AK, CA, CO, HI, ID, IL, IN, KY, MI, MT, NM, NV, OH, OR, PR, TN, UT, VA, WA, WI, WY
 - ADVANCED PROJECT SOLUTIONS, LLC AT (608) 204-8640 AREA: AR, IA, KS, MO, MS, ND, NE, OK, SD, WI
 2. GENERAL: NONCODED, ZONED SYSTEM WITH MANUAL AND AUTOMATIC ALARM INITIATION; AND HARD-WIRED FOR SIGNAL TRANSMISSION, USING SEPARATE INDIVIDUAL CIRCUITS FOR EACH ZONE OF ALARM INITIATION AND NOTIFICATION APPLIANCES.
 3. INSTALLER QUALIFICATIONS: AN EXPERIENCED INSTALLER WHO IS AN AUTHORIZED REPRESENTATIVE OF THE FACP MANUFACTURER FOR BOTH INSTALLATION AND MAINTENANCE OF UNITS REQUIRED FOR THIS PROJECT.
 4. MANUFACTURER QUALIFICATIONS: A FIRM EXPERIENCED IN MANUFACTURING SYSTEMS SIMILAR TO THOSE INDICATED FOR THIS PROJECT AND WITH A RECORD OF SUCCESSFUL IN-SERVICE PERFORMANCE.
 5. COMPLIANCE WITH LOCAL REQUIREMENTS: COMPLY WITH APPLICABLE BUILDING CODE, LOCAL ORDINANCES AND REGULATIONS, AND REQUIREMENTS OF AUTHORITIES HAVING JURISDICTION.
 6. COMPLY WITH NFPA 72.
 7. FURNISH EXTRA MATERIALS DESCRIBED BELOW THAT MATCH PRODUCTS INSTALLED AND THAT ARE PACKAGED WITH PROTECTIVE COVERING FOR STORAGE AND IDENTIFIED WITH LABELS DESCRIBING CONTENTS.
 - A. SMOKE DETECTORS, FIRE DETECTORS, AND FLAME DETECTORS: QUANTITY EQUAL TO 10 PERCENT OF AMOUNT OF EACH TYPE INSTALLED, BUT NOT LESS THAN ONE UNIT OF EACH TYPE.
 - B. DETECTOR BASES: QUANTITY EQUAL TO 2 PERCENT OF AMOUNT OF EACH TYPE INSTALLED, BUT NOT LESS THAN ONE UNIT OF EACH TYPE.
 - C. KEYS AND TOOLS: ONE EXTRA SET FOR ACCESS TO LOCKED AND TAMPERPROOFED COMPONENTS.
 8. EQUIPMENT INSTALLATION:
 - A. CONNECT THE FACP WITH A CIRCUIT BREAKER WITH LOOKABLE HANDLE OR COVER.
 - B. MANUAL PULL STATIONS: MOUNT SEMIFLUSH IN RECESSED BACK BOXES.
 - C. WATER-FLOW DETECTORS AND VALVE SUPERVISORY SWITCHES: CONNECT FOR EACH SPRINKLER VALVE STATION REQUIRED TO BE SUPERVISED. SUPPLIED AND INSTALLED BY SPRINKLER CONTRACTOR.

- DIVISION 12 - SPECIAL CONSTRUCTION - NOT USED**
- SECTION 10.14.00 - FIRE PROTECTION**
1. CVS/PHARMACY HAS ENTERED INTO