


Order Plans @ www.alddieline.com

Key Value	Keynote Text
P1	EXISTING EQUIPMENT TO BE RELOCATED. RELOCATE ALL ELECTRICAL CIRCUITS (POWER AND LOW VOLTAGE) TO NEW LOCATION AS REQUIRED. REUSE EXISTING CONDUIT, JUNCTION BOXES, CORD DROPS, ETC. WHERE POSSIBLE. PROVIDE ALL DEVICES AS REQUIRED. MAKE ALL FINAL CONNECTIONS.
P2	EXISTING REFRIGERATED CASE(S) TO BE RELOCATED. RELOCATE ALL EXISTING POWER CIRCUITS (FANS, LIGHTS, ANTI-SWEATS) FROM PANELS TO NEW LOCATION. RELOCATE ALL EXISTING DEFROST CIRCUITS AS REQUIRED FROM REFRIGERATION SOURCE TO NEW LOCATION. REFER TO DEFROST WIRING DETAIL IN REFRIGERATION PLANS FOR ADDITIONAL INFORMATION. COORDINATE WITH REFRIGERATION INSTALLER PRIOR TO INSTALLATION. PROVIDE NEW WIRING AS REQUIRED. REFER TO REFRIGERATED EQUIPMENT LAYOUT PLAN SHEET (R1) FOR GROUPING OF CASES. REUSE EXISTING CONDUIT, JUNCTION BOXES, CORD DROPS, ETC. WHERE POSSIBLE. PROVIDE ALL DEVICES AS REQUIRED. MAKE ALL FINAL CONNECTIONS.
P3	CONNECT NEW RELOCATED REFRIGERATED CASES TO EXISTING POWER CIRCUITS (FANS, LIGHTS, ANTI-SWEATS) PREVIOUSLY SERVING DEMOLISHED CASES. NEWLY LOCATED REFRIGERATED CASES TO BE CONNECTED TO ALL EXISTING REFRIGERATION CIRCUITS (DEFROST, TEMPERATURE SENSOR, DEFROST TERMINATION SENSOR, ETC.) AS REQUIRED. CONTRACTOR TO VERIFY EXISTING REFRIGERATION CIRCUITRY IS ROUTED TO THE APPROPRIATE REFRIGERATION RACK (SEE SHEET R1) AND RELOCATE IF NECESSARY. REFER TO DEFROST WIRING DETAIL IN REFRIGERATION PLANS FOR ADDITIONAL INFORMATION. COORDINATE WITH REFRIGERATION INSTALLER PRIOR TO INSTALLATION. PROVIDE NEW WIRING AS REQUIRED. RELOCATE CONDUIT AND CONDUITORS TO NEW LOCATION AS REQUIRED. REFER TO REFRIGERATED EQUIPMENT LAYOUT PLAN SHEET (R1) FOR GROUPING OF CASES. REUSE EXISTING CONDUIT, JUNCTION BOXES, CORD DROPS, ETC. WHERE POSSIBLE. PROVIDE ALL DEVICES AS REQUIRED. MAKE ALL FINAL CONNECTIONS.
P4	EXISTING RECEIPTS TO BE RELOCATED. RELOCATE ALL ASSOCIATED ELECTRICAL CIRCUITS (POWER, DATA/TELEPHONE, CORD DROPS, ETC.) TO NEW LOCATION. REUSE EXISTING CONDUIT, JUNCTION BOXES, ETC. WHERE POSSIBLE. SEE ESD-62 FOR MORE INFORMATION. MAKE ALL FINAL CONNECTIONS.
P5	EXISTING SELF-SCAN CHECKOUTS TO BE RELOCATED. RELOCATE ALL ASSOCIATED ELECTRICAL CIRCUITS (POWER, DATA/TELEPHONE, CORD DROPS, ETC.) TO NEW LOCATION. REUSE EXISTING CONDUIT, JUNCTION BOXES, ETC. WHERE POSSIBLE. SEE ESD-64 FOR MORE INFORMATION. MAKE ALL FINAL CONNECTIONS.
P6	120 VOLT OUTLET BOX AT BAR JOIST FOR CONNECTION TO TELE POWER POLE. TELE POWER POLES FOR CHECK LINES SHALL BE FURNISHED BY KROGER AND NOT TIED BY GENERAL CONTRACTOR'S ELECTRICAL SUBCONTRACTOR. TERMINATE AND LABEL CONDUITS IN OUTLETS AT BAR JOIST. SEE ESD-62, ESD-62A AND ESD-62B FOR MORE INFORMATION. CONTRACTOR TO PROVIDE ANY OTHER TELE POWER POLE INDICATED ON THE DRAWINGS. SEE KROGER SPECIFICATION SECTION 26 25 33 FOR ADDITIONAL INFORMATION.
P7	EXISTING SHELVING TO BE RELOCATED. RELOCATE ALL TRACK LIGHTING AND POWER CORD DROPS AS NECESSARY. RELOCATE ALL ASSOCIATED ELECTRICAL CIRCUITS (POWER, DATA/TELEPHONE, CORD DROPS, ETC.) TO NEW LOCATION. REUSE EXISTING CONDUIT, JUNCTION BOXES, ETC. WHERE POSSIBLE. SEE POWER DEMOLITION PLANS FOR MORE INFORMATION. MAKE ALL FINAL CONNECTIONS.
P8	CONNECT NEW FLY TRAPPER(Z) ZAPPER TO EXISTING POWER CIRCUITS PREVIOUSLY SERVING DEMOLISHED FLY TRAPPER(Z) ZAPPER. EXTEND CIRCUIT AND RELOCATE RECEPTACLE WHERE REQUIRED. REUSE EXISTING CONDUIT, JUNCTION BOXES, CORD DROPS, ETC. WHERE POSSIBLE. PROVIDE ALL DEVICES AS REQUIRED. MAKE ALL FINAL CONNECTIONS.
P9	CONNECT NEW RELOCATED REFRIGERATED CASES TO EXISTING POWER CIRCUITS (FANS, LIGHTS, ANTI-SWEATS) SERVING ADJACENT CASES. NEWLY LOCATED REFRIGERATED CASES TO BE CONNECTED TO ALL EXISTING REFRIGERATION CIRCUITS (DEFROST, TEMPERATURE SENSOR, DEFROST TERMINATION SENSOR, ETC.) AS REQUIRED. PROVIDE NEW DEVICES WIRING, CONDUITS, ETC. AS REQUIRED. REFER TO REFRIGERATED EQUIPMENT LAYOUT PLAN (SEE SHEET R1) FOR GROUPING OF CASES. IF NECESSARY, PROVIDE NEW CIRCUITS FROM SPACES AVAILABLE IN THE EXISTING PANELS USED FOR FANS, LIGHTS AND ANTI-SWEATS. NOTE: ALL ANTI-SWEAT CIRCUITS ARE TO BE ROUTED THROUGH THE ANTI-SWEAT CONTROL PANEL. MAKE ALL FINAL CONNECTIONS.
P10	PROVIDE OVERHEAD CORD DROP WITH DUPLEX RECEPTACLE. MOUNT JUNCTION BOX ABOVE FINISHED CEILING GRID AT BAR JOIST AT LOCATION WITH FINISHED CEILING (SALES AREA). RECEPTACLE TO BE 8'-0" ABOVE FINISHED FLOOR. WHITE COLOR AT LOCATIONS WHEN WIRE TO BE PUBLIC AND BLACK COLOR AT OTHER AREAS. SEE ESD-18A ON ES-SERIES DRAWINGS. COORDINATE EXACT LOCATION WITH KROGER PROJECT MANAGER.
P11	PROVIDE OVERHEAD CORD DROP WITH TWIS TLOCK MALE & FEMALE CONNECTIONS AS REQUIRED BY CIRCUIT VOLTAGE AND AMPERAGE. MOUNT JUNCTION BOX ABOVE FINISHED CEILING GRID AT BAR JOIST AT LOCATION WITH FINISHED CEILING (SALES AREA). TWIS TLOCK DEVICES TO BE 8'-0" ABOVE FINISHED FLOOR. SEE ESD-18A ON ES-SERIES DRAWINGS. COORDINATE EXACT LOCATION WITH KROGER PROJECT MANAGER.
P12	20A CIRCUIT FOR PROMOTIONAL OR CONVENIENCE OUTLET. MAKE AVAILABLE BY DEMOLITION OF CHECKSTANDS. COORDINATE EXACT LOCATION WITH KROGER PROJECT MANAGER.
P14	CIRCUIT FOR FROZEN FOOD CASE EXHAUST FAN. EXHAUST FAN FURNISHED AND NOT TIED BY CONTRACTOR. COORDINATE EXACT LOCATION WITH KROGER PROJECT MANAGER AND KROGER PROJECT MANAGER. PROVIDE ALL ELECTRICAL DEVICES AS REQUIRED. MAKE ALL FINAL CONNECTIONS.
P15	CONNECT NEW EXHAUST FAN TO EXISTING CIRCUIT. PREVIOUSLY SERVING DEMOLISHED EXHAUST FAN. CONTRACTOR TO CONFIRM EXISTING CIRCUIT IS ADEQUATE FOR NEW FAN AND PROVIDE NEW WIRING AS REQUIRED. PROVIDE NEW PULL OUT SWITCH AS INDICATED. WIRE TO RESTROOM. SEE ESD-62 FOR MORE INFORMATION. CONTRACTOR TO PROVIDE ALL ELECTRICAL DEVICES REQUIRED FOR AN OPERATIONAL SYSTEM. MAKE FINAL CONNECTIONS.
P21	CONNECT NEW MENU BOARD TO EXISTING CIRCUIT. PREVIOUSLY SERVING DEMOLISHED MENU BOARD. EXTEND CIRCUIT TO MENU BOARD. REUSE EXISTING CONDUIT, JUNCTION BOXES, CORD DROPS, ETC. WHERE POSSIBLE. PROVIDE ALL DEVICES AS REQUIRED. MAKE ALL FINAL CONNECTIONS.
P22	CONNECT NEW JUMPER TO EXISTING CIRCUIT AS INDICATED. VERIFY EXISTING CIRCUIT WIRING IS ADEQUATE BY ADDITION OF NEW EQUIPMENT. PROVIDE NEW CIRCUIT FROM PANEL AS REQUIRED. PROVIDE ALL ELECTRICAL DEVICES AS REQUIRED.
P23	EXISTING SHELVING TO BE RELOCATED. RELOCATE ALL ASSOCIATED ELECTRICAL CIRCUITS (POWER, DATA/TELEPHONE, CORD DROPS, ETC.) TO NEW LOCATION. REUSE EXISTING CONDUIT, JUNCTION BOXES, ETC. WHERE POSSIBLE. SEE ESD-62 FOR MORE INFORMATION. MAKE ALL FINAL CONNECTIONS.
P24	RELOCATE CORD DROPS FOR THE SHELVING POWER FEEDS. PROVIDE NEW TO MATCH WHERE REQUIRED.
P25	POWER FEED CORD DROPS FOR KPMR SHELVING TO MATCH DTC. PROVIDE QUANTITY AS REQUIRED.
P26	CONNECT NEW WATER FOUNTAIN TO EXISTING POWER CIRCUIT. PREVIOUSLY SERVING DEMOLISHED WATER FOUNTAIN. EXTEND CIRCUIT AND RELOCATE RECEPTACLE WHERE REQUIRED. REUSE EXISTING CONDUIT, JUNCTION BOXES, CORD DROPS, ETC. WHERE POSSIBLE. PROVIDE ALL DEVICES AS REQUIRED. MAKE ALL FINAL CONNECTIONS.
P27	CONDUIT FOR RECEPTACLE TO BE ROUTED OUTSIDE COOLER PANEL AND PENETRATE AT RECEPTACLE LOCATION. SEE ESD-26 FOR MORE INFORMATION.
P28	NEW SELF-SCAN CHECKOUTS TO BE CONNECTED TO CIRCUITS MADE AVAILABLE BY DEMOLITION OF CHECKSTANDS. SEE ELECTRICAL EQUIPMENT REQUIREMENTS FOR MORE INFORMATION. PROVIDE DEDICATED, ISOLATED GROUND CIRCUIT FROM PANEL. USE SELF-SCANS PER CIRCUIT. PROVIDE ADDITIONAL CIRCUIT FROM PANEL. REUSE EXISTING CONDUIT, JUNCTION BOXES, ETC. WHERE POSSIBLE. SEE ESD-62A FOR MORE INFORMATION. MAKE ALL FINAL CONNECTIONS.
P30	EXISTING PHARMACY COMPUTER EQUIPMENT TO BE POLE MOUNTED. RELOCATE ALL ELECTRICAL CIRCUITS (POWER AND LOW VOLTAGE) TO NEW LOCATION AS REQUIRED. COORDINATE EXACT REQUIREMENTS WITH KROGER PROJECT MANAGER. REUSE EXISTING CONDUIT, JUNCTION BOXES, CORD DROPS, ETC. WHERE POSSIBLE. PROVIDE ALL DEVICES AS REQUIRED. MAKE ALL FINAL CONNECTIONS.
P31	PROVIDE NEW 45A CIRCUIT FOR BAKER FROM WDP. 3/8" x 1/80" 3/4" REUSE EXISTING CONDUIT, JUNCTION BOXES AND SWITCH WHERE POSSIBLE. PROVIDE NEW CLASS RK1 FUSE. MAKE ALL FINAL CONNECTIONS.
P32	EXISTING REFRIGERATED CASE TO BE CONVERTED FROM LOW TEMP TO DUAL TEMP. CONNECTIONS PROVIDED BY REFRIGERATION CONTRACTOR. PROVIDE ALL ELECTRICAL DEVICES AS REQUIRED FOR CONVERSION. COORDINATE REQUIREMENTS WITH REFRIGERATION INSTALLER.
P33	CUSTOMER SERVICE AREA TO BE REMODELED. DISCONNECT / RECONNECT ALL ELECTRICAL AND LOW VOLTAGE DEVICES AS REQUIRED. COORDINATE WITH ALL OTHER TRADES.
P34	FLOOR WORKSTATION TO BE REMODELED. DISCONNECT / RECONNECT ALL ELECTRICAL AND LOW VOLTAGE DEVICES AS REQUIRED. COORDINATE WITH ALL OTHER TRADES.
P35	PHARMACY TO BE REMODELED. DISCONNECT / RECONNECT ALL ELECTRICAL AND LOW VOLTAGE DEVICES AS REQUIRED. COORDINATE WITH ALL OTHER TRADES.
P36	CONNECT NEW EXHAUST FAN TO EXISTING CIRCUIT. PREVIOUSLY SERVING DEMOLISHED EXHAUST FAN. CONTRACTOR TO CONFIRM EXISTING CIRCUIT IS ADEQUATE FOR NEW FAN AND PROVIDE NEW WIRING AS REQUIRED. PROVIDE NEW PULL OUT SWITCH AS INDICATED. FIELD COORDINATE SWITCH LOCATION WITH KROGER PROJECT MANAGER. CONTRACTOR TO PROVIDE ALL ELECTRICAL DEVICES REQUIRED FOR AN OPERATIONAL SYSTEM. MAKE FINAL CONNECTIONS.
P37	JUNCTION BOX FOR CONDENSATE PUMP. VERIFY MOUNTING LOCATION IN FIELD. PROVIDE TWO-POLE SWITCH FOR DISCONNECT.
P40	CONNECT SELF-CHECKOUT ATTENDANT STATION TO CIRCUIT MADE AVAILABLE IN PANEL. MAKE ALL FINAL CONNECTIONS.



1 ENLARGED POWER PLAN - DELI / BAKERY
3/16" = 1'-0"

- NO SURFACE MOUNTED CONDUIT OR PIPING ALLOWED IN MEAT AND PRODUCE PREP ROOMS.
- REFER TO SHEET E01 FOR LEGENDS, NOTES, AND SCHEDULES.
- AT MECHANICAL CHASES AND STORES WITHOUT CEILING IN SALES AREA, GROUP VERTICAL PIPING (REFRIGERATION, ELECTRICAL CONDUIT AND MECHANICAL DROPS) NEARLY TOGETHER AS POSSIBLE AND PAINT TO MATCH STRUCTURAL COLUMNS.
- NO ELECTRICAL EQUIPMENT SHALL BE LOCATED UNDERNEATH THE SKYLIGHTS INCLUDING BUT NOT LIMITED TO CONDUIT, LIGHTS, CABLES FOR SIGNAGE, ETC.
- RUN CONDUITS ON TOP OF INSULATED ROOF PANEL, SUB THRU PANEL INTO FIXTURES FOR PREP ROOM LIGHTING.
- THE ONLY SURFACE MOUNTED CONDUIT PERMITTED IN THE DELI AND BAKERY PREP ROOMS SHALL BE ON THEIR COOLER AND FREEZER WALL AND CEILING.
- REFER TO ES SERIES SHEETS FOR ELECTRICAL STANDARD DETAILS (ESDs).
- ALL CONDUITS IN SALES AREA FROM ROOF TO LOW WALLS OR EQUIPMENT SHALL BE COORDINATED AND GROUPED TOGETHER WITH OTHER MECHANICAL CONDUITS.

ROBERTSON LOJA ROOF ARCHITECTS & ENGINEERS
3400 Princeton Ridge Road, Suite 275 Alpharetta, GA 30005
770.974.2800 / www.rlr.com

REGISTERED PROFESSIONAL ENGINEER
STATE OF GEORGIA
No. 26555
12/13/2020

Kroger

Kroger GA-464
2175 Park Lake Drive, Atlanta, GA 30326

The Kroger Company

REVISIONS

DATE: 02-12-20
PROJECT NUMBER: 20-107
SHEET NUMBER: E4.1

ELECTRICAL ENLARGED POWER PLAN