

PRE-ENGINEERED LIGHT GAUGE STRUCTURAL FRAMING:

GENERAL:

- LIGHT GAUGE FRAMING INCLUDING EXTERIOR WALL STUDS, INTERIOR WALLS AND SOFFIT STUDS, FLOOR JOISTS, AND ROOF JOISTS SHALL BE DESIGNED BY A STRUCTURAL ENGINEER REGISTERED IN THE PROJECT STATE.
- PRIOR TO FABRICATION, THE CONTRACTOR SHALL SUBMIT SEALED SHOP DRAWINGS INDICATING DESIGN DATA AND SHALL INCLUDE COMPLETE PLANS AND DETAILS.
- INFORMATION INCLUDED IN THESE PLANS ARE THE MINIMUM REQUIREMENTS. EXTERIOR WALL STUDS SHALL BE A MINIMUM OF 600 S 162-54 AT 16" O.C.
- METAL STUD STRENGTH CRITERIA:
 - GAUGES 20 THROUGH 18 - 33 KSI MIN. YIELD STRESS
 - GAUGES 16 THROUGH 12 - 50 KSI MIN. YIELD STRESS
 - TRACK RUNNER - 33 KSI MIN. YIELD STRESS
- METAL STUD MEMBER DESIGNATION: 600 S 162 - 33

| MILS | GAUGE |
|------|-------|
| 33 | 20 |
| 43 | 18 |
| 54 | 16 |
| 68 | 14 |
| 97 | 12 |

WEB DEPTH: 600 = 6"
MEMBER TYPE: S = STUD
FLANGE WIDTH: 162 = 1.625" (1 5/8")
MINIMUM THICKNESS IN MILS
- FASTENERS:
 - SCREW CONNECTIONS

FASTENING STUD TO STUD
USE #10-18 TEK® x 5/8" LONG BY ITW BUILDEX UNLESS OTHERWISE NOTED.
MIN. EDGE DISTANCE = 3/4"
MIN. SPACING BETWEEN FASTENERS = 3/4"

FASTENING STUD TO MASONRY:
USE 1/4" DIA. TAPCON SCREWS BY ITW BUILDEX.
MIN. EMBEDMENT = 1" MIN. EDGE DISTANCE = 2"
MIN. SPACING BETWEEN FASTENERS = 3"
 - POWDER ACTUATED FASTENERS (P.A.F.):

FASTENING TO CONCRETE OR MASONRY:
USE 0.145" DIA. DOME HEAD NAIL BY HILTI, UNLESS NOTED OTHERWISE.
MIN. EMBEDMENT = 1 1/4" MIN. EDGE DISTANCE = 2"
MIN. SPACING BETWEEN FASTENERS = 3"

FASTENING TO STEEL:
USE 0.145" DIA. DOME HEAD KNURLED SHANK FASTENER BY HILTI, UNLESS NOTED OTHERWISE.
MIN. EMBEDMENT = FULL PENETRATION MIN. EDGE DISTANCE = 1/2"
MIN. SPACING BETWEEN FASTENERS = 1"
- FASTENING:
 - MINIMUM FASTENING REQUIREMENTS, UNLESS NOTED OTHERWISE.

TRACK TO CONCRETE:
(2) FASTENERS AT 16" O.C. TYP. w/ADD'L FASTENER 3" FROM END OF TRACK AND (2) FASTENERS MINIMUM AT JAMBS.

TRACK TO STRUCTURAL STEEL:
12" O.C. TYP. w/ADD'L FASTENER 3" FROM END OF TRACK AND (2) FASTENERS MINIMUM AT JAMBS.

STUD TO TRACK:
(1) SCREW MINIMUM AT EACH FLANGE

STUD TO STUD:
(3) SCREWS MINIMUM

STUD TO STEEL OR CONCRETE:
USE POWDER ACTUATED FASTENERS REFERENCED ABOVE.
SEE DETAILS FOR CONNECTIONS, MINIMUM 2 FASTENERS.
- WALL OPENING FRAMING: ALL STUDS CUT TO CREATE WALL OPENING MUST BE REPLACED WITH EQUAL FULL HEIGHT KING STUDS ON EACH SIDE OF THE OPENING.
- CURTAIN WALL AND NON LOAD BEARING PARTITIONS:

MECHANICAL BRACING OF STUDS IS NOT NECESSARY WHERE WALL SHEATHING IS ATTACHED ON BOTH SIDES OF THE STUDS.

WHEN ONLY ONE FACE OF THE STUDS RECEIVE SHEATHING, PROVIDE BRACING BY ONE OF THE FOLLOWING METHODS:

 - COLD ROLLED CHANNEL, RUN HORIZONTALLY THROUGH STUD PUNCH OUTS AND ATTACHED AT EACH STUD.
 - 2" WIDE, 18 GAUGE, STEEL STRAPS RUN HORIZONTALLY, ON BOTH SIDES OF THE STUDS, AND ATTACHED AT EACH STUD.

VERTICAL SPACING OF THE BRACING IS LIMITED TO A MAXIMUM OF 4'-0" THROUGHOUT THE HEIGHT OF THE WALL.
- PROVIDE ALL ACCESSORIES AS REQUIRED BY THE METAL STUD MANUFACTURER.
- JOISTS SHALL BE FABRICATED TO PROVIDE 12" OF UNPUNCHED WEB AT BEARING ENDS.
- PROVIDE JOIST WEB STIFFENERS PER METAL STUD MANUFACTURERS' RECOMMENDATIONS AT BEARING POINTS.
- PROVIDE END BLOCKING WHERE JOISTS ARE NOT RESTRAINED AGAINST ROTATION.
- NO LIGHT GAUGE MEMBER, THAT HAS BEEN TRIMMED OR CUT, SHALL BE INSTALLED SO THAT AN EDGE OF A WEB PUNCH OUT OCCURS WITHIN 10" MINIMUM OF THE TRIMMED OR CUT MEMBER END.
- ALL MEMBER CUTTING MUST BE PERFORMED USING A SAW OR SHEAR. NO TORCH CUTTING IS ALLOWED AT ANY TIME. ALSO CUTTING OF ADDITIONAL HOLES, OTHER THAN THOSE PROVIDED BY THE MANUFACTURER, IN THE MEMBER WEB IS NOT PERMITTED AT ANY TIME.
- SPlicing OF AXIALLY LOADED MEMBERS IS NOT ALLOWED AT ANY TIME.
- BUILT UP LIGHT GAUGE HEADERS, CONSTRUCTED FOR EXTERIOR WALL CONDITIONS, SHALL HAVE INSULATION PLACED WITHIN THEM PRIOR TO THEIR INSTALLATION IN WALL SYSTEM.

PERFORMANCE REQUIREMENTS:

- STRUCTURAL PERFORMANCE: PROVIDE COLD FORMED METAL FRAMING CAPABLE OF WITHSTANDING DESIGN LOADS WITHIN LIMITS AND UNDER CONDITIONS INDICATED.
 - DESIGN LOADS: AS INDICATED IN STRUCTURAL DESIGN CRITERIA.
 - DEFLECTION LIMITS: DESIGN FRAMING SYSTEMS TO WITHSTAND DESIGN LOADS WITHOUT DEFLECTIONS GREATER THAN THE FOLLOWING:
 - EXTERIOR LOAD BEARING WALL FRAMING: HORIZONTAL DEFLECTION OF L/360 OF THE WALL HEIGHT.
 - INTERIOR LOAD BEARING WALL FRAMING: HORIZONTAL DEFLECTION OF L/240 OF THE WALL HEIGHT.
 - WALL FRAMING SUPPORTING BRICK VENEER: DEFLECTION OF L/600 OF THE SPAN LENGTH.
 - DESIGN FRAMING SYSTEMS TO PROVIDE FOR MOVEMENT OF FRAMING MEMBERS WITHOUT DAMAGE OR OVERSTRESSING, SHEATHING FAILURE, CONNECTION FAILURE, UNDUE STRAIN ON FASTENERS AND ANCHORS, OR OTHER DETRIMENTAL EFFECTS WHEN SUBJECT TO A MAXIMUM AMBIENT TEMPERATURE CHANGE OF 120 DEG. F.
 - DESIGN FRAMING SYSTEM TO MAINTAIN CLEARANCES AT OPENINGS, TO ALLOW FOR CONSTRUCTION TOLERANCES, AND TO ACCOMMODATE LIVE LOAD DEFLECTION OF PRIMARY BUILDING STRUCTURE.
 - METAL STUD MANUFACTURER SHALL BE A MEMBER OF THE STEEL STUD MANUFACTURERS ASSOCIATION (SSMA).
 - ALL METAL STUDS AND ACCESSORIES SHALL HAVE A G60 GALVANIZED COATING, UNLESS NOTED OTHERWISE.

SUBMITTALS:

- PRODUCT DATA: FOR EACH TYPE OF COLD FORMED METAL FRAMING PRODUCT AND ACCESSORY INDICATED.
- SHOP DRAWINGS: SHOW LAYOUT, SPACINGS, SIZES, THICKNESSES, AND TYPES OF COLD FORMED METAL FRAMING; FABRICATION; AND FASTENING AND ANCHORAGE DETAILS, INCLUDING MECHANICAL FASTENERS. SHOW REINFORCING CHANNELS, OPENING FRAMING, SUPPLEMENTAL FRAMING, STRAPPING, BRACING, BRIDGING, SPLICES, ACCESSORIES, CONNECTION DETAILS, AND ATTACHMENT TO ADJOINING WORK.
 - FOR COLD FORMED METAL FRAMING INDICATED TO COMPLY WITH DESIGN LOADS, INCLUDE STRUCTURAL ANALYSIS DATA SIGNED AND SEALED BY THE QUALIFIED PROFESSIONAL ENGINEER (LICENSED IN THE PROJECT STATE) RESPONSIBLE FOR THEIR PREPARATION.

QUALITY ASSURANCE:

- INSTALLER QUALIFICATIONS: AN EXPERIENCED INSTALLER WHO HAS COMPLETED COLD FORMED METAL FRAMING SIMILAR IN MATERIAL, DESIGN, AND EXTENT TO THAT INDICATED FOR THIS PROJECT AND WHOSE WORK HAS RESULTED IN CONSTRUCTION WITH A RECORD OF SUCCESSFUL IN SERVICE PERFORMANCE.
- ENGINEERING RESPONSIBILITY: ENGAGE A QUALIFIED PROFESSIONAL ENGINEER (LICENSED IN THE PROJECT STATE) TO PREPARE DESIGN CALCULATIONS, SHOP DRAWINGS, AND OTHER STRUCTURAL DATA.

REFER TO LIGHT GAUGE FRAMING DRAWINGS FOR LIGHT GAGE METAL NOTES, PLANS AND DETAILS REQUIRED TO COMPLETE SYSTEM.
- AISI SPECIFICATIONS: COMPLY WITH AISI'S "SPECIFICATION FOR THE DESIGN OF COLD FORMED STEEL STRUCTURAL MEMBERS" OR "LOAD AND RESISTANCE FACTOR DESIGN SPECIFICATION FOR COLD FORMED STEEL STRUCTURAL MEMBERS".

Order Plans @ www.LDILine.com

| ABBREVIATIONS | | | |
|---------------|----------------------------|---------|--------------------------|
| A.B | ANCHOR BOLT | MAS | MASONRY |
| AFF | ABOVE FINISHED FLOOR | MAX | MAXIMUM |
| ARCH | ARCHITECT | MFR. | MANUFACTURER |
| B/ | BOTTOM OF | MIN. | MINIMUM |
| BM | BEAM | MISC. | MISCELLANEOUS |
| BOTT | BOTTOM | M.O. | MASONRY OPENING |
| BLKG | BLOCKING | MTL. | METAL |
| BLDG. | BUILDING | N.A. | NOT APPLICABLE |
| | | N/A | NOT APPLICABLE |
| CJ | CONTROL/CONSTRUCTION JOINT | N.D.T. | NON-DESTRUCTIVE TESTING |
| C.L. | CENTER LINE | N.I.C. | NOT IN CONTRACT |
| CLR | CLEAR | N.T.S. | NOT TO SCALE |
| CMU | CONCRETE MASONRY UNIT | O.C. | ON CENTER |
| COL | COLUMN | O.D. | OUTSIDE DIAMETER |
| CONC | CONCRETE | O.H. | OPPOSITE HAND |
| CONT | CONTINUOUS | OPNG | OPENING |
| CONST | CONSTRUCTION | OPP. | OPPOSITE |
| CONTR. | CONTRACTOR | P.A.F. | POWDER ACTUATED FASTENER |
| COORD | COORDINATE | P.J.F. | PREMOLDED JOINT FILLER |
| CTR. | CENTER | PL | PLATE |
| DET. | DETAIL | PLYWD. | PLYWOOD |
| DIA | DIAMETER | PREFAB. | PREFABRICATED |
| DN | DOWN | P.T. | PRESSURE TREATED |
| DIM | DIMENSION | PTD. | PAINTED |
| DWG. | DRAWING | RAD. | RADIUS |
| EA | EACH | REINF | REINFORCING |
| E.J. | EXPANSION JOINT | REQ'D | REQUIRED |
| EL | ELEVATION | SECT. | SECTION |
| ELEV | ELEVATION | SHT. | SHEET |
| E.O.R. | ENGINEER OF RECORD | SIM. | SIMILAR |
| E.W. | EACH WAY | SPCS | SPACES |
| EXIST. | EXISTING | SQ. | SQUARE |
| E.O.S. | EDGE OF SLAB | STD. | STANDARD |
| F.F | FINISH FLOOR | STL | STEEL |
| FIN. FLR. | FINISH FLOOR | STRUC. | STRUCTURAL |
| FT. | FOOT | S.W. | SHORT WAY |
| F.S. | FOOTING STEP | | |
| FTG. | FOOTING | | |
| F.V. | FIELD VERIFY | TJ | TOP OF |
| | | THK. | THICK |
| GA. | GAUGE | T.O.S. | TOP OF STEEL |
| GALV. | GALVANIZED | TYP | TYPICAL |
| G.C. | GENERAL CONTRACTOR | U.N.O. | UNLESS NOTED OTHERWISE |
| GDR | GIRDER | VERT. | VERTICAL |
| HT. | HEIGHT | WD | WOOD |
| HORIZ | HORIZONTAL | WF | WIDE FLANGE |
| JBE | JOIST BEARING ELEVATION | WWF | WELDED WIRE FABRIC |
| JST | JOIST | WWM | WELDED WIRE MESH |
| JT | JOINT | W/ | WITH |
| | | W/O | WITHOUT |
| KB | KNEE BRACE | WP | WORK POINT |
| LG | LONG | | |
| LLH | LONG LEG HORIZONTAL | | |
| LLV | LONG LEG VERTICAL | | |
| LW | LONG WAY | | |

RaceTrac.
COPYRIGHT NOTICE
THESE PLANS ARE SUBJECT TO FEDERAL
COPYRIGHT LAWS; ANY USE OF SAME
WITHOUT THE EXPRESSED WRITTEN
PERMISSION OF RACETRAC PETROLEUM,
INC. IS PROHIBITED. 2016 RACETRAC
PETROLEUM INC.

DESIGN PROFESSIONALS



ISSUE/REVISION RECORD

| DATE | DESCRIPTION |
|----------|----------------------|
| 01/25/19 | PERMIT SET |
| 03/16/20 | REFRESH TO 2020.0113 |

RaceTrac
RACETRAC PETROLEUM, INC.
200 GALLERIA PARKWAY SOUTHEAST
SUITE 900
ATLANTA, GEORGIA 30339
(770) 431-7600

PROJECT NAME

HWY 316 @ 81

**BETHLEHEM
GA 30620
839 LOGANVILLE HWY**

RACETRAC STORE NUMBER

#1304

PROTOTYPE SERIES 5.5K 2.0

2018 LH MO 0405

PLAN MODIFICATION NOTICE

SPB NO. 0405 DATE 12/18/18

STANDARD PLAN BULLETINS (SPB) MODIFY THE PROTOTYPE SERIES SET NOTED ABOVE. THE LISTED SPB REPRESENTS THE LATEST MODIFICATION INCORPORATED TO THIS PROTOTYPE SERIES SET AT ORIGINAL RELEASE. THE ISSUE/REVISION RECORD COLUMN ABOVE LISTS ANY REVISIONS OR SPB INCORPORATED TO THIS SET AFTER THE ORIGINAL RELEASE. CONTACT RACETRAC ENGINEERING AND CONSTRUCTION FOR ANY SUBSEQUENT BULLETINS NOT INCORPORATED HEREIN.

PROFESSIONAL SEAL

**PROJECT NUMBER
2018157.19**

SHEET TITLE

**GENERAL
STRUCTURAL
NOTES**

SHEET NUMBER

S001