



Order Plans @ www.LDILine.com

1 MECHANICAL ROOF PLAN
3/16" = 1'-0"



GENERAL NOTES

1. RUN REFRIGERANT PIPING PER MANUFACTURER'S RECOMMENDATIONS. SUCTION PIPING SHALL BE INSULATED WITH 1/2" MANVILLE AEROTUBE 11 PIPE INSULATION SLID OVER TUBING WITHOUT CUTTING. ALL JOINTS AND SEAMS SHALL BE SEALED WITH ADHESIVE. PROVIDE COATING TO PROTECT INSULATION FROM DETERIORATION FROM THE SUN AND WEATHER.
2. CONTRACTOR TO PROVIDE PROTECTIVE HOUSINGS ON ALL HVAC AND REFRIGERATION EQUIPMENT LOCATED OUTSIDE.
3. GENERAL CONTRACTOR TO PROVIDE PIPE STAND TO HOLD REFRIGERANT LINES UP OFF ROOF.
4. CONTRACTOR SHALL INSTALL 12" HARDWARE CLOTH ACROSS DIMENSIONS OF AIR INLET & OUTSIDE AIR INTAKE TO PREVENT BLOCKAGE FROM DEBRIS. CONTRACTOR RESPONSIBLE FOR PAINT TOUCH-UP AT ANY SCRATCHED/MARRED SURFACES. PAINT SPEC PER MANUFACTURER'S RECOMMENDATIONS.
5. COORDINATE EXACT LOCATION OF ALL ROOF PENETRATIONS WITH THE ARCHITECTURAL DRAWINGS.

SHEET KEYNOTES

1. CONTRACTOR TO MAINTAIN 10'-0" CLEARANCE OF OUTSIDE AIR INTAKES ON HVAC UNITS TO ALL EXHAUST OUTLETS AND SANITARY VENTS.
2. MAINTAIN FACTORY RECOMMENDED SERVICE CLEARANCES FOR EQUIPMENT ON ROOF.
3. COORDINATE LOCATION OF UNITS AND ROOF CURBS WITH THE ARCHITECTURAL AND STRUCTURAL DWGS SHOWING BUILDING STEEL. SEE DETAIL 1 AND 6 ON SHEET M430.
4. ALL UTILITIES TO ROOFTOP HVAC UNITS TO BE ROUTED UP THROUGH ROOF CURB. COORDINATE WITH MANUFACTURER'S RECOMMENDATION THROUGH THE BASE LOCATIONS FOR UTILITIES.
5. G.C. SHALL PROVIDE EQUIPMENT SUPPORT RACKS FOR REMOTE CONDENSERS M.C. SHALL INSTALL CLUMBER FURNISHED CONDENSERS ON RACKS. SEE DETAIL 8 ON SHEET M430.
6. CONTRACTOR SHALL FURNISH AND INSTALL REFRIGERANT PIPING FROM CONDENSERS TO EVAPORATOR/COOLERS IN THE SPACE. COORDINATE EXACT LINE SIZES WITH EQUIPMENT VENDOR.
7. G.C. SHALL PROVIDE ATR HUB FOR REFRIGERANT PIPING PENETRATION THROUGH ROOF. SEAL ALL OPENINGS AROUND PIPING WITH FOAM AIR TIGHT. SEE DETAIL 3 ON SHEET A201.
8. CONTRACTOR SHALL FURNISH AND INSTALL 1 1/4" CHILLED WATER SUPPLY AND RETURN PIPING FROM CHILLER TO YOGURT MACHINES. COORDINATE EXACT REQUIREMENTS WITH VENDOR.
9. SHOWN FOR REFERENCE.
10. PROVIDE 1" CONDENSATE DRAIN PIPING FROM ROOFTOP HVAC UNIT TO CLOSEST SCUPPER. SEE DETAIL 3/P431.
11. RTU CONDENSATE SHALL TERMINATE AT SCUPPER WITH ELBOW TURNED DOWN IN SCUPPER WITH REQUIRED AIR GAP.
12. NON-FREEZE ROOF HYDRANT. SHOWN FOR REFERENCE. SEE PLUMBING PLANS FOR MORE INFORMATION.

RaceTrac.
COPYRIGHT NOTICE
THESE PLANS ARE SUBJECT TO FEDERAL
COPYRIGHT LAWS. ANY USE OF SAME
WITHOUT THE EXPRESSED WRITTEN
PERMISSION OF RACETRAC PETROLEUM,
INC. IS PROHIBITED. 2016 RACETRAC
PETROLEUM, INC.

DESIGN PROFESSIONALS



ISSUE/REVISION RECORD

DATE	DESCRIPTION
01/25/19	PERMIT SET
03/16/20	REFRESH TO 2020.0113

RaceTrac.

RACETRAC PETROLEUM, INC.
200 GALLERIA PARKWAY SOUTHEAST
SUITE 900
ATLANTA, GEORGIA 30339
(770) 431-7600

PROJECT NAME

HWY 316 @ 81

**BETHLEHEM
GA 30620**

839 LOGANVILLE HWY

RACETRAC STORE NUMBER

#1304

PROTOTYPE SERIES 5.5K 2.0

2018 LH MO 0405

PLAN MODIFICATION NOTICE

SPB NO. 0405 DATE 12/18/18

STANDARD PLAN BULLETINS (SPB) MODIFY THE PROTOTYPE SERIES SET NOTED ABOVE. THE LISTED SPB REPRESENTS THE LATEST MODIFICATION INCORPORATED TO THIS PROTOTYPE SERIES SET AT ORIGINAL RELEASE. THE ISSUE/REVISION RECORD COLUMN ABOVE LISTS ANY REVISIONS OR SPB INCORPORATED IN THIS SET AFTER THE ORIGINAL RELEASE. CONTACT RACETRAC ENGINEERING AND CONSTRUCTION FOR ANY SUBSEQUENT BULLETINS NOT INCORPORATED HEREIN.

PROFESSIONAL SEAL

PROJECT NUMBER
2018157.19

SHEET TITLE
**MECHANICAL ROOF
PLAN**

SHEET NUMBER

M200