



DOOR SCHEDULE ("X" INDICATES EXISTING DOOR)

NOTE: HARDWARE PACKAGES ARE BASED ON PROJECT SPECIFICATIONS BOOK. THE CONDITION OF ALL EXISTING HARDWARE SHALL BE VERIFIED BY THE FOOD LION CONSTRUCTION SUPERVISOR AT THE TIME WALK-THROUGH.

REMARKS:
 1. AT NEW EGRESS DOORS, ELECTRICAL CONTRACTOR TO SUPPLY & INSTALL JUNCTION BOX FOR SECURITY ALARM (IF NOT EXISTING) BEFORE DOOR FRAME IS SET.
 2. THE GENERAL CONTRACTOR SHALL SUPPLY AND INSTALL THE EXIT DEVICE PURCHASED FROM BA HOFT 919-596-4446. EXIST DEVICE SHALL BE VON DUPPIN C096D-1E. NO SUBSTITUTION (POWER AND TIME DELAY SUPPLIED AND ACTIVATED BY OTHERS).
 3. ALL ACCESSIBLE DOORS SHALL HAVE HANDLES, PULLS, LATCHES, LOCKS AND OTHER OPERABLE PARTS WITH A SHAPE THAT IS EASY TO GRASP WITH ONE HAND AND DOES NOT REQUIRE TIGHT GRASPING, TIGHT PINCHING, OR TWISTING OF THE WRIST TO OPERATE.

NO	SIZE	LOCATION	RM	HRDW	TYPE	FRAME	HEAD	JAMB	SILL	FRAME COLOR	DOOR FINISH	NOTES AND COMMENTS
100A*	PR 2'-6"x7'-0"x1 3/4"	EXISTING VESTIBULE	100	EXIST	1	EXIST	EXIST	EXIST	EXIST	FACTORY	FACTORY	SEE DOOR SCHEDULE NOTES #2,8,12,16,17
100B*	PR 2'-6"x7'-0"x1 3/4"	EXISTING VESTIBULE	100	EXIST	1	EXIST	EXIST	EXIST	EXIST	FACTORY	FACTORY	SEE DOOR SCHEDULE NOTES #2,8,12,16,17
102*	3'-0"x7'-0"x1 3/4"	REMODELED WORK ROOM	102	EXIST	7	EXIST	EXIST	EXIST	EXIST	P-3(B)	P-3(B)	SEE DOOR SCHEDULE NOTES #9,10,11,12,15,16,18
104*	3'-0"x7'-0"x1 3/4"	REMODELED CORRIDOR	104	EXIST	2	EXIST	EXIST	EXIST	EXIST	P-3(B) CORR/ EXT MATCH ADJ	P-3(B) CORR/ EXT MATCH ADJ	SEE DOOR SCHEDULE NOTES #9,10,12,15,16,17,20
105*	3'-0"x7'-0"x1 3/4"	REMODELED MEN'S RESTROOM	105	EXIST	2	EXIST	EXIST	EXIST	EXIST	P-3(B) CORR/ P-3(B) RR	P-3(B) CORR/ P-3(B) RR	SEE DOOR SCHEDULE NOTES #9,10,11,12,18,19
106*	3'-0"x7'-0"x1 3/4"	REMODELED WOMEN'S RESTROOM	106	EXIST	2	EXIST	EXIST	EXIST	EXIST	P-3(B) CORR/ P-3(B) RR	P-3(B) CORR/ P-3(B) RR	SEE DOOR SCHEDULE NOTES #9,10,11,12,18,19
107A*	4'-0"x7'-0"x1 3/4"	EXISTING RECEIVING ROOM	107	EXIST	2	EXIST	EXIST	EXIST	EXIST	P-3(B) ROOM/ EXT MATCH ADJ	P-3(B) ROOM/ EXT MATCH ADJ	SEE DOOR SCHEDULE NOTES #12,13
107B*	4'-0"x7'-0"x1 3/4"	EXISTING RECEIVING ROOM EXIT	107	EXIST	2	EXIST	EXIST	EXIST	EXIST	P-3(B) ROOM/ EXT MATCH ADJ	P-3(B) ROOM/ EXT MATCH ADJ	SEE DOOR SCHEDULE NOTES #12,17,20
107C*	8'-0"x8'-0"	EXISTING RECEIVING ROOM	107	EXIST	9	EXIST	EXIST	EXIST	EXIST	FACTORY	FACTORY	SEE DOOR SCHEDULE NOTES #12,13
107D*	8'-0"x8'-0"	EXISTING RECEIVING ROOM	107	EXIST	9	EXIST	EXIST	EXIST	EXIST	FACTORY	FACTORY	SEE DOOR SCHEDULE NOTES #12,13
107E*	PR 3'-0"x7'-0"x1 3/4"	EXISTING STAGING AREA	107A	EXIST	12	EXIST	EXIST	EXIST	EXIST	P-3(B)	FACTORY	SEE DOOR SCHEDULE NOTES #1,3,4,14,16- NEW WINDOW KIT
108*	3'-0"x7'-0"x1 3/4"	EXISTING LOUNGE	108	EXIST	8	EXIST	EXIST	EXIST	EXIST	P-3(B)	P-3(B)	SEE DOOR SCHEDULE NOTES #9,10,11,12,18
108A*	3'-0"x7'-0"	EXISTING LOUNGE	108	EXIST	2	EXIST	EXIST	EXIST	EXIST	P-3(B)	P-3(B)	SEE DOOR SCHEDULE NOTES #9,10,11,12,18
109*	3'-0"x7'-0"x1 3/4"	EXISTING ASSOCIATES TRAINING ROOM	109	EXIST	8	EXIST	EXIST	EXIST	EXIST	P-3(B)	P-3(B)	SEE DOOR SCHEDULE NOTES #9,10,11,12,18
110*	6'-0"x7'-0"x1 3/4"	EXISTING MECHANICAL ROOM	110	EXIST	2	EXIST	EXIST	EXIST	EXIST	FACTORY	FACTORY	SEE DOOR SCHEDULE NOTES #12,13
110A*	3'-0"x7'-0"x1 3/4"	EXISTING MECH. ROOM #2	110A	EXIST	2	EXIST	EXIST	EXIST	EXIST	P-3(B)	P-3(B)	SEE DOOR SCHEDULE NOTES #10,12
110B*	3'-0"x7'-0"x1 3/4"	EXISTING ELECTRICAL ROOM	110B	EXIST	2	EXIST	EXIST	EXIST	EXIST	P-4(B) PREP	PREP SIDE	SEE DOOR SCHEDULE NOTES #10,12
111*	3'-0"x7'-0"x1 3/4"	EXISTING JANITOR'S CLOSET	111	EXIST	2	EXIST	EXIST	EXIST	EXIST	P-3(B)	P-3(B)	SEE DOOR SCHEDULE NOTES #9,10,11,12,18
112*	PR 3'-0"x7'-0"x1 3/4"	EXISTING MEAT PREP	112	EXIST	12	EXIST	EXIST	EXIST	EXIST	P-4(B) PREP/P-3(B) SALES	FACTORY	SEE DOOR SCHEDULE NOTES #3,12
112A*	3'-6"x7'-0"x1 3/4"	EXISTING MEAT PREP	112	EXIST	11	EXIST	EXIST	EXIST	EXIST	P-4(B) PREP/P-3(B) SALES	FACTORY	SEE DOOR SCHEDULE NOTES #3,12- NEW WINDOW KIT
113*	3'-0"x7'-0"x1 3/4"	EXISTING MEAT OFFICE	113	EXIST	11	EXIST	EXIST	EXIST	EXIST	P-4(B)	FACTORY	SEE DOOR SCHEDULE NOTES #3,12
114*	3'-0"x7'-0"x1 3/4"	EXISTING DEPT. MGRS. OFFICE	114	EXIST	8	EXIST	EXIST	EXIST	EXIST	P-3(B)	P-3(B)	SEE DOOR SCHEDULE NOTES #9,10,11,12,18
115*	PR 3'-0"x7'-0"x1 3/4"	EXISTING PRODUCE PREP	115	EXIST	12	EXIST	EXIST	EXIST	EXIST	P-4(B) PREP/P-3(B) STAGING	FACTORY	SEE DOOR SCHEDULE NOTES #3,12
115A*	PR 3'-0"x7'-0"x1 3/4"	EXISTING PRODUCE PREP	115	EXIST	2	EXIST	EXIST	EXIST	EXIST	P-4(B) PREP/P-3(B) SALES	FACTORY	SEE DOOR SCHEDULE NOTES #3,12
115B*	3'-6"x7'-0"x1 3/4"	EXISTING PRODUCE PREP EXIT	115	EXIST	2	EXIST	EXIST	EXIST	EXIST	P-4(B) PREP/ EXT MATCH ADJ	P-4(B) PREP/ EXT MATCH ADJ	SEE DOOR SCHEDULE NOTES #9,10,11,12,18,20
116	PR 3'-0"x3'-6"x1 3/4"	EXISTING DELI/ BAKERY PREP	116	NEW	17	NEW	-	-	-	FACTORY	FACTORY	SEE DOOR SCHEDULE NOTES #1 WALL AND FLOOR MOUNTED
116C*	3'-0"x7'-0"x1 3/4"	EXISTING DELI/ BAKERY STORAGE	116C	EXIST	2	EXIST	EXIST	EXIST	EXIST	P-3(B)	P-3(B)	SEE DOOR SCHEDULE NOTES #9,10,11,12,18
117*	2'-4"x7'-0"x1 3/4"	EXISTING DELI/ BAKERY CLOSET	117	EXIST	2	EXIST	EXIST	EXIST	EXIST	P-3(B)	P-3(B)	SEE DOOR SCHEDULE NOTES #9,10,11,12,18

INTERPLAN
 ARCHITECTURE
 ENGINEERING
 INTERIOR DESIGN
 PROJECT MANAGEMENT

604 COURTLAND STREET
 SUITE 100
 ORLANDO, FLORIDA 32804
 PH 407.645.5008
 FX 407.629.9124

ARCHITECTS SEAL:
 LAUREL B. MARTIN
 Lic. No. 040108351
 FEB 13 2020

Order Plans @ WWW.INTERPLAN.COM

- DOOR SCHEDULE NOTES:**
- REFER TO FOOD LION SPECIFICATIONS & NATIONAL ACCOUNT REFERENCES FOR DOOR MANUFACTURERS.
 - GENERAL CONTRACTOR SHALL VERIFY ALL AUTOMATIC SLIDING DOOR OPENINGS WITH THE MANUFACTURER OR CONTRACTOR.
 - ALL PREP TRAFFIC DOORS TO RECEIVE "TEAR-DROP" BUMPERS ON BOTH SIDES OF THE DOOR. BUMPERS SUPPLIED BY DOOR MANUFACTURER.
 - NEW TRAFFIC DOORS TO RECEIVE GASKETS AROUND DOOR PERIMETER. GASKETS SUPPLIED BY DOOR MANUFACTURER. (REFER TO SCOPE OF WORK)
 - STORE NUMBER TO BE STENCILED (4" HIGH) TO TRUCK DRIVERS (DSD) DOOR IN PAINT COLOR CONTRASTING TO COLOR OF DOOR.
 - DOOR SCOPE TO BE PART NO. SOLD1 FROM WARNOK-HERSEY HARDWARE DISTRIBUTOR, (800) 632-1324.
 - PROVIDE 1/4" WIRE GLASS IN HALF GLASS DOOR WINDOW, APPLICABLE TO ALL OFFICES.
 - ALL EXTERIOR GLAZING @ AUTO DOORS TO BE 1/4" TEMPERED GLASS (COLOR- REFER TO GLAZING SCHEDULE), TO BE PROVIDED BY STOREFRONT CONTRACTOR.
 - GENERAL CONTRACTOR SHALL INSTALL KICKPLATES ON BOTH SIDES OF ALL HOLLOW METAL DOORS. (EXCEPTION- EXTERIOR SIDE EXTERIOR DOORS). REPLACE MISSING AND DAMAGED KICKPLATES.
 - THE GENERAL CONTRACTOR SHALL SAND, CLEAN, AND REPAINT ALL EXISTING HOLLOW METAL DOORS & FRAMES SCHEDULED FOR REUSE. THE GENERAL CONTRACTOR SHALL FURNISH NEW HOLLOW METAL FRAMES FOR THOSE DOORS TO BE RELOCATED. DOOR HARDWARE TO BE BROUGHT UP TO CURRENT FOOD LION STANDARDS. ALL EXTERIOR DOOR SWEEPS WILL BE REPLACED WITH PEMKO #18100CNB84. CONTRACTOR INSTALL & ORDER NEW DELAY EGRESS STICKERS FROM BA HOFT ONCE DOORS REPAINTED.
 - GENERAL CONTRACTOR SHALL INSTALL NEW DOOR SILENCERS ON ALL DOORS (AFTER PAINTING) AND COMMERCIAL GRADE KICK DOWNS ON ALL INTERIOR HOLLOW METAL DOORS. (EXCEPT WORKROOM WITH SAFE).
 - THE GENERAL CONTRACTOR SHALL VERIFY CONDITION OF ALL DOORS AND COORDINATE THE REUSE WITH THE FOOD LION CONSTRUCTION MANAGER.
 - DOCK DOORS, SEALS, DOCK LEVELER AND EQUIPMENT SHALL BE ORDERED FROM OVERHEAD DOOR AS PER FOOD LION SPECIFICATIONS. REFER TO NATIONAL ACCOUNT REFERENCE INFORMATION, SCOPE OF WORK, & COORDINATE W/ FOOD LION CONSTRUCTION MANAGER.
 - TRAFFIC DOORS TO BE ORDERED FROM CHASE DURAS AT HEFCO. REFER TO NATIONAL ACCOUNT INFORMATION.
 - HOLLOW METAL DOORS, FRAMES AND HARDWARE SHALL BE ORDERED FROM B.A. HOFT. GENERAL CONTRACTOR MUST ORDER NEW DELAY EGRESS STICKERS FROM B.A. HOFT ONCE THE DOORS ARE REPAINTED. REFER TO NATIONAL ACCOUNT INFORMATION.
 - ALL JAMB GUARDS, MISC ALUMINUM, STAINLESS STEEL, ETC BREAK METAL ITEMS SHALL BE FIELD VERIFIED, FABRICATED AND INSTALLED GENERAL CONTRACTOR.
 - GENERAL CONTRACTOR SHALL REPLACE MISSING OR DAMAGED WEATHER-STRIPPING, SWEEPS & NEW STYLE CARPET THRESHOLDS ON ALL EXTERIOR DOORS, ROLL-UP DOORS 5-3/8" BRUSH GASKET-WFR/MODEL: #H015642 BY NATIONAL GUARD.
 - G.C. TO ADJUST INTERIOR DOOR CLOSERS SO THAT NO MORE THAN 5 LBS OF FORCE IS REQUIRED TO OPERATE AND SO THAT DOORS GO FROM 90 DEGREE OPEN TO 12 DEGREE OPEN IN 5 SECONDS MIN.
 - REVERSE DOOR SWING USING ALUMINUM CONTINUOUS GEARED HINGE MODEL # A571HD BY ARCHITECTURAL BUILDERS HARDWARE MFG. INC. PATCH EXISTING HARDWARE CUT-OUTS IN DOOR FRAME.
 - EXTERIOR SIDE OF DOOR/FRAME TO BE PREPPED FOR PAINT AND REPAINTED TO MATCH EXISTING COLOR.

REVISIONS

NO	DATE	REMARKS

FOOD LION
 2119 Executive Drive, Salisbury, NC 28145
 Telephone: 781.633.8228
 foodlion.com
 Food Lion is a GEORGETOWN INDUSTRIES company.

FOOD LION REMODEL STORE #1208
 13490 DUMFRIES RD
 MANASSAS, VA 20112

PROJECT NO: 2019.0917
 DATE: 2-13-20
 20 OF 47
A6.02
 DOOR FINISH SCHEDULES
 CHECKED: JM DRAWN: EC

COPYRIGHT © 2020 INTERPLAN. REVISIONS COPYRIGHT © OTHER RIGHTS RESPECTING THIS DOCUMENT ARE TO THE ORIGINAL SITE OF EXPOSURE FOR WHICH THEY WERE PREPARED. REPRODUCTIONS, CHANGES OR ASSUMPTIONS ARE PROHIBITED.