ABBREVIATIONS LEGEND

A		F		M		S	
ACOUS	ACOUSTICAL	FIN	FINISH	MNFG.	MANUFACTURER	S	SOUTH
AC	AIR CONDITIONING	FFL	FINISHED FLOOR LINE	MH	MANHOLE	SG	SAFETY GLASS
AFF	ABOVE FINISHED FLOOR	FEC	FIRE EXTINGUISHER CABINET	MO	MASONRY OPENING	SCHED	SCHEDULE
ALUM	ALUMINUM	FHC	FIRE HOSE CABINET	MAX	MAXIMUM	SEC	SECTION/SECRETARY
ARCH	ARCHITECT	FR	FIRE RATED	MED	MEDIUM	SS	SERVICE SINK
AB	ANCHOR BOLTS	FL	FLOOR LINE OR FLOW LINE	MTL	METAL	SHT	SHEET
		FD	FLOOR DRAIN	MIN	MINIMUM	SIM	SIMILAR
B		FLOUR	FLUORESCENT	MR	MIRROR	SC	SOLID CORE
BES	BANK EQUIPMENT SUPPLIER	FT	FOOT/FEET	MISC	MISCELLANEOUS	SPKR	SPEAKER
BFF	BELOW FINISHED FLOOR	FTG	FOOTING	MULL	MULLION	SPECS	SPECIFICATIONS
BJ	BAR JOIST	FAS	FASTEN	MUNT	MUNTIN	SQ	SQUARE
BLK	BLOCK/BLOCKING	FEC	FIRE EXTINGUISHER CABINET	MC	MECHANICAL CONTRACTOR	SF	SQUARE FEET
BD	BOARD	FF	FINISH FLOOR	MECH	MECHANICAL	STD	STANDARD
BW	BOTH WAYS	FLR	FLOOR	MGR	MANAGER	SST	STAINLESS STEEL
BLDG	BUILDING	FLSG	FLASHING	ML	METAL LATH	STL	STEEL
BU ROOF	BUILT-UP ROOFING	FND	FOUNDATION	MLDG	MOULDING	STR	STRUCTURAL
BR	BULLET RESISTANT OR BACKER ROD	FOS	FACE OF STUD/STEEL	MT	METAL THRESHOLD	SUSP	SUSPENDED
		FRGWB	FIBER GLASS REINFORCED GYPSUM WALL BOARD	MTP	METAL TOILET PARTITION	SHLV	SHELVES/SHELVING
BB	BULLETIN BOARD					SHR	SHOWER
BL	BUILDING LINE	FRT	FIRE-RETARDANT-TREATED	N		ST	STREET
BM	BENCH MARK	FRP	FIBERGLASS REINFORCED PANELS	ND	NIGHT DEPOSIT	STA	STATION
BO	BOTTOM OF			NOM	NOMINAL	STO	STORAGE
BRM	BEDROOM	FTG	FOOTING	NIC	NOT IN CONTRACT		
BSMT	BASEMENT	FURN	FURNITURE	NTS	NOT TO SCALE	T	
				NO	NUMBER(#)	TEL	TELEPHONE
C		G		N	NORTH	TV	TELEVISION
CAB	CABINET	GA	GAGE, GAUGE			TEMP	TEMPERED
CPT	CARPET	GC	GENERAL CONTRACTOR	O		THK	THICK
CI	CAST IRON	GL	GLASS, GLAZING	OC	ON CENTER	TK	THINK
CLG	CEILING	GB	GRAB BAR	OPNG	OPENING	TPD	TOILET PAPER DISPENSER
CTR	CENTER	GR BM	GRADE BEAM	OPH	OPPOSITE HAND	TC	TOP OF CURB/CONCRETE
CLR	CLEAR(ANCE)	GR	GRADE, GRADING	OZ	OUNCE	TJ	TOP OF JOIST
CW	COLD WATER	GYP	GYPSUM	OD	OUTSIDE DIAMETER / DIMENSION	TS	TOP OF SLAB
CONC	CONCRETE	GAL	GALVANIZED			TO	TOP OF
CMU	CONCRETE MASONRY UNIT	GWB	GYPSUM WALLBOARD	OH	OVERHEAD	TOS	TOP OF STEEL
CONST	CONSTRUCTION					TYP	TYPICAL
CONT	CONTINUOUS OR CONTINUE	H		P		TD	TOWEL DISPENSER
CJ	CONTROL JOINT	HDW	HARDWARE	PG	PAGE	T	TREADS/TOILET
CB	CATCH BASIN/CHALKBOARD	HTG	HEATING	PNT	PAINT	TB	TACKBOARD
CEM	CEMENT	HT	HEIGHT	PART	PARTITION	TH	TEST HOLE
CLO	CLOSET	HM	HOLLOW METAL	PVMT	PAVEMENT		
COL	COLUMN	HOR	HORIZONTAL	/	PER	U	
CONN	CONNECTION	HB	HOSE BIBB	%	PERCENT	UL	UNDERWRITERS LABORATORY
CG	CORNER GUARD	HW	HOT WATER	PC	PIECE	UNO	UNLESS NOTED OTHERWISE
CT	CERAMIC TILE	H	HIGH	P.LAM	PLASTIC LAMINATE	UCR	UNDER COUNTER REFRIGERATOR
C&R	CURTAIN AND ROD	HC	HOLLOW CORE	PLMB	PLUMBING		
CWS	CURTAIN WALL STUDS			PVC	POLYVINYL CHLORIDE	V	
		I		PPT	PRESSURE PRESERVATIVE TREATED	VAR	VARIABLE
D		IN	INCH (")	PTDD	PAPER TOWEL DISPENSER & DISPOSAL	VOL	VOLUME
DIM	DIMENSION	ID	INSIDE DIAMETER DIMENSION	PCC	PRECAST CONCRETE	VB	VAPOR BARRIER
DW	DISHWASHER	INFO	INFORMATION	PE	PORCELAIN ENAMEL	VCGB	VINYL COVERED GYPSUM BOARD
DSP	DISPOSAL	INS	INSULATION	PL	PLASTER/PLASTIC LAMINATE	VERT	VERTICAL/VERTICALLY
DR	DOOR	INT	INTERIOR	PTD	PAPER TOWEL DISPENSER	VEST	VESTIBULE
DN	DOWN					VWC	VINYL WALL COVERING
DS	DOWNSPOUT	J		R			
DWG	DRAWING	JAN	JANITOR'S CLOSET	R	RADIUS	W	
DF	DRINKING FOUNTAIN	JS	JANITOR'S SINK	RE	REFERENCE	WSCT	WAINSCOT
DA	DOUBLE ACTION	JT	JOINT	REF	REFRIGERATOR	WC	WATER CLOSET
DEPT	DEPARTMENT	JST	JOIST	RA	RETURN AIR	WH	WATER HEATER
DET	DETAIL	JB	JUNCTION BOX	RH	RIGHT HAND	WP	WATERPROOFING
DIA	DIAMETER			RHR	RIGHT HAND REVERSE	WS	WATERSTOP / WEATHERSTRIP
DO	DOOR ACTION	K		ROW	RIGHT OF WAY	WT	WEIGHT
DP	DAMPROOFING	KPL	KICKPLATE	RD	ROOF DRAIN	WWM	WELDED WIRE MESH (FABRIC)
DW	DUMBWAITER			RFG	ROOFING	W	WIDE
D/W	DISHWASHER	L		RO	ROUGH OPENING	WW	WINDOW WALL
DWS	DRYWALL STUDS	LAM	LAMINATE	REG	REGISTER	W/	WITH
		LAV	LAVATORY	REINF	REINFORCING	WO	WITHOUT
E		LAB	LABORATORY	REQ	REQUIRED	WD	WOOD
EA	EACH	LH	LEFT HAND			W	WEST
EL	ELEVATION	LHR	LEFT HAND REVERSE			WDIM	WINDOW DIMENSION
ELEV	ELEVATOR	LT	LIGHT			WDW	WINDOW
EQ	EQUAL	LWF	LIGHT WEIGHT FILL			WWF	WELDED WIRE FABRIC
EQUIP	EQUIPMENT	LR	LIVING ROOM				
EXH	EXHAUST	LVR	LOUVER				
EF	EXHAUST FAN	LB	POUND				
EJ	EXPANSION JOINT	LKR	LOCKER				
EXT	EXTERIOR	LL	LEAD LINED				
EIFS	EXTERIOR INSULATING FINISH SYSTEM	LOC	LIMITS OF CONSTRUCTION				
		LWCMU	LIGHT WEIGHT CONCRETE MASONRY UNIT				
E	EAST						
EC	ELECTRICAL CONTRACTOR						
EIF	EXTERIOR INSULATING FINISH						
ELEC	ELECTRICAL						
EP	ELECTRICAL PANEL						
EWC	ELECTRIC WATER COOLER						
EXP	EXPOSED						

TYPICAL REFERENCE



MATERIALS LEGEND



ENVELOPE COMCHECK

COMcheck Software Version 4.1.2.0

Envelope Compliance Certificate

Project Information

Energy Code:	2015 IECC
Project Title:	Comprehensive Healthcare
Location:	Atlanta, Georgia
Climate Zone:	3a
Project Type:	New Construction
Vertical Glazing / Wall Area:	24%

Construction Site: South Fulton, GA 30213

Owner/Agent: South Fulton, GA

Designer/Contractor: JBG Architects, Peachtree City, GA 30269

Additional Efficiency Package(s)

High efficiency HVAC. Systems that do not meet the performance requirement will be identified in the mechanical requirements checklist report.

Building Area	Floor Area
1-Office : Nonresidential	27178

Envelope Assemblies

Assembly	Gross Area or Perimeter	Cavity R-Value	Cont. R-Value	Proposed U-Factor	Budget U-Factor(a)
ROOFING - FLAT TPO: Insulation Entirely Above Deck: High Alberdo Roof Required, 3-Year-Aged Solar Reflectance = 0.70, Thermal Emittance = 0.86 (d), [Bldg. Use 1 - Office]	6316	---	25.0	0.028	0.039
ROOF - SLOPED ATTIC: Attic Roof with Steel Joists. [Bldg. Use 1 - Office]	5273	38.0	0.0	0.035	0.027
Floor 2: Slab-On-Grade:Unheated, [Bldg. Use 1 - Office] (c)	520	---	---	0.730	0.730
NORTH					
SIDE 1: Steel-Framed, 16" o.c., [Bldg. Use 1 - Office]	3203	19.0	0.0	0.109	0.064
Window 7: Metal Frame:Fixed, Perf. Specs.: Product ID NA, SHGC 0.25, VT 0.72, [Bldg. Use 1 - Office] (b)	305	---	---	0.290	0.460
Window 8: Metal Frame:Fixed, Perf. Specs.: Product ID NA, SHGC 0.25, VT 0.72, [Bldg. Use 1 - Office] (b)	265	---	---	0.290	0.460
EAST					
REAR: Steel-Framed, 16" o.c., [Bldg. Use 1 - Office]	4279	19.0	0.0	0.109	0.064
Door 2: Glass (> 50% glazing):Metal Frame, Entrance Door, Perf. Specs.: Product ID NA, SHGC 0.25, VT 0.72, [Bldg. Use 1 - Office] (b)	48	---	---	0.290	0.770
Door 3: Insulated Metal, Swinging, [Bldg. Use 1 - Office]	25	---	---	0.[illegible]	0.610
Window 4: Metal Frame:Fixed, Perf. Specs.: Product ID NA, SHGC 0.25, VT 0.72, [Bldg. Use 1 - Office] (b)	559	---	---	0.[illegible]	0.460
Window 5: Metal Frame:Fixed, Perf. Specs.: Product ID NA, SHGC 0.25, VT 0.72, [Bldg. Use 1 - Office] (b)	484	---	---	0.290	0.460
Window 6: Metal Frame:Fixed, Perf. Specs.: Product ID NA, SHGC 0.25, VT 0.72, [Bldg. Use 1 - Office] (b)	11	---	---	0.290	0.460
SOUTH					
SIDE 2: Steel-Framed, 16" o.c., [Bldg. Use 1 - Office]	1[illegible]	19.0	0.0	0.109	0.064

Assembly	Gross Area or Perimeter	Cavity R-Value	Cont. R-Value	Proposed U-Factor	Budget U-Factor(a)
Window 9: Metal Frame:Fixed, Perf. Specs.: Product ID NA, SHGC 0.25, VT 0.72, [Bldg. Use 1 - Office] (b)	305	---	---	0.290	0.460
Window 10: Metal Frame:Fixed, Perf. Specs.: Product ID NA, SHGC 0.25, VT 0.72, [Bldg. Use 1 - Office] (b)	265	---	---	0.290	0.460
Door 4: Insulated Metal, Non-Swinging, [Bldg. Use 1 - Office]	125	---	---	0.560	0.179
WEST					
FRONT: Steel-Framed, 16" o.c., [Bldg. Use 1 - Office]	4279	19.0	0.0	0.109	0.064
Window 1: Metal Frame:Fixed, Perf. Specs.: Product ID NA, SHGC 0.25, VT 0.72, [Bldg. Use 1 - Office] (b)	611	---	---	0.290	0.460
Window 2: Metal Frame:Fixed, Perf. Specs.: Product ID NA, SHGC 0.25, VT 0.72, [Bldg. Use 1 - Office] (b)	538	---	---	0.290	0.460
Window 3: Metal Frame:Fixed, Perf. Specs.: Product ID NA, SHGC 0.25, VT 0.72, [Bldg. Use 1 - Office] (b)	112	---	---	0.290	0.460
Door 1: Glass (> 50% glazing):Metal Frame, Entrance Door, Perf. Specs.: Product ID NA, SHGC 0.25, VT 0.72, [Bldg. Use 1 - Office] (b)	48	---	---	0.290	0.770

(a) Budget U-factors are used for software baseline calculations ONLY, and are not code requirements.
(b) Fenestration product performance must be certified in accordance with NFRC and requires supporting documentation.
(c) Slab-On-Grade proposed and budget U-factors shown in table are F-factors.
(d) High albedo roof requirement options: 1) 3-year aged solar reflectance >= 0.55 thermal emittance >= 0.75, 2) 3-year aged solar reflectance index >= 64.0, 3) Initial year aged solar reflectance >= 0.70 thermal emittance >= 0.75, 4) Initial year aged solar reflectance index >= 82.0

Envelope PASSES: Design 1% better than code

Envelope Compliance Statement

Compliance Statement: The proposed envelope design represented in this document is consistent with the building plans, specifications, and other calculations submitted with this permit application. The proposed envelope systems have been designed to meet the 2015 IECC requirements in COMcheck Version 4.1.2.0 and to comply with any applicable mandatory requirements listed in the Inspection Checklist.

Paul Gresham - Architect of Record — Name - Title
Signature
3/27/2020 — Date

GENERAL NOTES

JEFFERSON BROWNE GRESHAM ARCHITECTS, INC. IS NOT RESPONSIBLE FOR QUALITY OF COPIES MADE FROM DOCUMENTS PROVIDED BY ARCHITECT.

A. CONTRACTOR / BIDDER TO VISIT SITE AND FIELD VERIFY EXISTING CONDITIONS PRIOR TO BIDDING.

B. CONTRACTOR IS RESPONSIBLE FOR CHECKING ALL FIELD CONDITIONS, AND DIMENSIONS FOR ACCURACY AND CONFIRMING THAT WORK IS BUILDABLE AS SHOWN PRIOR TO PROCEEDING WITH CONSTRUCTION. OBTAIN CLARIFICATION FROM THE ARCHITECT OF RECORD AT JEFFERSON BROWNE ARCHITECTS IF THERE ARE ANY QUESTIONS OR DISCREPANCIES.

C. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO PROVIDE ALL NECESSARY BRACING, SHORING, AND OTHER SAFEGUARDS TO MAINTAIN ALL PARTS OF THE EXISTING WORK IN A SAFE CONDITION DURING THE PROCESS OF DEMOLITION AND CONSTRUCTION AND TO PROTECT FROM DAMAGE, DUST AND DEBRIS DURING DEMOLITION AND CONSTRUCTION.

D. CONTRACTOR SHALL PROVIDE ALL LABOR, MATERIALS, TOOLS, AND INCIDENTAL PARTS AND MATERIALS FOR A COMPLETE OPERATIVE INSTALLATION.

E. THOSE ITEMS NOTED N.I.C. (NOT IN CONTRACT), OR NOTED TO BE PERFORMED BY OTHERS, SHALL BE COORDINATED IN A MUTUALLY AGREEABLE AND COOPERATIVE MANNER WITH ALL INVOLVED DICIPLINES BY THE CONTRACTOR SO AS TO ALLOW TIMELY INTEGRATION INTO THE PROJECT AS REQUIRED.

F. UNLESS NOTED OTHERWISE, MOVING OF FURNITURE, FURNISHINGS, AND EQUIPMENT SHALL BE PERFORMED BY OWNER / TENANT COORDINATE TIMING WITH REPRESENTATIVE.

G. GENERAL CONTRACTOR COORDINATE WITH OWNER OR TENANT AND OBTAIN WRITTEN APPROVAL TO MINIMIZE CONSENT AND IN ADVANCE, THE CONSTRUCTION SCHEDULE AND DURATION, INCLUDING ANY REQUIRED BUILDING SYSTEM INTERRUPTIONS.

H. MAINTAIN A JOB SITE SET OF CONSTRUCTION DOCUMENTS AND, THESE, RECORD ANY DEVIATIONS FROM THE ORIGINAL PLANS, LOCATE CONCEALED PLUMBING PIPING, AND SYSTEMS IN-INS, AND AS BUILT SET OVER TO OWNER / ARCHITECT UPON COMPLETION OF PROJECT.

I. CONFINE CONSTRUCTION ACTIVITIES TO DESIGNATED CONSTRUCTION AREAS ONLY, STAGING AND STORAGE IN CONSTRUCTION AREA(S) OR, IF ADDITIONAL SPACE IS REQUIRED, IN OWNER / TENANT DESIGNATED AREAS OR ROOM, SUPPLY AND REMOVAL OF MATERIALS BY PRIOR APPROVED ROUTES ONLY, USE PROTECTION PADS WHEN USING ELEVATOR(S) (WHEN APPLICABLE)

J. ALL DEMOLISHED MATERIALS SHALL BE DISPOSED OF OFF-SITE BY CONTRACTOR, UNLESS NOTED OTHERWISE.

K. CLEAN CONSTRUCTION AREAS THOROUGHLY UPON COMPLETION. DO NOT USE BUILDING DUMPSTERS. DISPOSE OF DEBRIS IN ACCORDANCE WITH LOCALLY APPROVED REGULATIONS. IF REQUIRED, USE ELEVATOR ONLY AFTER BUILDING HOURS. (WHEN APPLICABLE)

L. ALL WORK SHALL BE PERFORMED IN COMPLIANCE WITH ALL APPLICABLE CODES AND REGULATIONS, INCLUDING COUNTY BUILDING CODE, N.E.C., A.D.A.A.G. AND STATE ACCESSIBILITY STANDARDS FOR THE ELIMINATION OF ARCHITECTURAL BARRIERS, CURRENT AS OF DATE OF ISSUANCE OF THESE DOCUMENTS.

M. LOCATE THE TOP OF ALL NEW AND RELOCATED SWITCHES AND CONTROLS AT 45" O.C. A.F.F. U.N.O.

N. LOCATE ALL NEW EXPOSED WALL OUTLETS AT 18" O.C. A.F.F., U.N.O. WHEN APPLICABLE OUTLETS IN FLOOR CABINETS SHALL BE AT 18" O.C. A.F.F.

O. ALL DIMENSIONS SHOWN ARE FRAMING TO FRAMING, U.N.O.

P. IT IS THE INTENT THAT SPECIFIED PRODUCTS ARE TO BE USED ON THIS PROJECT. THEY WERE SELECTED AS PART OF THE DESIGN CONCEPT. ARCHITECT WILL ONLY ANALYZE PROPOSED SUBSTITUTIONS THAT WILL BENEFIT THE OWNER BY A SIGNIFICANTLY LOWER COST OR AN IMPROVED QUALITY, OR IN THE CASE OF PRODUCT UNAVAILABILITY OR OTHER CONDITIONS BEYOND THE CONTROL OF THE CONTRACTOR. IF ANY SUBSTITUTION AFFECTS A CORRELATED FUNCTION, ADJACENT CONSTRUCTION, OR WORK OF OTHER TRADES OR CONTRACTORS, THE NECESSARY CHANGES AND MODIFICATIONS SHALL BE CONSIDERED AN ESSENTIAL PART OF THE PROPOSED SUBSTITUTION, TO BE ACCOMPLISHED BY CONTRACTOR WITHOUT ADDITIONAL EXPENSE TO THE OWNER IF AND WHEN ACCEPTED.

Q. SUBMIT SHOP DRAWINGS / PRODUCT INFORMATION / SAMPLES OF SPECIFIED PRODUCTS. FABRICATIONS SHALL BEGIN ONLY AFTER APPROVED SHOP DRAWINGS HAVE BEEN RETURNED BY ARCHITECT TO CONTRACTOR.

R. CONTRACTOR SHALL SUBMIT CONFIRMATION OF DELIVERY DATES OF PRODUCTS WITH LONG LEAD TIMES WITH PRODUCT SUBMITTALS.

S. INSTALL ALL MANUFACTURED ITEMS, MATERIALS, AND EQUIPMENT IN STRICT ACCORDANCE WITH SPECIFIC MANUFACTURER'S WRITTEN SPECIFICATIONS, RECOMMENDATIONS AND INSTRUCTIONS.

T. CONTRACTORS SHALL CONFINE THEMSELVES TO CONSTRUCTION AREAS. CONSTRUCTION PARKING ONLY IN PRIOR DESIGNATED LOCATIONS.

U. CONTRACTOR SHALL BE PERMITTED TO USE BUILDING ELECTRICITY AND WATER TO A REASONABLE EXTENT. PROVIDE OWN SOURCES FOR EXCESSIVE CONSTRUCTION POWER REQUIREMENTS. DO NOT USE RESTROOMS FOR TOOL, BRUSH, ETC. CLEANING. USE DESIGNATED CLEAN UP FACILITIES ONLY.

V. PRIOR TO COMMENCING WORK, CONTRACTOR SHALL, ACCOMPANIED BY REPRESENTATIVE BUILDING MANAGEMENT, TAKE AND DOCUMENT INVENTORY OF EXISTING FINISHES AND SYSTEMS TO REMAIN IN CONSTRUCTION AREA, AND ESTABLISH ANY EXISTING DAMAGE. ANY SUBSEQUENT DAMAGE ATTRIBUTABLE TO CONSTRUCTION ACTIVITIES SHALL BE REPAIRED TO COMPENSATED FOR BY CONTRACTOR.

W. FIRE STOP ALL EXISTING AND NEW FLOOR PENETRATIONS IN PROJECT AREAS.

X. ALL PERMITS, LICENSES AND INSPECTIONS REQUIRED TO PERFORM AND COMPLETE WORK SHALL PAID FOR BY CONTRACTOR.

Y. OBTAIN A COPY OF MANAGEMENT CONSTRUCTION RULES PRIOR TO BIDDING FOR ADDITIONAL AND UPDATED REQUIREMENTS AND RESTRICTIONS ABIDE BY THESE RULES AT ALL TIMES.

Z. WELDING TO AND WITHIN AN EXISTING FACILITY PRESENTS POTENTIAL HAZARDS INCLUDING:
1. FIRE HAZARD DUE TO THE EXISTING CONSTRUCTION AND BUILDING CONTENTS.
2. STRUCTURAL LIQUEFACTION DUE TO WELDING ACROSS THE FULL SECTION OF STRUCTURAL STEEL MEMBERS.
- RECOMMENDATIONS TO PREVENT THESE HAZARDS INCLUDE:
  a. FIRE HAZARD-PROTECT EXISTING COMBUSTIBLES PRIOR TO WELDING. KEEP A SEPARATE WATCHMAN AND SEVERAL FIRE EXTINGUISHERS ON HAND.
  b. STRUCTURAL LIQUEFACTION-WELD IN SMALL INCREMENTS. ALLOW WELDS TO HARDEN BEFORE CONTINUING TO THE NEXT INCREMENT.
  c. DO NOT LEAVE THE SITE UNTIL SATISFIED THAT NO FIRE HAZARD EXISTS.

AA. FIRE EXTINGUISHERS SHALL BE SELECTED, INSTALLED AND MAINTAINED IN ACCORDANCE WITH IFC AND NFPA 10

PARTITION NOTES

1. PENETRATIONS THROUGH WALLS SHALL CONTAIN CONTINUOUS FIRESTOPPING THROUGH FIRE RATED PARTITION OR CONTINUOUS ACOUSTICAL SEALANT THROUGH NON-RATED PARTITIONS

2. ALL WET ROOMS AND WET AREA SHALL BE CONSTRUCTED WITH ⅝" DENS SHIELD TILE BACKER BOARD WHERE TILE IS USED. ALL WET ROOMS AND WET AREAS WITHOUT TILE TO USE MOISTURE RESISTANT GYPSUM BOARD

3. ALL RATED GYPSUM BOARD PARTITION WILLS USE FIRECODE GYPSUM BOARD AND BE CONSTRUCTED IN STRICT ACCORDANCE WITH THE DESIGN UL CONSTRUCTION.

4. INSTALL ⅝" GYPSUM BOARD THROUGHOUT AND CONFIRM A SMOOTH AND LEVEL PAINT READY WALL SURFACE IS INSTALLED.

Order Plans @ WWW.LDILine.com

JBG
JEFFERSON BROWNE GRESHAM ARCHITECTS
150 HUDDLESTON ROAD, SUITE 1000
PEACHTREE CITY, GEORGIA 30269
770 - 638 - 9345
JEFFERSONBROWNEARCHITECTS.COM

REVISIONS

NO.	DESCRIPTION

RENEWED MEDICAL BUILDING
CORE & SHELL ONLY

SOUTH FULTON, GEORGIA
PROJECT #19-2883

PROJECT

STATE OF GEORGIA
PAUL LEE GRESHAM
CERTIFICATE NO. 019611
REGISTERED ARCHITECT
3/27/2020

SEAL

MARCH 27, 2020

PERMIT SET

RELEASE DATE

GENERAL NOTES AND COMCHECK

DRAWING TITLE

© COPYRIGHT 2020 JEFFERSON BROWNE GRESHAM ARCHITECTS, INC. THIS DOCUMENT AS AN INSTRUMENT OF SERVICE REMAINS THE PROPERTY OF JEFFERSON BROWNE GRESHAM ARCHITECTS AND NO PART THEREOF MAY BE REPRODUCED IN ANY FORM WITHOUT WRITTEN PERMISSION FROM JEFFERSON BROWNE GRESHAM ARCHITECTS.

Drawn By: JC
Checked By: PGG, JLB
PROJECT # 19-2883

A-002

SHEET 02 of 37