

PLAN KEY NOTES

- 1 MENU BOARDS & MENU BOARD LIGHT FIXTURE -- REFER TO 1/A-8.2 FOR ADDITIONAL INFORMATION.
- 2 KITCHEN EXHAUST HOOD -- COORDINATE WITH MECHANICAL AND MANUFACTURER'S DRAWINGS
- 3 NOT USED
- 4 NOT USED
- 5 CENTER GRID IN CEILING AREA AS SHOWN.
- 6 GYPSUM BOARD SOFFIT ABOVE SERVING COUNTER -- SEE 2/A-3 FOR ADDITIONAL INFORMATION.
- 7 AWNING CENTERED OVER WINDOW, UNLESS NOTED OTHERWISE.
- 8 ALUMINUM CANOPY AT DOOR WITH INTEGRAL LIGHT FIXTURE TO BE CIRCUITED W/ EMERGENCY LIGHTS -- G.C. TO REFER TO VENDOR FOR ADDITIONAL INFORMATION.
- 9 ALUMINUM CANOPY AT DRIVE-THRU WINDOW WITH INTEGRAL LIGHT FIXTURES -- G.C. TO REFER TO VENDOR FOR ADDITIONAL INFORMATION, TYP. PRE-MANUFACTURED COOLER/FREEZER WALK-IN BOX CEILING INCLUDING
- 10 LIGHT FIXTURES, TYP.
- 11 EXTERIOR TUBE LIGHTING AT PORTHOLE ABOVE ROOF -- REFER TO A-6 FOR ADDITIONAL INFORMATION.
- 12 REFER TO STRUCTURAL DRAWINGS FOR HOOD SUSPENSION DETAILS.
- 13 NOT USED
- 14 ALL EXTERIOR SIGN / AWNING LIGHTS TO BE CENTERED OVER WINDOW, UNLESS NOTED OTHERWISE. REFER TO EXTERIOR ELEVATIONS FOR MOUNTING HEIGHTS.
- 15 FIXTURE PREINSTALLED IN CANOPY, CONTAINS WHIP FOR CONNECTION BY GC.

GENERAL NOTES


- 1. CONTRACTOR TO STUDY AND COMPARE THE REFLECTED CEILING PLANS WITH THE MECHANICAL AND ELECTRICAL DRAWINGS FOR LUMINARIES, DIFFUSERS, AND GRILLES. REPORT TO THE ARCHITECT ANY ERROR, INCONSISTENCY, OR OMISSION DISCOVERED.
- 2. CONTRACTOR TO VERIFY AND PROVIDE ACCESS PANELS OF APPROPRIATE SIZE AND TYPE ARE INSTALLED IN GYPSUM BOARD CEILING/SOFFITS OR ANY OTHER NON-ACCESSIBLE TYPE CEILING OR SOFFITS WHERE ACCESS, SERVICE OR ADJUSTMENT TO MECHANICAL, PLUMBING, OR ELECTRICAL ITEMS MAY BE REQUIRED. ACCESS PANELS SHALL BE FIRE RATED EQUAL TO THE RATING OF CEILING OR SOFFIT IN WHICH THEY OCCUR.
- 3. DIFFUSERS, INCANDESCENT LUMINARIES, AND OTHER SURFACE-MOUNTED OR RECESSED CEILING ITEMS SHALL BE LOCATED IN THE CENTER OF THE CEILING PANELS, UNLESS NOTED OTHERWISE.
- 4. THE ELECTRICAL CONTRACTOR SHALL FURNISH AND INSTALL ALL REQUIRED ACCESSORIES, OPTIONS, MOUNTING HARDWARE, AND FIELD FABRICATION REQUIRED TO PROPERLY ADAPT THE FIXTURES TO THE SPECIFIC APPLICATIONS.
- 5. LAY-IN LIGHTING FIXTURES SHALL NOT RELY ON THE CEILING SYSTEM ALONE FOR SUPPORT. LAY-IN LIGHTING FIXTURES SHALL BE SUPPORTED FROM THE STRUCTURE BY NO LESS THAN TWO HANGER WIRES AND SECURED TO THE CEILING GRID SYSTEM WITH THE APPROPRIATE SCREW HARDWARE.
- 6. CUT OUTS AT FIXTURES IN LAY-IN CEILING SHALL BE PRECISE WITH NO GAPS, CHIPS OR IRREGULARITIES.
- 7. CEILING GRID SHALL BE LEVEL WITHIN A TOLERANCE OF 1/8" IN A SPAN OF 10'-0"
- 8. SEE ELECTRICAL AND MECHANICAL DRAWINGS FOR ADDITIONAL REQUIREMENTS AND SPECIFICATIONS.
- 9. ALL DIMENSIONS ARE TO FINISH (THIS SHEET), UNLESS NOTED OTHERWISE.
- 10. ALL RETURN DIFFUSERS, SUPPLY DIFFUSERS, AND SPEAKERS TO BE PRE-FINISHED TO MATCH CEILING TILES IN CUSTOMER AREAS (DINING, ORDER AREAS, AND RESTROOM AREAS)
- 11. REFER TO ROOF PLAN AND EXTERIOR ELEVATIONS FOR ALL EXTERIOR LIGHT FIXTURES, TYP.
- 12. ALL PENDANT LIGHT FIXTURES TO BE CENTERED OVER TABLE BELOW. -- REFER TO INTERIOR ELEVATIONS FOR ADDITIONAL INFORMATION.
- 13. ALL GYP BOARD CEILING / GYP BOARD SOFFITS ARE TO BE 5/8" TYP.

LIGHTING LEGEND

	REMOTELY MOUNTED EXTERIOR EMERGENCY LIGHT
	WALL WASHER -- LOCATE IN CEILING TILE AS SHOWN
	RECESSED LED CAN LIGHTS
	RECESSED LED CAN LIGHT FIXTURE ON NIGHT LIGHT CIRCUIT
	PENDANT LIGHT FIXTURE -- MOUNT AT 5'-6" AFF AND CENTER OVER TABLE, UNLESS NOTED OTHERWISE
	WALL PACK
	EMERGENCY LIGHT FIXTURE
	2'X4' RECESSED TROFFER FIXTURE W/ ACRYLIC LENS
	2'X4' RECESSED TROFFER FIXTURE W/ ACRYLIC LENS AND DIFFUSER
	EMERGENCY / EXIT COMBO LIGHT FIXTURE
	EXTERIOR CANOPY LIGHT FIXTURE
	EXTERIOR AWNING / SIGN LIGHTING LOCATED ABOVE AWNING
	EXTERIOR PORTHOLE TUBE LIGHTING FIXTURE
	SUPPLY AIR DIFFUSER -- 2'X2' SUPPLY
	RETURN AIR GRILLE -- 2'X2' RETURN
	E.G. EXHAUST GRILLE
	2X4 LAY-IN CEILING
	GYPSUM BOARD CEILING
	CEILING HEIGHT A.F.F. CEILING TYPE/FINISH


CEILING FINISHES

CL-1	2' X 2' LAY-IN CEILING
CL-2	2' X 4' SCRUBBABLE LAY-IN CEILING
CL-3	2' X 2' SCRUBBABLE LAY-IN CEILING
P-#	PAINT: SEE FINISH SCHEDULE ON SHEET A-7 FOR LISTING OF PAINT FINISHES. (# REPRESENTS SPECIFIC PAINT NUMBER)
NOTES: 1. SEE FINISH SCHEDULE ON SHEET A-7 FOR ADDITIONAL INFORMATION, TYP.	



2 SOFFIT DETAIL @ SERVICE COUNTER

A-3 SCALE: 1 1/2" = 1'-0"



1 REFLECTED CEILING PLAN


A-3 SCALE: 1/4" = 1'-0"

SEISMIC DESIGN NOTES:

IN LOCATIONS WHERE SEISMIC CONDITIONS DICTATE COMPLIANT CEILING SUSPENSION SYSTEMS AND LIGHT FIXTURE / CEILING MOUNTED EQUIPMENT SUPPORT, THE GENERAL CONTRACTOR SHALL PROVIDE AND INSTALL SAID SYSTEMS AND INCLUDE THE ASSOCIATED COSTS IN HIS/HER BID. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING SEISMIC SUSPENSION SYSTEM REQUIREMENTS WITH ASSOCIATED TRADES. REFER TO A-9.2 FOR ADDITIONAL INFORMATION.



A NEW LOCATION FOR
CAPTAIN D'S
 7525 STATE AVENUE
 KANSAS CITY, KS 66112
CAPTAIN D'S, LLC
 624 GRASSMERE PARK DRIVE,
 SUITE 30
 NASHVILLE, TN 37211



Job Number:

Revisions:

A-3
REFLECTED
CEILING PLAN