

# ELECTRICAL SPECIFICATIONS

## DIVISION 16 - ELECTRICAL SPECIFICATIONS

### PART I. GENERAL PROVISIONS

- SCOPE: PROVIDE ALL LABOR, MATERIAL, AND EQUIPMENT IN ACCORDANCE WITH THESE SPECIFICATIONS, AND THE ACCOMPANYING DRAWINGS TO PROVIDE A COMPLETE AND PROPERLY OPERATING ELECTRICAL SYSTEM FOR THE BUILDING.
- THE CONTRACTOR SHALL FURNISH AND INSTALL ALL OF THE FOLLOWING MATERIAL AND EQUIPMENT UNDER THIS DIVISION OF THE SPECIFICATIONS, UNLESS NOTED OTHERWISE: PANELBOARDS; LIGHTING FIXTURES, LAMPS, RACEWAYS, 600 VOLT WIRE AND CABLE; WIRING DEVICES, DEVICE PLATES, DEVICE, PULL, AND JUNCTION BOXES; SAFETY SWITCHES; MOTOR STARTERS; LIGHTING CONTROLS; CIRCUIT BREAKERS; FUSES; TIME CLOCKS; EQUIPMENT IDENTIFICATION (NAMEPLATES AND DIRECTORIES); WIRE AND CABLE TERMINATIONS; CONNECTIONS TO INDIVIDUAL UNITS OF EQUIPMENT FOR THE WALK-IN FREEZERS AND COOLERS; AND TEMPORARY POWER.
- THE FOLLOWING MATERIAL AND EQUIPMENT WILL BE FURNISHED AND/OR INSTALLED BY OTHERS, OR UNDER OTHER DIVISIONS OF THE SPECIFICATIONS, UNLESS NOTED OTHERWISE: LOW VOLTAGE (24 VOLT) WIRE AND CABLE, COMMUNICATION DEVICES, SECURITY EQUIPMENT, POINT OF SALE (POS) EQUIPMENT, SIGNAGE, CONCRETE BASES FOR SITE LIGHTING POLES.
- THE FOLLOWING MATERIAL AND EQUIPMENT WILL BE FURNISHED BY OTHERS, OR UNDER OTHER DIVISIONS OF THE SPECIFICATIONS, AND INSTALLED BY THE CONTRACTOR, UNLESS NOTED OTHERWISE: SITE LIGHTING FIXTURES AND POLES.
- GENERAL REQUIREMENTS: ALL WORK SHALL BE PERFORMED BY SKILLED LICENSED ELECTRICIANS IN ACCORDANCE WITH THE BEST PRACTICES OF THE TRADE, MEETING THE REQUIREMENTS OF THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE 2011 EDITION, APPLICABLE FEDERAL, STATE AND LOCAL CODES, AND THE REQUIREMENTS OF THE ELECTRICAL UTILITY COMPANY. FURNISHING THE SERVICES, NECESSARY INSPECTION PERMITS AND CERTIFICATES OF INSPECTION SHALL BE PURCHASED AND OBTAINED UNDER THIS CONTRACT.
- COORDINATION: ALL OUTLETS MUST BE ACCURATELY LOCATED, PARTICULARLY APPLIANCE OUTLETS WHICH SHALL BE LOCATED FROM THE DIMENSIONED DRAWING AND FIELD VERIFIED. REVIEW THE ARCHITECTURAL, PLUMBING AND HEATING AND VENTILATING PLANS IN ORDER TO COORDINATE THIS WORK WITH OTHER TRADES, AND COOPERATE WITH THEM IN THE ENTIRE INSTALLATION.
- SERVICE VOLTAGE: THESE DRAWINGS ARE FOR A METERED, UNDERGROUND BUILDING SERVICE OF 120/208 VOLT, THREE PHASE, FOUR WIRE, 60 HERTZ. ALL KITCHEN AND AIR CONDITIONING EQUIPMENT HAS BEEN DESIGNED AND PURCHASED FOR USE ON THIS ELECTRICAL SYSTEM. THE CONTRACTOR SHALL CONTACT THE ELECTRICAL UTILITY AND VERIFY ALL OF THE ABOVE SERVICE CHARACTERISTICS, AND THE AVAILABLE FAULT CURRENT.
- SERVICE EQUIPMENT: THE SERVICE SHALL BE LOCATED AS SHOWN ON THE SITE PLAN, OR AS INDICATED IN THE INSTRUCTIONS TO BIDDERS. UTILITY POLES, PADS FOR UTILITY TRANSFORMERS, CURRENT TRANSFORMER ENCLOSURES, METERING EQUIPMENT, SERVICE MASTS, AND OTHER RELATED MATERIALS AND EQUIPMENT SHALL BE APPROVED, FURNISHED, AND INSTALLED AS REQUIRED. INCLUDE THE COST OF ALL THE ABOVE ITEMS. SERVICE CONNECTIONS, AND METER CHARGES IN THE BASE BID. MAIN SERVICE SWITCHES AND CURRENT TRANSFORMER CABINETS SHALL BE INCLUDED IN THE BASE BID. UNLESS NOTED OTHERWISE, A MAIN SERVICE SWITCH WITH CURRENT LIMITING FUSES MAY BE USED WHEN THE AVAILABLE FAULT CURRENT (AFC) IS EXCESSIVE. IN ORDER TO USE STOCK PANELBOARDS, WITH 10K OR 22K AIC RATINGS.

### PART II. MATERIALS

- MATERIALS: ALL MATERIALS SHALL BE NEW AND OF THE QUALITY INDICATED BY THE SPECIFIED BRAND NAMES. SUBSTITUTIONS OF MATERIAL OF EQUAL QUALITY BY OTHER MAJOR MANUFACTURERS OF COMMERCIAL EQUIPMENT MAY BE ACCEPTABLE PROVIDED A LIST OF SUCH SUBSTITUTIONS IS APPROVED IN WRITING BY POPEYES ARCHITECTURE AND ENGINEERING DEPARTMENT. THE CONTRACTOR SHALL SUBMIT A SUBSTITUTION LIST IN TRIPLICATE AT LEAST FIVE DAYS PRIOR TO THE BID OPENING.

- PANELBOARDS: PANELBOARDS SHALL BE BOLT-IN CIRCUIT BREAKER TYPE, AS SHOWN ON THE PLANS. PANELS SHALL BE OF PANELBOARD CONSTRUCTION, 20 INCHES WIDE (MINIMUM), 5-3/4" TO 6-1/2" DEEP, UL LISTED, AND MEET UL 67, UL 50, AND FEDERAL SPECIFICATION W-P-115B AS TYPE 1, CLASS 1, WITH BOLT-ON CIRCUIT BREAKERS, COPPER BUS BARS, NEUTRAL BUS, GROUND BUS, AND A HINGED LOCKABLE DOOR. CABINETS SHALL BE CODE GAUGE, GALVANIZED STEEL, MOUNTED AS SHOWN. PROVIDE TYPEWRITTEN CIRCUIT DIRECTORIES WITH CLEAR PLASTIC PROTECTORS IN ALL PANELS. ALL WIRES SHALL BE TAGGED WITH PANEL AND CIRCUIT NUMBERS. PANEL "MP" SHALL BE UL LISTED AND LABELED AS SUITABLE FOR USE AS SERVICE ENTRANCE EQUIPMENT. APPROVED MANUFACTURERS OF PANELS ARE SQUARE D/TELEMECHANIQUE, CUTLER-HAMMER, GENERAL ELECTRIC, WESTINGHOUSE, AND SIEMENS (I-FE).
- LIGHTING FIXTURES: ALL LIGHTING FIXTURES SHALL BE UL LISTED, COMMERCIAL QUALITY. REFER TO NATIONAL ACCOUNT SCHEDULE. REVIEW AT: WWW.POPEYESDEVELOPMENT.COM. PASSWORD: lagniappe
- LAMPS: ALL NEW FLUORESCENT LAMPS (F40T8) SHALL BE COOL WHITE, OR COLOR IMPROVED COOL WHITE, WITH A 4100 DEGREE K COLOR TEMPERATURE, 2950 MIN INITIAL LUMENS, 20,000 HOURS RATED LIFE, AND 62 MIN CRI, UNLESS NOTED OTHERWISE.
- WIRING DEVICES: ALL WIRING DEVICES SHALL BE UL LISTED, COMMERCIAL SPECIFICATION GRADE. SWITCHES SHALL BE RATED 20 AMPS AT 120/277 VOLTS, AC. STANDARD RECEPTACLES SHALL BE 20 AMP, DUPLEX, GROUNDING TYPE, IN NEMA CONFIGURATIONS, UNLESS NOTED OTHERWISE. SWITCHES IN THE SAME LOCATION SHALL BE GANGED BEHIND A SINGLE PLATE. DEVICE PLATES IN THE KITCHEN AREA SHALL BE METAL, ALUMINUM OR STAINLESS STEEL. DEVICE PLATES IN THE DINING AREA SHALL BE THERMOPLASTIC PLASTIC (NYLON) OR METAL, COLOR AS APPROVED BY THE ARCHITECT OR OWNER. APPROVED MANUFACTURERS OF SWITCHES AND RECEPTACLES ARE HUBBELL, ARROW HART, BRYANT, LEVITON, PASS & SEYMOUR, GENERAL ELECTRIC, SLATER, OR EQUAL.

- SWITCHES:
  - SINGLE POLE: HUBBELL HBL1221-I, OR EQUAL.
  - THREE WAY: HUBBELL HBL1223-I, OR EQUAL.
- RECEPTACLES:
  - NEMA 5-20R: HUBBELL 5362I, OR EQUAL.
  - NEMA 5-20R-IG: HUBBELL IG-5362, OR EQUAL.
  - NEMA 5-20R-IG/SS: HUBBELL IG-5362-OS, OR EQUAL.
  - NEMA 5-20R-GFCI: HUBBELL GF5362-I, OR EQUAL.
  - NEMA 5-20R: HUBBELL 5462-I, OR EQUAL.
- OTHERS: COMMERCIAL OR INDUSTRIAL GRADE, UL LISTED, FEDERAL SPECIFICATION WCS96F.
- WP PLATES: WEATHERPROOF COVERS ARE PERMITTED UNDER NEC ARTICLE 406.8(B)(1).
- NATIONAL ACCOUNT: REFER TO THE NATIONAL ACCOUNT DIRECTORY. THE FOLLOWING EQUIPMENT MAY BE AVAILABLE: MAIN SERVICE PANELBOARD WITH BREAKERS INSTALLED, LIGHTING AND DISTRIBUTION PANELBOARDS WITH BREAKERS INSTALLED, ROOF-TOP DISCONNECTS FOR HVAC UNITS AND KITCHEN HOOD FANS, LIGHTING CONTACTOR PANEL, AND SHUNT TRIP SYSTEMS (IF REQUIRED PER LOCAL CODE).
- EXCAVATIONS: PERFORM ALL NECESSARY EXCAVATING AND BACK-FILLING REQUIRED FOR THIS INSTALLATION. ALL EXCAVATIONS BELOW THE BOTTOM OF FOOTINGS SHALL BE BACKFILLED WITH 3000 PSI CONCRETE. WHERE DITCHES ARE CUT FOR OUTSIDE RUNS OF CONDUIT, REPLACE AND TAMP THE EARTH IN 12" LAYERS AND LEAVE THE GROUND LEVEL AND EQUAL TO ITS ORIGINAL CONDITION.
- CONDUIT AND FITTINGS: CONDUIT PERMITTED: (A) RIGID GALVANIZED STEEL (RGS); (B) EMT; (C) PVC; AND (D) ENT. TYPES UTILIZED SHALL BE RUN ONLY AS PERMITTED PER CODE. ALL WIRING SHALL BE RUN IN CONDUIT. CONDUIT PLACED IN CONCRETE OR RUN UNDERGROUND SHALL BE RIGID GALVANIZED CONDUIT OR PVC. IF PVC IS USED, ALL ELBOWS, SWEEPS, AND STUB-UPS SHALL BE RGS. CONDUIT EXPOSED OR RUN IN MASONRY WALLS ABOVE GRADE MAY BE PVC OR ENT, WHERE ALLOWED BY LOCAL CODES. IF EMT IS NOT PERMITTED, SCREWED GALVANIZED PIPE CONDUIT AND FITTINGS SHALL BE USED. IF SHIELDED CABLE IS REQUIRED FOR CONTROL CIRCUITRY, IT SHALL BE TAN OR GREEN OR NEUTRAL COLOR OTHER THAN BLACK, AS SPECIFIED ON THE DRAWING. NO CONDUIT SMALLER THAN 1/2" SHALL BE INSTALLED EXCEPT FOR TWO-WIRE SWITCHES. ALL CONDUIT BEINGS SHALL BE FREE FROM DEBRIS AND FUSES. ALL CONDUIT SHALL BE ELECTRICALLY TINUOLATED FROM THE SERVICE EQUIPMENT TO ALL OUTLETS, AND SHALL BE SECURED TO METAL BOXES WITH ONE LOCK NUT, WASHER, AND ONE WEDGE OF THE BOX WITH A REINFORCED BACKWASHING. IF PVC OR ENT IS USED, THEN APPROPRIATE SIZED, ELECTRICALLY CONTINUOUS, BOND WIRES SHALL BE RUN FROM THE SERVICE EQUIPMENT TO ALL OUTLETS, AND SHALL BE SECURED TO EACH WIRING DEVICE PER THE NATIONAL

- ELECTRICAL CODE. WHERE CONNECTIONS ARE TO BE MADE BETWEEN CONDUIT TERMINATIONS AND MOTORS, EQUIPMENT, OR APPARATUS NECESSITATING FLEXIBLE CONNECTIONS, APPROVED FLEXIBLE CONDUIT SHALL BE USED. OUTDOOR CONNECTIONS TO FANS, HVAC UNITS, OR ROTATING EQUIPMENT SHALL BE MADE WITH HELICAL WOUND, LIQUID TIGHT, FLEXIBLE STEEL CONDUIT. EXPOSED CONDUIT SHALL BE SUITABLY SUPPORTED AT INTERVALS NOT TO EXCEED FIVE (5) FEET. DURING CONSTRUCTION, CONDUIT SHALL BE KEPT FREE OF ALL FOREIGN MATTER BY USE OF CAPPED BUSHINGS ON ALL TURNED UP ENDS. PAPER OR WOOD PULPS ARE NOT ACCEPTABLE FOR THIS PURPOSE.
- WIRE AND CABLES: ALL WIRE AND CABLES SHALL BE UNDERWRITERS LABORATORIES' LISTED, AND LABELED, AND CONFORM WITH APPLICABLE STANDARDS OF UL (44, AND 83), NEMA (WC-5, AND WC-7), IPCEA (S-61-402, AND S-66-524), FEDERAL SPECIFICATIONS (J-C-30A(1), AND HH-I-595C), ANSI, AND OTHER APPLICABLE INDUSTRY STANDARDS. CONNECTORS AND LUGS SHALL MEET UL PUBLICATION 486. ALL BRANCH CIRCUIT WIRING SHALL BE 600 VOLT COPPER, 75 DEGREE C (MIN), TYPE THHN/THWN WITH A MINIMUM SIZE OF #12 AWG, UNLESS NOTED OTHERWISE. WIRE SIZES OF #8 AWG AND LARGER SHALL BE STRANDED. SERVICE AND FEEDER CABLES SHALL BE 600 VOLT, STRANDED COPPER, 75 DEGREE C (MIN), TYPE XHHW. ALL CIRCUITS SHALL HAVE A SEPARATE GROUND CONDUCTOR. PROVIDE GREEN-INSULATED GROUND WIRE IN ALL RACEWAYS, CABLE ASSEMBLIES, AND WHERE NOTED. SIZE EQUIPMENT GROUNDS PER TABLE 250-122 OF THE NATIONAL ELECTRICAL CODE. INSULATION COLOR CODES SHALL BE BLACK, RED, AND BLUE (PHASE), WHITE (NEUTRAL), AND GREEN (GROUND).
  - ALL WIRING SHALL BE INSTALLED IN CONDUIT EXCEPT WHERE SPECIFICALLY SHOWN ON THE DRAWINGS. NON-METALLIC SHEATHED (TYPE NM) CABLE IS NOT PERMITTED.
  - ALL BRANCH CIRCUIT, COMMUNICATION, SIGNALING, AND CONTROL WIRING TO KITCHEN, FIRE PROTECTION, AND OTHER EQUIPMENT SHALL BE ROUTED ABOVE THE CEILING. VERIFY WHETHER OR NOT THE SPACE ABOVE THE CEILING IS USED AS A SPACE FOR RETURN AIR FOR THE ENVIRONMENTAL AIR SYSTEM. IF IT IS USED FOR RETURN AIR, PROVIDE APPROVED RACEWAYS FOR ALL OVERHEAD WIRING PER NEC ARTICLE 300-22(B). IF IT IS NOT "OTHER SPACE USED FOR ENVIRONMENTAL AIR," APPROVED LOW VOLTAGE CABLES MEETING THE REQUIREMENTS OF NEC ARTICLES 725 AND 760 MAY BE RUN WITHOUT RACEWAYS, UNO. ALL SAFETY CONTROL WIRING FOR FIRE PROTECTION SYSTEMS, SHUNT TRIPS, ETC. SHALL BE RUN IN A RACEWAY IN ACCORDANCE WITH NEC ARTICLES 725.25 AND 725.28.
  - SITE LIGHTING: THE G.C. WILL FURNISH THE SITE LIGHTING PACKAGE, AS REQUIRED FOR THE SPECIFIC LOCATION. UNDER THIS SPECIFICATION SECTION, PROVIDE 1" RIGID GALVANIZED STEEL ELECTRICAL CONDUIT, AND THE REQUIRED WIRING FROM THE PANEL TO THE POLE. SET FIXTURES AND POLES ON CONCRETE BASES, AS PROVIDED UNDER SPECIFICATION SECTION 3A. CONCRETE GROUND/BOND ALL SITE LIGHTING FIXTURES/POLES PER THE NEC. THE BRANCH CIRCUIT CONDUCTORS SHALL BE INCREASED FROM #10 AWG TO #12 AWG IF THE HORIZONTAL DISTANCE FROM THE PANEL TO THE POLE IS GREATER THAN EIGHTY (80) FEET. ALL SITE LIGHTING SHALL BE CONTROLLED THROUGH THE LIGHTING CONTROL SYSTEM SHOWN ON THE DRAWINGS. REFER TO THE PLAN FOR QUANTITY AND LOCATION OF ALL SITE LIGHTING. SET FIXTURES AS SPECIFIED, AND AIM AT THE MARK FOR EVEN LIGHT DISTRIBUTION.
  - SIGNAGE LIGHTING: PROVIDE A 1" RIGID GALVANIZED STEEL ELECTRICAL CONDUIT, AND WIRING, FROM THE PANEL TO ALL ILLUMINATED SIGNS AS SHOWN ON THE LIGHTING AND SITE PLANS. GROUND AND EACH SIGN. SIGNS WILL BE FURNISHED AND INSTALLED BY THE OWNER, OR UNDER A SEPARATE CONTRACT. UNO. POWER AND WIRING SHALL BE FURNISHED AND INSTALLED UNDER THIS SECTION OF THE SPECIFICATIONS.
- OTHER NOTES:
- FURNISH AND INSTALL ALL POWER WIRING AND CONDUIT AS INDICATED ON THE DRAWINGS FOR ROOF-TOP HVAC EQUIPMENT, KITCHEN HOOD FANS, AND WALK-IN FREEZER AND COOLER EQUIPMENT. DISCONNECT SWITCHES, AVAILABLE FROM THE NATIONAL ACCOUNT, SHALL BE FURNISHED AND INSTALLED FOR EACH UNIT OF HVAC EQUIPMENT, AND FOR KITCHEN EQUIPMENT WITHOUT A CORD AND PLUG. BEFORE ENERGIZING ANY EQUIPMENT, VERIFY THAT THE CORRECT POWER SUPPLY VOLTAGE, AMPACITY, AND PHASING HAS BEEN PROVIDED AT THE LOAD SIDE OF THE DISCONNECT.
  - FURNISH AND INSTALL THE LIGHTING CONTACTOR PANEL, AND ALL ASSOCIATED POWER WIRING, AS INDICATED. THE LIGHTING CONTACTOR PANEL IS CUSTOM BUILT, AND AVAILABLE FROM THE NATIONAL ACCOUNT.
  - EMPTY CONDUIT: LEAVE A #12 AWG PULL WIRE IN ALL EMPTY CONDUITS.
  - BOXES AND WIREWAYS: ALL JUNCTION BOXES, PULL BOXES, WIREWAYS, ETC. SHALL BE SIZED IN ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE.
  - EQUIPMENT IDENTIFICATION: PROVIDE NAMEPLATES FOR ALL PANELBOARDS, CONTROLS, AND OTHER ELECTRICAL EQUIPMENT. EQUIPMENT VISIBLE TO THE PUBLIC SHALL BE IDENTIFIED WITH ENGRAVED LAMINATED NAMEPLATES ATTACHED WITH STAINLESS STEEL FASTENERS. ELECTRICAL EQUIPMENT NOT VISIBLE TO THE PUBLIC MAY BE NEATLY IDENTIFIED WITH BLACK PERMANENT MARKERS.

### PART III. EXECUTION

- TESTS: MAKE ALL TESTS NECESSARY TO ENSURE THAT THE ENTIRE INSTALLATION IS FREE FROM IMPROPER GROUNDS, AND FROM SHORTED AND/OR OPEN CONDUCTORS. VOLTAGE CURRENT, AND ROTATION TESTS SHALL BE MADE BEFORE ANY MOTORS ARE PLACED IN OPERATION. ALL LOADS SHALL BE BALANCED ACROSS PHASES. CHECK TO SEE THAT ALL LIGHTS WORK, AND ARE CONTROLLED BY SWITCHES INDICATED ON DRAWINGS, OR CIRCUIT BREAKERS SO INDICATED ON PANEL SCHEDULE.
- GUARANTEE: FURNISH A GUARANTEE IN WRITING TO THE OWNER THAT ALL WORK EXECUTED UNDER THIS SECTION IS FREE FROM DEFECTS OF MATERIALS AND WORKMANSHIP FOR A PERIOD OF ONE (1) YEAR FROM DATE OF FINAL ACCEPTANCE. IN ADDITION, DURING THE TERM OF THIS GUARANTEE, THE REPAIR AND/OR REPLACEMENT OF ANY DEFECTIVE WORK, AND ALL RESULTING DAMAGES SHALL BE MADE AT NO ADDITIONAL EXPENSE TO THE OWNER.
- TEMPORARY POWER: AT THE PROJECT SITE, PROVIDE A 100 AMP, 120/240 VOLT, SINGLE PHASE, SERVICE WITH POWER OUTLETS ADEQUATE FOR TEMPORARY CONSTRUCTION POWER. TEMPORARY LIGHTING SHALL BE MAINTAINED IN ALL AREAS OF THE BUILDING UNTIL PERMANENT POWER SOURCES HAVE BEEN ENERGIZED. TEMPORARY SERVICE SHALL BE PROVIDED UNDER SECTION 1A OF THESE SPECIFICATIONS.
- CLEAN-UP: LEAVE THE ELECTRICAL PORTION OF THE WORK IN A CLEAN AND FINISHED CONDITION.
- SHOP DRAWINGS: PROVIDE SHOP DRAWINGS FOR THE FOLLOWING ITEMS: PANELBOARDS, LIGHTING FIXTURES.
- AS-BUILT DRAWINGS: MAINTAIN AS-BUILT DRAWINGS, DATED DAILY DURING CONSTRUCTION, AND PRESENT THE OWNERS PERSONNEL WITH ON-SITE INSTRUCTIONS FOR OPERATION AND MAINTENANCE OF THE COMPLETED ELECTRICAL SYSTEM.

## LEGEND

### ELECTRICAL SYMBOLS

- SINGLE FACE EXIT LIGHT W/EMERGENCY BATTERY PACK AND TWO (2) EMERGENCY LIGHT HEADS. SEE FIXTURE SCHEDULE.
- BRACKET OR WALL MOUNTED LIGHT FIXTURE. LETTER DENOTES MARK. SEE FIXTURE SCHEDULE.
- CEILING MOUNTED EMERGENCY LIGHT FIXTURE
- FLUORESCENT LIGHT FIXTURE. LETTER DENOTES MARK. SEE FIXTURE SCHEDULE.
- FLUORESCENT LIGHT FIXTURE ON NIGHT LIGHT CIRCUIT.
- FLUORESCENT LIGHT FIXTURE. LETTER DENOTES MARK. SEE FIXTURE SCHEDULE.
- PENDANT LIGHT FIXTURE. LETTER DENOTES MARK. SEE FIXTURE SCHEDULE.
- RECESSED DOWN LIGHT FIXTURE. LETTER DENOTES MARK. SEE FIXTURE SCHEDULE.
- 8" VERTICAL FLUORESCENT RECESSED LIGHT FIXTURE. LETTER DENOTES MARK. SEE FIXTURE SCHEDULE.
- PADDLE FAN. LETTER DENOTES MARK. SEE FIXTURE SCHEDULE.
- TOGGLE SWITCH, SINGLE POLE - HUBBELL #HBL1221-I.
- DUPLEX RECEPTACLE. NUMBER SUBSCRIPT INDICATES MOUNTING HEIGHT 'ABV' FINISHED FLOOR IF DIFFERENT THAN SPECIFIED. HUBBELL #5362-I.
- DUPLEX RECEPTACLE - IN WEATHER PROOF ENCLOSURE OR COVER. GROUND FAULT INTERRUPTER.
- RECEPTACLE FLUSH MOUNTED IN CEILING. VERIFY EXACT LOCATION AND NEMA CONFIGURATION.
- DUPLEX RECEPTACLE - ISOLATED GROUND SURGE PROTECTED - HUBBELL #IG-5362-OSP FOR POS EQUIP. & PRINTERS
- DUPLEX RECEPTACLE - ISOLATED GROUND SURGE PROTECTED, MOUNTED IN CEILING. HUBBELL #IG-5362-OSP FOR MONITORS
- SPECIAL PURPOSE RECEPTACLE
- 208/120 PANELBOARD.
- DISCONNECT SWITCH SIZE AS NOTED.
- DOOR SWITCH MOUNTED IN DOOR FRAME (F.B.C.)
- SEE ELECTRICAL NOTES.
- A.F.F. ABOVE FINISHED FLOOR.
- A.F.C. ABOVE FINISHED CEILING.
- F.B.C. FURNISHED BY CONTRACTOR.
- G.F.I. GROUND FAULT INTERRUPTING
- W.P. WEATHERPROOF
- U.N.O. UNLESS NOTED OTHERWISE.
- CONDUIT RUN CONCEALED IN WALLS OR CL. SPACES. ARROWS INDICATE HOMERUNS. SUBSCRIPT INDICATES PANEL AND CIRCUIT NUMBERS. SLASH MARKS INDICATE NUMBER OF CONDUCTORS. EQUIPMENT GROUNDING CONDUCTOR REQUIRED IN ALL CONDUITS NOT INDICATED WITH HASHMARK.
- SAME AS ABOVE NOTE EXCEPT RUN CONDUIT BELOW FLOOR
- EXHAUST FAN.
- SUPPLY FAN.
- FLY FAN
- JUNCTION OR OUTLET BOX.
- JUNCTION OBOX FOR SIGN-MOUNT SWITCH NEAR SIGN. MAKE ALL CONNECTIONS REQ'D. VERIFY ALL ASPECTS WITH SIGNAGE VENDOR. SEE ARCHITECTURAL ELEVATIONS FOR HEIGHT AND LOCATION AS SHOWN.
- JUNCTION BOX FOR SMOKE DETECTOR (F.B.C.) 120v WIRING BY THIS CONTRACTOR.
- COMBINATION DUAL DATA OUTLET AND TELEPHONE OUTLET HEIGHT AS NOTED ON PLANS WITH 3/4" EMPTY CONDUIT TO ABOVE CEILING. PROVIDE PULL WIRE.
- TELEPHONE OUTLET, WALL TYPE, 24" AFF U.N.O. ON PLANS WITH 3/4" EMPTY CONDUIT TO ABOVE CEILING. PROVIDE PULL WIRE.
- DATA OUTLET, HEIGHT AS NOTED ON PLANS WITH 3/4" EMPTY CONDUIT TO ABOVE CEILING. PROVIDE PULL WIRE.
- PROVIDE 'ON/OFF' SELECTOR SWITCH AND PILOT LIGHT IN NEMA 4 STAINLESS STEEL ENCLOSURE MOUNTED ON THE FACE OF THE HOOD. PROVIDED BY HOOD MANUFACTURER.
- SPEAKER; CEILING MOUNTED
- SPEAKER OUTLET IN WALL STUB 3/4" CONDUIT TO SPACE ABOVE ACCESSIBLE CEILING. PROVIDE PULL WIRE.
- TRANSFORMER MOUNTED ACCESSIBLE
- ELECTRIC DOOR PUSHBUTTON; EDWARDS #590 48" MOUNTING HEIGHT
- ELECTRIC DOOR BUZZER. 8" BELOW CEILING
- PHOTOCELL

Order Forms

ARCHITECT/ENGINEER  
**LIS**  
 LAND INVESTMENT SERVICES, LLC  
 2512 West State Road 428  
 Suite 2054, Ocala, FL 32705  
 Phone: (352) 921-1414  
 Facsimile: (352) 921-9829

CLIENT NAME  
**SOUTHEASTERN RETAIL DEVELOPMENT, LLC**  
 BLDG M-1, UNIT Z31  
 2030 COUNTY ROAD 30A  
 SANTA ROSA BEACH, FL 32459

PROJECT NAME  
**POPEYES**  
 PLK 1930-28-DL SAILORMEN  
 501 N HWY 49  
 BAYCON, GA 31088

SEAL  
 ROBERT W. CASE  
 GEORGIA PE #202694

RELEASE	DATE
1	
2	
3	
4	
5	
6	

PROJECT NO.  
**2020-085**

ISSUE DATE  
**05/07/20**

DRAWN | CHECKED  
**JC | JC**

SHEET NO.  
**EO**  
ELECTRICAL DATA SHEET AND SPECIFICATIONS

LIS EXPRESSLY RESERVES ITS COPYRIGHT AND ALL OTHER PROPERTY RIGHTS TO THESE DOCUMENTS AND THEIR DESIGN. HENCE, THEY ARE NOT TO BE REPRODUCED.

ELECTRICAL DATA SHEET AND SPECIFICATIONS