

EXISTING COMPLEX
CURRENTLY UNDER CONSTRUCTION

Luminaire Schedule						
Symbol	Qty	Label	Arrangement	Total Lamp Lumens	LLF	Description
⊙	2	G	SINGLE	1600	0.810	2' x 4' wall Coach Light
⊙	1	F	SINGLE	N.A.	0.900	15W-AP-800-LED-EI-S14
⊙	1	L	SINGLE	N.A.	0.900	LD8A401D010 ER8A40840 8LM1H


Calculation Summary							
Label	CalcType	Units	Avg	Max	Min	Avg/Min	Max/Min
Site Lighting Planar	Illuminance	FC	0.96	15.5	0.0	N.A.	N.A.

WICKHAM ROAD

Order Plans

www.LDILine.com

NOTE: REFER TO PH-02 FOR LIGHTING CUT SHEETS



 MBV ENGINEERING, INC. <small>PO BOX 80888 WILMINGTON, NC 28408</small> CIVIL • STRUCTURAL • SURVEYING • ENVIRONMENTAL 1250 W. EAU GALLE BLVD., SUITE H MELBOURNE, FLORIDA 32955 P-321-253-1510 F-321-253-0811 <small>VERO 772-866-0035 FT PIERCE 772-468-8095 GAITHERSBURG 410-477-2222</small>	JOB NO. 19-1045 DESIGNED BY BJD DRAWN BY BJD DATE OCTOBER 2019 CHECKED BY BAM DATE ISSUED 5/7/2020	COMMENTS REVISIONS 1 2 3 4 5 6 7 8
	PHOTOMETRICS PLAN	
	CHRISTIAN BROTHERS AUTOMOTIVE REPAIRS	
	SHEET PH-1	

19-1045
PERMITTING SET