

**SECTION 16A GENERAL ELECTRICAL REQUIREMENTS:**

**16A 1 GENERAL INSTRUCTIONS**

**16A 1-1 GENERAL REQUIREMENTS**

ALL REQUIREMENTS UNDER DIVISION 1 AND THE GENERAL AND SUPPLEMENTARY CONDITIONS OF THESE SPECIFICATIONS APPLY TO THIS SECTION AND DIVISION. WHERE THE REQUIREMENTS OF THIS SECTION AND DIVISION EXCEED THOSE OF DIVISION 1, THIS SECTION AND DIVISION TAKE PRECEDENCE. BECOME THOROUGHLY FAMILIAR WITH ALL THEIR CONTENTS AS TO REQUIREMENTS THAT AFFECT THIS DIVISION, SECTION OR BOTH. WORK REQUIRED UNDER THIS DIVISION INCLUDES ALL MATERIAL, EQUIPMENT, APPLIANCES, AND LABOR REQUIRED TO COMPLETE THE ENTIRE ELECTRICAL SYSTEM AS REQUIRED BY THE DRAWINGS AND SPECIFICATIONS, OR REASONABLY INFERRED TO BE NECESSARY TO FACILITATE EACH SYSTEM'S FUNCTIONING AS IMPLIED BY THE DESIGN AND THE EQUIPMENT SPECIFIED.

THE SPECIFICATIONS AND DRAWINGS FOR THE PROJECT ARE COMPLEMENTARY, AND PORTIONS OF THE WORK DESCRIBED IN ONE, SHALL BE PROVIDED AS IF DESCRIBED IN BOTH, IN THE EVENT OF DISCREPANCIES, NOTIFY THE ENGINEER AND REQUEST CLARIFICATION PRIOR TO PROCEEDING WITH THE WORK INVOLVED.

DRAWINGS ARE GRAPHIC REPRESENTATIONS OF THE WORK UPON WHICH THE CONTRACT IS BASED. THEY SHOW THE MATERIALS AND THEIR RELATIONSHIP TO ONE ANOTHER, INCLUDING SIZES, SHAPES, LOCATIONS, AND CONNECTIONS. THEY ALSO CONVEY THE SCOPE OF WORK, INDICATING THE INTENDED GENERAL ARRANGEMENT OF THE EQUIPMENT, FIXTURES, OUTLETS AND CIRCUITS WITHOUT SHOWING ALL OF THE EXACT DETAILS AS TO ELEVATIONS, OFFSETS, CONTROL LINES, AND OTHER INSTALLATION REQUIREMENTS. USE THE DRAWINGS AS A GUIDE WHEN LAYING OUT THE WORK AND TO VERIFY THAT MATERIALS AND EQUIPMENT WILL FIT INTO THE DESIGNATED SPACES, AND WHICH, WHEN INSTALLED PER MANUFACTURERS' REQUIREMENTS, WILL ENSURE A COMPLETE, COORDINATED, STATISTICAL AND PROPERLY OPERATING SYSTEM.

DRAWINGS ARE SCHEMATIC IN NATURE, SHOW THE VARIOUS COMPONENTS OF THE SYSTEMS APPROXIMATELY TO SCALE AND ATTEMPT TO INDICATE HOW THEY SHALL BE INTEGRATED WITH OTHER PARTS OF THE WORK. FIGURED DIMENSIONS TAKE PRECEDENCE TO SCALED DIMENSIONS. DETERMINE EXACT LOCATIONS BY JOB MEASUREMENTS, BY CHECKING THE REQUIREMENTS OF OTHER TRADES, AND BY REVIEWING ALL CONTRACT DOCUMENTS, CORRECT ERRORS THAT COULD HAVE BEEN AVOIDED BY PROPER CHECKING AND INSPECTION, AT NO ADDITIONAL COST TO THE OWNER.

SPECIFICATIONS DEFINE THE QUALITATIVE REQUIREMENTS FOR PRODUCTS, MATERIALS, AND WORKMANSHIP UPON WHICH THE CONTRACT IS BASED.

**16A 1-2 DEFINITIONS**

WHENEVER USED IN THESE SPECIFICATIONS OR DRAWINGS, THE FOLLOWING TERMS SHALL HAVE THE INDICATED MEANINGS:

1. FURNISH: "TO SUPPLY AND DELIVER TO THE PROJECT SITE, READY FOR UNLOADING, UNPACKING, ASSEMBLING, INSTALLING, AND SIMILAR OPERATIONS."

2. INSTALL: "TO PERFORM ALL OPERATIONS AT THE PROJECT SITE, INCLUDING, BUT NOT LIMITED TO, AND AS REQUIRED: UNLOADING, UNPACKING, ASSEMBLING, ERECTING, PLACING, ANCHORING, APPLYING, WORKING TO DIMENSION, FINISHING, CURING, PROTECTING, CLEANING, TESTING, COMMISSIONING, STARTING UP AND SIMILAR OPERATIONS, COMPLETE, AND READY FOR THE INTENDED USE."

3. PROVIDE: "TO FURNISH AND INSTALL COMPLETE, AND READY FOR THE INTENDED USE."

4. FURNISHED BY OWNER (OR OWNER-FURNISHED) OR FURNISHED BY OTHERS: "AN ITEM FURNISHED BY THE OWNER OR UNDER OTHER DIVISIONS OR CONTRACTS, AND INSTALLED UNDER THE REQUIREMENTS OF THIS DIVISION, COMPLETE, AND READY FOR THE INTENDED USE, INCLUDING ALL ITEMS AND SERVICES INCIDENTAL TO THE WORK NECESSARY FOR PROPER INSTALLATION AND OPERATION. INCLUDE THE INSTALLATION UNDER THE WARRANTY REQUIRED BY THIS DIVISION."

5. ENGINEER: WHERE REFERENCED IN THIS DIVISION, "ENGINEER" IS THE ENGINEER OF RECORD AND THE DESIGN PROFESSIONAL FOR THE WORK UNDER THIS DIVISION, AND IS A CONSULTANT TO, AND AN AUTHORIZED REPRESENTATIVE OF, THE ARCHITECT, AS DEFINED IN THE GENERAL AND/OR SUPPLEMENTARY CONDITIONS. WHEN USED IN THIS DIVISION, IT MEANS INCREASED INVOLVEMENT BY, AND OBLIGATIONS TO, THE ENGINEER, IN ADDITION TO INVOLVEMENT BY, AND OBLIGATIONS TO, THE ARCHITECT AND THE LOCAL CODE AND/OR INSPECTION AGENCY (AUTHORITY) HAVING JURISDICTION OVER THE WORK.

7. NRTL: NATIONALLY RECOGNIZED TESTING LABORATORY, AS DEFINED AND LISTED BY OSHA IN 29 CFR 1910.7 (E.G., UL, ETL, CSA), AND ACCEPTABLE TO THE AHJ OVER THIS PROJECT.

8. THE TERMS "APPROVED EQUAL", "EQUIVALENT", OR "EQUAL" ARE USED SYNONYMOUSLY AND SHALL MEAN "ACCEPTED BY OR ACCEPTABLE TO THE ENGINEER AS EQUIVALENT TO THE ITEM OR MANUFACTURER SPECIFIED". THE TERM "APPROVED" SHALL MEAN LABELED, LISTED, CERTIFIED, OR ALL THREE, BY AN NRTL, AND ACCEPTABLE TO THE AHJ OVER THIS PROJECT.

**16A 1-3 PRE-BID SITE VISIT**

PERSONALLY INSPECT THE SITE OF THE PROPOSED WORK AND BECOME FULLY INFORMED OF CONDITIONS UNDER WHICH THE WORK IS TO BE DONE. FAILURE TO DO SO WILL NOT BE CONSIDERED SUFFICIENT JUSTIFICATION TO REQUEST OR OBTAIN EXTRA COMPENSATION OVER AND ABOVE THE CONTRACT PRICE.

**16A 1-4 MATERIAL AND WORKMANSHIP**

PROVIDE ALL MATERIAL AND EQUIPMENT NEW AND IN FIRST CLASS CONDITION. PROVIDE MARKINGS OR A NAMEPLATE FOR ALL MATERIAL AND EQUIPMENT IDENTIFYING THE MANUFACTURER AND PROVIDING SUFFICIENT REFERENCE TO ESTABLISH QUALITY, SIZE AND CAPACITY. ALL WORKMANSHIP SHALL BE OF THE FINEST POSSIBLE BY EXPERIENCED MECHANICS OF THE PROPER TRADE. IN GENERAL, PROVIDE THE FOLLOWING QUALITY GRADE(S) FOR ALL MATERIALS AND EQUIPMENT:

1. COMMERCIAL SPECIFICATION GRADE  
PROVIDE ALL HOISTS, SCAFFOLDS, STAGING, RUNWAYS, TOOLS, MACHINERY AND EQUIPMENT REQUIRED FOR THE PERFORMANCE OF THE ELECTRICAL WORK. STORE AND MAINTAIN MATERIAL AND EQUIPMENT IN CLEAN CONDITION, AND PROTECTED FROM WEATHER, MOISTURE, AND PHYSICAL DAMAGE.

FURNISH ONLY MATERIAL AND EQUIPMENT THAT ARE LISTED, LABELED, CERTIFIED, OR ALL THREE, BY A NATIONALLY RECOGNIZED TESTING LABORATORY (NRTL), WHEREVER USED, INCLUDING ALL ITEMS AND SERVICES FOR THE TYPES OF MATERIAL AND EQUIPMENT SPECIFIED. AT A MINIMUM, GENERAL WORK PRACTICES FOR ELECTRICAL CONSTRUCTION SHALL BE IN ACCORDANCE WITH NECA 1 (LATEST EDITION), "STANDARD PRACTICES FOR GOOD WORKMANSHIP IN ELECTRICAL CONSTRUCTION".

**16A 1-5 MANUFACTURERS**

IN OTHER ARTICLES WHERE LISTS OF MANUFACTURERS ARE INTRODUCED, SUBJECT TO COMPLIANCE WITH REQUIREMENTS, PROVIDE PRODUCTS BY ONE OF THE MANUFACTURERS SPECIFIED.

WHERE A LIST IS PROVIDED, MANUFACTURERS ARE LISTED ALPHABETICALLY AND NOT IN ACCORDANCE WITH ANY RANKING OR PREFERENCE.

WHERE MANUFACTURERS ARE NOT LISTED, PROVIDE PRODUCTS SUBJECT TO COMPLIANCE WITH REQUIREMENTS FROM MANUFACTURERS THAT HAVE BEEN ACTIVELY INVOLVED IN MANUFACTURING THE SPECIFIED PRODUCT FOR NO LESS THAN 5 YEARS.

**16A 1-6 COORDINATION**

COORDINATE ALL WORK WITH OTHER DIVISIONS AND TRADES SO THAT VARIOUS COMPONENTS OF THE ELECTRICAL SYSTEMS ARE INSTALLED AT THE PROPER TIME, FIT THE AVAILABLE SPACE, AND ALLOW PROPER SERVICE ACCESS TO ALL EQUIPMENT. REFER TO ALL DRAWINGS, INCLUDING, BUT NOT LIMITED TO, CIVIL, ARCHITECTURAL, STRUCTURAL, MECHANICAL, AND PLUMBING, AND TO RELATED EQUIPMENT SUBMITTALS AND SHOP DRAWINGS TO DETERMINE THE EXACT CLEAR SPACES. MAKE ALL OFFSETS REQUIRED TO CLEAR EQUIPMENT, BEARING OTHER ELECTRICAL EQUIPMENT. FACILITATE CONCEALING RACEWAYS IN THE MANNER INDICATED BY THE DESIGN. PROVIDE MATERIALS WITH TRIM THAT WILL FIT PROPERLY THE TYPES OF CEILING, WALLS OR FLOOR FINISHES ACTUALLY INSTALLED.

**16A 1-7 ORDINANCES, CODES, AND STANDARDS**

COMPLY, AT A MINIMUM, WITH NATIONAL FIRE PROTECTION ASSOCIATION (NFPA) STANDARDS, STATE AND LOCAL BUILDING CODES, AND ALL OTHER APPLICABLE CODES AND ORDINANCES FOR PERFORMANCE, WORKMANSHIP, EQUIPMENT, AND MATERIALS. ADDITIONALLY, COMPLY WITH RULES AND REGULATIONS OF PUBLIC UTILITIES AND MUNICIPAL DEPARTMENTS AFFECTED BY CONNECTION OF SERVICES.

WHERE CONFLICTS BETWEEN VARIOUS CODES, ORDINANCES, RULES, AND REGULATIONS EXIST, COMPLY WITH THE MOST STRINGENT. WHEREVER REQUIREMENTS OF THESE SPECIFICATIONS, DRAWINGS, OR BOTH, EXCEED THOSE OF THE ABOVE ITEMS, THE REQUIREMENTS OF THESE SPECIFICATIONS, DRAWINGS, OR BOTH, SHALL GOVERN. CODE COMPLIANCE AT A MINIMUM IS MANDATORY. CONSTRUCT NOTHING IN THESE CONSTRUCTION DOCUMENTS AS PERMITTING WORK NOT IN COMPLIANCE, AT A MINIMUM, WITH THESE CODES.

BRING ALL CONFLICTS OBSERVED BETWEEN CODES, ORDINANCES, RULES, REGULATIONS, REFERENCED STANDARDS, AND THESE DOCUMENTS TO THE ENGINEER'S ATTENTION FOR FINAL RESOLUTION. CONTRACTOR WILL BE HELD RESPONSIBLE FOR ANY VIOLATION OF THE LAW.

PROVIDE AND MAINTAIN ALL NECESSARY SIGNAL LIGHTS AND GUARDS FOR THE SAFETY OF THE PUBLIC. OBTAIN AND PAY FOR ALL PERMITS FOR WORK IN THIS DIVISION.

**16A 1-8 PROTECTION OF EQUIPMENT AND MATERIALS**

STORE AND PROTECT FROM DAMAGE EQUIPMENT AND MATERIALS DELIVERED TO JOB SITE, IN ACCORDANCE WITH MANUFACTURERS' RECOMMENDATIONS. FOR MATERIALS AND EQUIPMENT SUSCEPTIBLE TO CHANGING WEATHER CONDITIONS, DAMPNES, OR TEMPERATURE VARIATIONS, STORE INSIDE IN CONDITION SPACES. FOR MATERIALS AND EQUIPMENT NOT SUSCEPTIBLE TO THESE CONDITIONS, COVER WITH WATERPROOF, WEAR-RESISTANT, HEAVY TAPOR POLYETHYLENE PLASTIC AS REQUIRED TO PROTECT FROM PLASTER, DIRT, PAINT, WATER, OR PHYSICAL DAMAGE. EQUIPMENT AND MATERIAL THAT HAS BEEN DAMAGED BY CONSTRUCTION ACTIVITIES WILL BE REJECTED, AND CONTRACTOR SHALL FURNISH NEW EQUIPMENT AND MATERIAL OF A LIKE KIND. PLUG OR CAP OPEN ENDS OF CONDUITS WHILE STORED AND INSTALLED DURING CONSTRUCTION WHEN NOT IN USE TO PREVENT THE ENTRANCE OF DEBRIS INTO THE SYSTEMS.

**16A 1-9 SUBSTITUTIONS**

INCLUDE IN THE BASE BID THE PRODUCTS SPECIFICALLY NAMED IN THESE SPECIFICATIONS OR ON THE DRAWINGS. SUBMIT, IN THE FORM OF ALTERNATES, WITH BID, PRODUCTS OF ANY OTHER MANUFACTURERS FOR SIMILAR USE, PROVIDED THE DIFFERENCES IN COST, IF ANY, ARE INCLUDED FOR EACH PROPOSED ALTERNATE. PRIOR TO THE BID DATE, SUBSTITUTIONS WILL NOT BE CONSIDERED UNLESS SUBMITTED TO THE ARCHITECT, FOR ENGINEER'S REVIEW, AT LEAST TEN CALENDAR DAYS PRIOR TO THE DATE FOR RECEIPT OF BIDS. INCLUDE THE NAME OF THE MATERIAL OR EQUIPMENT FOR WHICH IT IS TO BE SUBSTITUTED AND A COMPLETE DESCRIPTION OF THE PROPOSED SUBSTITUTE INCLUDING CUTSHEETS, PHOTOMETRIC DATA, AND ALL OTHER INFORMATION NECESSARY FOR AN EVALUATION FOR EACH SUCH REQUEST. PROVIDE FACTORY GENERATED POINT-BY-POINT CALCULATIONS FOR ALL EXTERIOR LIGHT FIXTURES (PHOTOMETRIC FILES SUPPLIED SO THE ENGINEER CAN GENERATE A POINT-BY-POINT DO NOT SUFFICE FOR THE POINT-BY-POINT CALCULATIONS). PROVIDE INTERIOR POINT-BY-POINT CALCULATIONS AT THE DISCRETION OF THE ENGINEER. SUBMIT A \$100.00 REVIEW FEE TO THE ENGINEER WITH EACH SUCH POINT-BY-POINT CALCULATION FOR USE OF ELECTRONIC BASE FILES.

AFTER THE BID DATE, PROPOSALS TO SUBSTITUTE LIGHT FIXTURES FOR THOSE SHOWN ON THE DRAWINGS OR SPECIFIED HEREIN, WILL ONLY BE CONSIDERED AS A DEDUCT. SUBMIT PROPOSED SUBSTITUTIONS SEPARATELY, IN SUBMITTAL FORM, WITH A LIST OF PROPOSED SUBSTITUTIONS TOGETHER WITH A DEDUCT PRICE FOR EACH SUBSTITUTION. THE ARCHITECT, ENGINEER, OR BOTH, WILL THEN REVIEW PROPOSED SUBSTITUTIONS. THE ENGINEER WILL HAVE THE FINAL AUTHORITY AS TO WHETHER THE LIGHT FIXTURE IS AN ACCEPTABLE REPLACEMENT TO THE SPECIFIED ITEM. THE PROPOSED SUBSTITUTE MAY ALSO BE REJECTED BY THE ARCHITECT FOR AESTHETIC REASONS IF FELT NECESSARY OR DESIRABLE. IN THE EVENT THE PROPOSED SUBSTITUTIONS HEREIN DESCRIBED ARE REJECTED, FURNISH THE SPECIFIED ITEM.

**16A 1-10 ELECTRONIC DRAWING FILES**

IN PREPARATION OF SHOP DRAWINGS, CONTRACTOR MAY, AS AN OPTION, OBTAIN ELECTRONIC DRAWING FILES IN AUTOCAD OR DXF FORMAT FROM THE ENGINEER FOR A SHIPPING AND HANDLING FEE OF \$200 FOR A DRAWING SET UP TO 12 SHEETS AND \$15 PER SHEET FOR EACH ADDITIONAL SHEET. CONTACT THE ARCHITECT FOR WRITTEN AUTHORIZATION, AND, CONTACT THE ENGINEER TO OBTAIN THE NECESSARY RELEASE AGREEMENTS AND TO INDICATE THE DESIRED SHIPPING METHOD AND DRAWING FORMAT. IN ADDITION TO PAYMENT, ARCHITECT'S WRITTEN AUTHORIZATION AND ENGINEER'S RELEASE AGREEMENT FORM MUST BE RECEIVED BEFORE ELECTRONIC DRAWING FILES WILL BE SENT.

**16A 1-11 OPERATION AND MAINTENANCE INSTRUCTIONS**

SUBMIT TO THE ARCHITECT, FOR ENGINEER'S REVIEW, COPIES EACH OF OPERATIONS AND MAINTENANCE INSTRUCTION MANUALS, APPROPRIATELY BOUND INTO MANUAL FORM INCLUDING APPROVED COPIES OF THE FOLLOWING, REVISED IF NECESSARY TO SHOW SYSTEM AND EQUIPMENT AS ACTUALLY INSTALLED. PROVIDE THE NUMBER OF SUBMITTALS REQUIRED BY DIVISION 7; HOWEVER, AT A MINIMUM, SUBMIT THREE (3) SETS, AND INCLUDE, AT A MINIMUM, THE FOLLOWING INFORMATION:

1. MANUFACTURERS' CATALOGS AND PRODUCT DATA SHEETS
  2. WIRING DIAGRAMS
  3. MAINTENANCE INSTRUCTIONS
  4. OPERATING INSTRUCTIONS
  5. PARTS LISTS
  6. TEST REPORTS AS DEFINED IN NECA ATS FOR THE SYSTEMS AND EQUIPMENT PROVIDED OR FURNISHED OR INSTALLED UNDER THIS CONTRACT.
  7. NAMES, ADDRESSES, TELEPHONE NUMBERS, AND E-MAIL ADDRESSES OF LOCAL CONTACTS FOR WARRANTY SERVICES AND SPARE PARTS.
- SUBMIT MANUALS PRIOR TO REQUESTING THE FINAL PUNCH LIST AND BEFORE ANY REQUESTS FOR SUBSTANTIAL COMPLETION. ALSO PROVIDE ADEQUATE VERBAL INSTRUCTIONS OF SYSTEM OPERATIONS TO OWNER'S REPRESENTATIVE AT THE COMPLETION OF, AND BEFORE FINAL ACCEPTANCE OF, THE WORK.

**16A 1-12 TRAINING**

AT A TIME MUTUALLY AGREED UPON BETWEEN THE OWNER AND CONTRACTOR, PROVIDE THE SERVICES OF A FACTORY TRAINED AND AUTHORIZED REPRESENTATIVE TO TRAIN OWNER'S DESIGNATED PERSONNEL ON THE OPERATION AND MAINTENANCE OF THE EQUIPMENT PROVIDED FOR THIS PROJECT.

PROVIDE TRAINING TO INCLUDE BUT NOT BE LIMITED TO AN OVERVIEW OF THE SYSTEM AND/OR EQUIPMENT AS IT RELATES TO THE FACILITY AS A WHOLE; OPERATION AND MAINTENANCE PROCEDURES AND SCHEDULES RELATED TO STARTUP AND SHUTDOWN, TROUBLESHOOTING, SERVICING, PREVENTIVE MAINTENANCE AND APPROPRIATE OPERATOR INTERVENTION; AND REVIEW OF DATA INCLUDED IN THE OPERATION AND MAINTENANCE INSTRUCTIONS.

SUBMIT A CERTIFICATION LETTER TO THE ARCHITECT STATING THAT THE OWNER'S DESIGNATED REPRESENTATIVE HAS BEEN TRAINED AS SPECIFIED HEREIN. LETTER SHALL INCLUDE DATE, TIME, ATTENDEES AND SUBJECT OF TRAINING. THE CONTRACTOR AND THE OWNER'S REPRESENTATIVE SHALL SIGN THE CERTIFICATION LETTER INDICATING AGREEMENT THAT THE TRAINING HAS BEEN PROVIDED. SCHEDULE TRAINING WITHIN 90 DAYS WITH AT LEAST 7 DAYS ADVANCE NOTICE.

**16A 1-13 WARRANTIES**

WARRANT EACH SYSTEM AND EACH COMPONENT THEREOF AGAINST ALL DEFECTS DUE TO FAULTY WORKMANSHIP, WITHIN A PERIOD OF 12 MONTHS FROM DATE OF SUBSTANTIAL COMPLETION, UNLESS SPECIFICALLY NOTED TO CARRY A LONGER WARRANTY IN THE CONSTRUCTION DOCUMENTS. MANUFACTURER'S STANDARD WARRANTY EXCEEDS 12 MONTHS, REMEDY ALL DEFECTS, OCCURRING WITHIN THE WARRANTY PERIOD(S), AS STATED IN THE GENERAL CONDITIONS AND DIVISION 7, AND WARRANT THE FOLLOWING ADDITIONAL ITEMS:

1. ALL RACEWAYS ARE FREE FROM OBSTRUCTIONS, HOLES, CRUSHING, OR BREAKS OF ANY NATURE.
  2. ALL RACEWAY SEALS ARE EFFECTIVE.
  3. THE ENTIRE ELECTRICAL SYSTEM IS FREE FROM ALL SHORT CIRCUITS AND UNWANTED OPEN CIRCUITS AND GROUNDS.
- THE ABOVE WARRANTIES SHALL INCLUDE LABOR AND MATERIAL. MAKE REPAIRS OR REPLACEMENTS WITHOUT ANY ADDITIONAL COSTS TO THE OWNER.
- PERFORM THE REMEDIAL WORK PROMPTLY, UPON WRITTEN NOTICE FROM THE ENGINEER OR OWNER.

AT THE TIME OF SUBSTANTIAL COMPLETION, DELIVER TO THE OWNER ALL WARRANTIES, IN WRITING AND PROPERLY EXECUTED, INCLUDING TERM LIMITS FOR WARRANTIES EXTENDING BEYOND THE ONE YEAR PERIOD. EACH WARRANTY INSTRUMENT BEING ADDRESSED TO THE OWNER AND STATING THE COMMENCEMENT DATE AND TERM.

**16A 2 ELECTRICAL WORK**

**16A 2-1 EXCAVATION AND BACKFILL**

PERFORM EXCAVATION AND BACKFILL REQUIRED FOR INSTALLATION OF UNDERGROUND WORK UNDER THIS CONTRACT. TRENCHES SHALL BE OF SUFFICIENT WIDTH, CRIB OR CRUCE TRENCHES TO PREVENT CAVE-IN OR SETTLEMENT. DO NOT EXCAVATE TRENCHES CLOSE TO COLUMNS AND WALLS OF NEW BUILDING WITHOUT PRIOR CONSULTATION WITH THE ENGINEER. USE PUMPING EQUIPMENT IF REQUIRED TO KEEP TRENCHES FREE OF WATER. BACKFILL TRENCHES IN MAXIMUM 6-INCH LAYERS OF WELL TAMPED DRY EARTH IN A MANNER TO PREVENT FUTURE SETTLEMENT.

EXCAVATION AS HEREIN SPECIFIED SHALL BE CLASSIFIED AS COMMON EXCAVATION. COMMON EXCAVATION SHALL COMPRISE THE SATISFACTORY REMOVAL AND DISPOSITION OF MATERIAL OF WHATEVER SUBSTANCE AND OF EVERY DESCRIPTION ENCOUNTERED, INCLUDING ROCK, IF ANY, WITHIN THE LIMITS OF THE WORK AS SPECIFIED AND SHOWN ON THE DRAWINGS. EXCAVATION SHALL BE PERFORMED TO THE LINES AND GRADES INDICATED ON THE DRAWINGS. DISPOSE OF EXCAVATED MATERIALS THAT ARE CONSIDERED UNSUITABLE FOR BACKFILL, AND SURPLUS OF EXCAVATED MATERIAL, WHICH IS NOT REQUIRED FOR BACKFILL, ALL TO THE SATISFACTION OF THE ENGINEER.

**16A 2-2 INCIDENTAL DAMAGE**

REPAIR ALL STREETS, SIDEWALKS, DRIVES, PAVING, WALLS, FINISHES, AND OTHER FACILITIES DAMAGED IN THE COURSE OF THIS WORK. REPAIR MATERIALS SHALL MATCH EXISTING CONSTRUCTION. REPAIR MATERIALS SHALL GENERALLY MATCH EXISTING CONSTRUCTION. ALL BACKFILLING AND REPAIRING SHALL MEET ALL REQUIREMENTS OF THE OWNER, CITY AND OTHERS. REPAIR WORK SHALL BE THOROUGHLY FIRST CLASS. CONFORM TO ALL REQUIREMENTS OF DIVISION 2 OF THESE SPECIFICATIONS CONCERNING CUTTING AND PATCHING.

FOLLOWING THE REQUIREMENTS IN DIVISION 1, CUT WALLS, FLOORS, CEILING, AND OTHER PORTIONS OF THE FACILITY AS REQUIRED TO PERFORM WORK UNDER THIS DIVISION. OBTAIN PERMISSION OF THE ENGINEER, OWNER, OR BOTH, BEFORE DOING ANY CUTTING, CUT ALL HOLES AS SMALL AS POSSIBLE. PATCH WALLS, FLOORS, AND OTHER PORTIONS OF THE FACILITY AS REQUIRED BY WORK UNDER THIS DIVISION. ALL PATCHING SHALL BE THOROUGHLY FIRST CLASS AND SHALL MATCH THE ORIGINAL MATERIAL AND CONSTRUCTION, INCLUDING FINE RATINGS IF APPLICABLE.

**16A 2-4 ROUGH-IN**

COORDINATE WITHOUT DELAY ALL ROUGHING-IN WITH OTHER DIVISIONS. CONCEAL ALL RACEWAYS EXCEPT IN UNFINISHED AREAS AND WHERE OTHERWISE INDICATED ON THE DRAWINGS.

**16A 2-5 SUPPORT SYSTEMS**

STEEL SLOTTED SUPPORT SYSTEMS (SLOTTED CHANNEL): COMPLY WITH MFMA-3, FACTORY-FABRICATED COMPONENTS FIELD ASSEMBLY, 12-GAUGE, 1-5/8"-INCH BY 1-5/8"-INCH, COPPER B-LINE, ERICO INTERNATIONAL CORPORATION, HULY, INC., POWER-STRUT, THOMAS & BETTS CORPORATION, UNISTRUT, FINISHES:

1. METALLIC COATINGS: HOT-DIP GALVANIZED AFTER FABRICATION AND APPLIED ACCORDING TO MFMA-3.

**FIELD FABRICATION:**

1. WHERE FIELD CUTTING OF STANDARD LENGTHS OF CHANNEL ARE REQUIRED, MAKE CUTS STRAIGHT AND PERPENDICULAR TO MANUFACTURED SURFACES.
2. FOR FIELD-CUT OR DAMAGED SURFACES OF COATED CHANNELS, DRESS CUT ENDS, DAMAGED SURFACES, OR BOTH, WITH AN ABRASIVE MATERIAL (E.G., FILE, GRINDING STONE, OR SIMILAR) AND CLEANER TO REMOVE OILS, RUST, SHARP EDGES AND SHARDS.
3. FOR CHANNEL WITH A FACTORY-APPLIED COATING, RE-FINISH CUT EDGES WITH A COATING COMPATIBLE WITH THE FACTORY FINISH AND AS RECOMMENDED BY THE MANUFACTURER (E.G., MANUFACTURER'S TOUCH-UP PAINT OR ZINC-RICH COLD-GALVANIZING COMPOUND, AS APPLICABLE).

**16A 2-6 PENETRATIONS**

COORDINATE SLEEVE SELECTION AND APPLICATION WITH SELECTION AND APPLICATION OF FIRE-STOPPING SPECIFIED IN DIVISION 7 SECTION "THROUGH-PENETRATION FIRESTOP SYSTEMS."

**ROOFS:**

1. COORDINATE ALL ROOF PENETRATIONS WITH ARCHITECT, OWNER, AND AS APPLICABLE, THE ROOF CONTRACTOR PROVIDING A ROOF WARRANTY.
2. KEEP ALL RACEWAY PENETRATIONS WITHIN MECHANICAL EQUIPMENT CURB, WHEREVER POSSIBLE. COORDINATE WITH DIVISION 15 WORK.
3. FLASH AND COUNTERFLASH ALL OPENINGS THROUGH ROOF, AND/OR PROVIDE NON-FABRICATED MOLDS, SEALS COMPATIBLE WITH THE ROOF CONSTRUCTION INSTALLED, OR AS REQUIRED BY THE ENGINEER, OWNER, OR ROOFING CONTRACTOR. ALL ROOF PENETRATIONS SHALL BE LEAKTIGHT AT THE TERMINATION OF THE WORK AND SHALL NOT VOID ANY NEW OR EXISTING ROOF WARRANTIES.

**WALLS AND FLOORS:**

1. SLEEVES FOR RACEWAYS AND CABLES:
  - A. STEEL PIPE SLEEVES: USE A 53/76.8MM TYPE E, DUCT, B, SCHEDULE 40, GALVANIZED STEEL, PLAIN ENDS AND DRIP BUNG.
2. SLEEVES FOR ANGULAR OPENINGS: GALVANIZED SHEET STEEL WITH MINIMUM 0.052- OR 0.138-INCH THICKNESS, AS INDICATED AND OF LENGTH TO SUIT APPLICATION.

**16A 2-7 THROUGH-PENETRATION PENETRATIONS**

FIRE-RESISTANT THROUGH-PENETRATION SEALANTS: TWO-PART, FOAMED-IN-PLACE, SILICONE SEALANT FORMULATED FOR USE WITH THROUGH-PENETRATION FIRE-STOPPING AROUND CABLES, RACEWAYS, AND CHIMNEY TRAP PENETRATIONS THROUGH FIRE-RATED WALLS AND FLOORS. SEALANTS AND ACCESSORIES SHALL HAVE FIRE-RESISTANCE RATINGS INDICATED AS ESTABLISHED BY TESTING IDENTICAL ASSEMBLIES WITH ACCORDANCE WITH ASTM E 814, BY UNDERWRITERS' LABORATORIES, INC. OR OTHER NRTL.

**1. LISTED MANUFACTURERS:**

- A. NIEL, INC.
- B. 3M CORP.
- C. RECTORSEAL.
- D. SPECIFY TECHNOLOGY INC.
- E. UNITED STATES GYPSUM COMPANY.

**SUBMITTALS**

1. SUBMIT PRODUCT DATA - MANUFACTURER'S SPECIFICATIONS AND TECHNICAL DATA FOR EACH MATERIAL INCLUDING THE COMPOSITION AND LIMITATIONS, DOCUMENTATION OF UL FIRESTOP SYSTEMS TO BE USED AND MANUFACTURER'S INSTALLATION INSTRUCTIONS TO COMPLY WITH DIVISION 7.
2. MANUFACTURER'S ENGINEERING JUDGMENT IDENTIFICATION NUMBER AND DRAWING DETAILS WHEN NO UL SYSTEM IS AVAILABLE FOR AN APPLICATION. ENGINEERING JUDGMENT SHALL INCLUDE BOTH PROJECT NAME AND CONTRACTOR'S NAME WHO WILL INSTALL FIRESTOP SYSTEM AS DESCRIBED IN DRAWINGS.
3. SUBMIT MATERIAL SAFETY DATA SHEETS PROVIDED WITH PRODUCT DELIVERED TO JOB-SITE.

**16A 2-8 ACCESS DOORS**

PROVIDE ACCESS DOORS IN CEILINGS AND WALLS, WHERE INDICATED OR REQUIRED FOR ACCESS OR MAINTENANCE TO CONCEALED EQUIPMENT INSTALLED UNDER THIS SECTION. PROVIDE CONCEALED HINGES, SCREWDRIVER-TYPE LOCK, AND ANCHOR STRAPS. MANUFACTURED BY MILCOR, ZURR, TITUS, OR EQUAL. OBTAIN ARCHITECT'S APPROVAL OF TYPE, SIZE, LOCATION AND COLOR BEFORE ORDERING.

**16A 2-9 EQUIPMENT FURNISHED BY OTHERS**

PROVIDE NECESSARY EQUIPMENT AND ACCESSORIES THAT ARE NOT PROVIDED BY THE EQUIPMENT SUPPLIER OR OWNER TO COMPLETE INSTALLATION OF EQUIPMENT FURNISHED BY OTHERS, IN LOCATIONS AS INDICATED ON THE DRAWINGS, SPECIFIED HEREIN, OR BOTH. EQUIPMENT AND ACCESSORIES NOT PROVIDED BY THE EQUIPMENT SUPPLIER MAY INCLUDE SUCH ITEMS AS FLEXIBLE CORDS AND PLOGS, AS REQUIRED FOR PROPER OPERATION OF THE COMPLETE SYSTEM, IN ACCORDANCE WITH THE MANUFACTURERS' INSTRUCTIONS.

BE RESPONSIBLE FOR CORRECT ROUGH-IN DIMENSIONS, AND VERIFY THEM WITH ENGINEER, OWNER'S REPRESENTATIVE, EQUIPMENT SUPPLIER, OR ALL THREE, PRIOR TO ROUGH-IN AND SERVICE INSTALLATIONS.

**2-10 CLEANING**

IN ADDITION TO THE REQUIREMENTS OF DIVISION 1, REMOVE FROM THE PREMISES DIRT AND REFUSE RESULTING FROM THE PERFORMANCE OF THE ELECTRICAL WORK, AS REQUIRED, TO PREVENT ACCUMULATION. COOPERATE IN MAINTAINING REASONABLY CLEAN PREMISES AT ALL TIMES. IMMEDIATELY PRIOR TO FINAL INSPECTION, MAKE A FINAL CLEANUP OF DIRT AND REFUSE RESULTING FROM THE WORK. CLEAN ALL MATERIAL AND EQUIPMENT INSTALLED UNDER THIS DIVISION. REMOVE DIRT, DUST, PLASTER, STAINS AND FOREIGN MATTER FROM ALL SURFACES. TOUCH UP AND RESTORE ALL DAMAGED FINISHES TO THEIR ORIGINAL CONDITION.

**16A 2-11 ADJUSTING, ALIGNING AND TESTING**

ADJUST, ALIGN, AND TEST ALL ELECTRICAL EQUIPMENT ON THIS PROJECT PROVIDED UNDER THIS DIVISION AND ALL ELECTRICAL EQUIPMENT FURNISHED BY OTHERS FOR INSTALLATION OR WIRING UNDER THIS DIVISION, FOR PROPER OPERATION.

TEST ALL SYSTEMS AND EQUIPMENT ACCORDING TO THE REQUIREMENTS IN NECA ATS (LATEST EDITION) AND ALL ADDITIONAL REQUIREMENTS SPECIFIED IN FOLLOWING SECTIONS.

MAINTAIN THE FOLLOWING ON THE PROJECT PREMISES AT ALL TIMES: A TRUE RMS READING VOLTMETER, A TRUE RMS READING AMMETER, AND A MEGOHMMETER INSULATION RESISTANCE TESTER. PROVIDE TEST DATA READINGS AS REQUESTED OR AS REQUIRED BY THE ENGINEER.

**16A 2-12 EQUIPMENT IDENTIFICATION**

PROVIDE EQUIPMENT IDENTIFICATION NAMEPLATES:

1. ON ALL PANELBOARDS, SWITCHES, AND STARTERS.

NAMEPLATES:

1. ENGRAVED, CONTRASTING COLOR, THREE-LAYER, LAMINATED PLASTIC INDICATING THE NAME OF THE EQUIPMENT, LOAD, OR CIRCUIT AS DESIGNATED ON THE DRAWINGS AND IN THE SPECIFICATIONS.
2. SELF-ADHERING, WITH A PERMANENT, WEATHERPROOF ADHESIVE
3. ATTACHMENT METHOD SHALL BE ACCEPTABLE TO THE MANUFACTURERS OF THE EQUIPMENT TO WHICH THE NAMEPLATES ARE BEING APPLIED.
4. COLOR: BLACK BACKGROUND WITH WHITE LETTERS FOR NORMAL POWER. LETTER HEIGHT: 1/4-INCH MINIMUM.

**16A 2-13 SYSTEM START UP**


PRIOR TO STARTING UP THE ELECTRICAL SYSTEMS:

1. CHECK ALL COMPONENTS AND DEVICES.
2. LUBRICATE ITEMS ACCORDINGLY.
3. TIGHTEN SCREWS AND BOLTS FOR CONNECTIONS AND TERMINALS ACCORDING TO MANUFACTURER'S PUBLISHED TORQUE-TIGHTENING VALUES. IF MANUFACTURER'S TORQUE VALUES ARE NOT INDICATED, USE THOSE SPECIFIED IN UL 88.
4. ADJUST TAPS ON EACH TRANSFORMER TO THE RATED SECONDARY VOLTAGE.

CHECK AND RECORD BUILDING'S SERVICE ENTRANCE VOLTAGE, GROUNDING CONDITIONS, GROUNDING RESISTANCE, AND PROPER PHASING.

BALANCE THE SINGLE-PHASE LOADS AT EACH PANELBOARD, REDISTRIBUTING BRANCH CIRCUIT CONNECTIONS UNTIL BALANCE IS ACHIEVED. DO NOT TYPE UP FINAL PANELBOARD DIRECTORIES UNTIL ALL BALANCING AND REDISTRIBUTION OF CIRCUITS ARE COMPLETE.


7. REPLACE ALL BURNED-OUT LAMPS AND LAMPS USED FOR TEMPORARY CONSTRUCTION LIGHTING IN PERMANENT LIGHT FIXTURES.
8. AFTER ALL SYSTEMS HAVE BEEN INSPECTED AND ADJUSTED, CONFIRM ALL OPERATING FEATURES REQUIRED BY THE DRAWINGS AND SPECIFICATIONS AND MAKE FINAL ADJUSTMENTS AS NECESSARY.
9. PROVIDE SEISMIC RESTRAINTS PER APPLICABLE CODE AND AS SPECIFIED OR INDICATED. DESIGN RESTRAINTS TO PREVENT PERMANENT DISPLACEMENT IN ANY DIRECTION CAUSED BY LATERAL MOTION, OVERTURNING, OR UPLIFT. SEISMIC RESTRAINTS DESIGN SHALL BE BASED ON SEISMIC CATEGORY 2. VERIFY SEISMIC CATEGORY DESCRIBED ON STRUCTURAL DRAWINGS AND PROVIDE SEISMIC RESTRAINTS BASED ON STRINGENT REQUIREMENTS.



5450 E. High Street, Suite 200  
Phoenix, Arizona 85054  
P: 480.515.5123  
www.sra360.com

**Christian Brothers Automotive**  
Wickham Road  
Melbourne, Florida

**Christian Brothers Automotive**  
17726 Katy Freeway, Ste. 200  
Houston, TX 77064



Revisions	
1/23/20 - Prototype Update	
4/1/20 - City Comments	
4/9/20 - T2 Client Rev.	

Project No. 19-097

Drawn By:

Date: 03/06/20

Sheet Title:

**ELECTRICAL SPECIFICATION**

Drawing No.

**E-5.01**

10RHS-11-2019

THIS SHEET IS PART OF THE CONSTRUCTION DOCUMENTS. OTHER SHEETS INCLUDING SPECIFICATIONS APPLY. THAT SHOWN HEREON IS SCHEMATIC IN NATURE AND NOT TO BE USED AS A SHOP DRAWING. THEREFORE, INCLUDE ALL MODIFICATIONS REQUIRED TO CONFORM TO SITE CONDITIONS AND THE EQUIPMENT AND MATERIAL USED. VERIFY LOCATIONS AND DIMENSIONS OF ALL ARCHITECTURAL AND STRUCTURAL ELEMENTS AS SHOWN ON THEIR RESPECTIVE DOCUMENTS. THESE ELEMENTS ARE SHOWN FOR REFERENCE AND SHALL BE VERIFIED PRIOR TO CONSTRUCTION AND THE ENGINEER ASSUMES NO LIABILITY FOR THE ACCURACY OF THESE ELEMENTS. NO DESIGN RESPONSIBILITY IS ASSUMED FOR ANY PORTION OF THE WORK THAT THE PROFESSIONAL ENGINEER HAS NOT SIGNED AND SEALED PER STATE/PROVINCE REQUIREMENTS.

**Dialectic**

Dialectic Inc.  
310 W 20th Street, Suite 200  
Kansas City, MO 64108  
Florida Certificate of Authorization Number 8039

T 816-997-9601  
F 816-997-9602  
DialecticEng.com

Copyright 2020