CONSTRUCTION PLANS

FOR

FREEDOM PARK PHASE 3

3301 ROFF AVENUE, MACON, GA 31204

SHEET INDEX

No.	DESCRIPTION
C0.1	COVER SHEET
C1.0	EXISTING CONDITIONS AND DEMOLITION PLAN
C2.0	SITE PLAN
C3.0	GRADING PLAN
C4.0	EROSION CONTROL PLAN - INITIAL PHASE
C4.1	EROSION CONTROL PLAN - INTERMEDIATE PHASE
C4.2	EROSION CONTROL PLAN - FINAL PHASE
C4.3 - C4.6	EROSION, SEDIMENTATION & POLLUTION CONTROL NOTES
L5.0	LANDSCAPE PLAN
C6.0 - C6.10	CONSTRUCTION DETAILS
C7.0	STORM PROFILES
E1 - E2	ELECTRICAL PLANS
I1 - I2	IRRIGATION PLANS

LEGEND:

EXIST. POWER POLE
EXIST. POWER POLE W/GUY WIRE
EXIST. LIGHT STANDARD
EXIST. ELECTRIC TRANSFORMER
EXIST. WATER METER
EXIST. WATER VALVE
EXIST. UNKNOWN UTILITY STRUCTURES
EXIST. TELEPHONE MONUMENT
EXIST. TELEPHONE BOX
EXIST. GAS METER
EXIST. GAS VALVE
EXIST. SANITARY SEWER MANHOLE
EXIST. CLEAN OUT
EXIST. JUNCTION BOX/STORM SEWER MANHOLE
EXIST. CATCH BASIN
EXIST. DROP INLET
EXIST. STORM SEWER LINE
EXIST. FLARED END SECTION
EXIST. YARD INLET
EXIST. SANITARY SEWER LINE
EXIST. OVERHEAD POWER LINE
EXIST. OVERHEAD TELEPHONE LINE
APPROX. LOCATION UNDERGROUND POWER LINE
APPROX. LOCATION UNDERGROUND TELEPHONE LINE
APPROX. LOCATION UNDERGROUND GAS LINE
APPROX. LOCATION UNDERGROUND WATER LINE
APPROX. LOCATION CHILLED WATER LINE
APPROX. LOCATION STREAM WATER LINE
EXIST. FENCE LINE (AS NOTED)
EXIST. SIGN (AS NOTED)
EXIST. TREE (AS NOTED)
TEMPORARY BENCHMARK (TBM)
CONCRETE MONUMENT FOUND
PROPERTY CORNER
FIELD LOCATED PIN (AS NOTED)
EXIST. SPOT ELEVATION
EXIST. CONTOUR ELEVATION
IRON PIN SET (1/2" REBAR)
IRON PIN FOUND
POINT OF BEGINNING
RIGHT-OF-WAY
NAIL OR CHISEL
NON-DISC SETBACK LINE
DEED BOOK
PAGE
TOP OF CURB
BOTTOM OF CURB
REINFORCED CONCRETE PIPE
CORRUGATED METAL PIPE
POLYVINYL CHLORIDE PIPE
DUCTILE IRON PIPE
HIGH DENSITY POLYETHYLENE
INVERT
THROAT
CONCRETE
CURB & GUTTER
AMERICANS WITH DISABILITIES ACT
NEW SANITARY SEWER LINE
NEW CHILLED WATER LINE
NEW STREAM WATER LINE
NEW FIRE LINE
NEW WATER LINE
NEW GAS LINE
NEW STORM SEWER
NEW GATE VALVE
NEW FIRE HYDRANT
NEW DROP INLET
NEW HEADWALL
NEW CATCH BASIN
NEW MANHOLE
NEW CLEANOUT
NEW SPOT ELEVATION
NEW CONTOUR
NEW NUMBER OF PARKING SPACES
STORM STRUCTURE IDENTIFICATION
SANITARY STRUCTURE IDENTIFICATION
NEW ASPHALT PAVEMENT
NEW CONCRETE SIDEWALK
NEW CONCRETE PAVEMENT
HEAVY DUTY ASPHALT PAVEMENT
EXISTING PAVEMENT AREA TO BE DEMOLISHED
STRUCTURE/STREAM TO BE DEMOLISHED
TRAFFIC DIRECTION ARROWS (FOR INFORMATION ONLY)
NEW ADA ACCESSIBLE SYMBOL

APPROXIMATE CONSTRUCTION SCHEDULE

ACTIVITY	TIME (WEEKS) 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20
INSTALL TREE PROTECTION MEASURES	
INSTALL CONSTRUCTION EXIT, SEDIMENT BARRIERS & OTHER PERIMETER CONTROLS	
TEMPORARY SEDIMENT BASIN CONSTRUCTION	
CLEARING & GRUBBING OF AREAS NECESSARY FOR THE INSTALLATION OF SEDIMENT RETENTION BASINS & EROSION CONTROL STRUCTURES	
INSTALLATION OF PERMANENT PONDS & RELATED STRUCTURES	
CLEARING & GRUBBING OF REMAINING AREAS	
ROUGH GRADING	
INSTALLATION OF SANITARY SEWER SYSTEM	
INSTALLATION OF STORMWATER MANAGEMENT SYSTEM	
INSTALLATION OF CURB & GUTTER	
FINAL GRADING	
INSTALLATION OF WATER SYSTEM	
INSTALLATION OF GRAVEL SUBBASE FOR ROADS	
ASPHALT PAVING	
BUILDING CONSTRUCTION	
INSTALLATION OF UNDERGROUND UTILITIES	
TEMPORARY STABILIZATION / LANDSCAPING	
PERMANENT STABILIZATION / LANDSCAPING	
REMOVAL OF EROSION & SEDIMENT CONTROL MEASURES	
MAINTENANCE OF EROSION CONTROL MEASURES	
MAINTENANCE OF TREE PROTECTION MEASURES	

THIS ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES PRIOR TO, OR CONCURRENT WITH, LAND DISTURBING ACTIVITIES

EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF SUCH IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE.

ALL EXPOSED AREAS WILL BE GRASSED IF THEY WILL BE LEFT EXPOSED FOR 14 DAYS.

APPROXIMATE PROJECT START DATE: 06/05/2020
APPROXIMATE PROJECT COMPLETION DATE: 05/31/2020

GENERAL NOTES:

SITE NOTES

1. SITE ADDRESS: 3301 ROFF AVENUE, MACON, GA 31204
2. SITE TAX PARCEL NUMBERS: N072-0095
3. TOTAL PROJECT AREA: 39.3 ACRES DISTURBED AREA ± 2.7 ACRES

SURVEY REFERENCE

1. BOUNDARY AND TOPOGRAPHIC INFORMATION WAS TAKEN FROM THAT BOUNDARY AND TOPOGRAPHIC SURVEY FOR MACON-BIBB COUNTY PARKS AND RECREATION DEPARTMENT, PREPARED BY (I) PREPARED BY, DATED (a) SURVEY DATE.
2. PROJECT BENCHMARK: [000] NAIL AND WASHER SET IN POWER POLE ELEVATION = 386.62ft.

STATE WATERS

1. STATE WATERS ARE PRESENT WITHIN 200' OF THIS SITE. ANY STATE WATERS PRESENT ON THIS SITE ARE DULY INDICATED HEREON AND ANY APPLICABLE BUFFER RESTRICTIONS ARE NOTED AND ADHERED TO.

WETLANDS

1. THERE ARE WETLANDS LOCATED ON THIS SITE. THE OWNER OF THE PROPERTY IS RESPONSIBLE FOR COMPLIANCE WITH THE CORPS OF ENGINEERS REQUIREMENTS REGARDING WETLANDS.

UTILITIES

1. ALL PROPOSED WATER SERVICE FOR THIS PROJECT TO BE PUBLIC. PUBLIC WATER SERVICE TO BE PROVIDED BY BIBB COUNTY.
2. ALL PROPOSED SANITARY SEWER TO BE GRAVITY FLOW. ALL PROPOSED SANITARY SEWER SERVICE FOR THIS PROJECT TO BE PUBLIC. PUBLIC SANITARY SEWER SERVICE TO BE PROVIDED BY BIBB COUNTY.

BUFFERS

1. NO BUFFERS ON SITE.

CONSTRUCTION

1. ALL CONSTRUCTION SHALL CONFORM TO CITY OF MACON, BIBB COUNTY, AND/OR GEORGIA D.O.T. STANDARDS AND SPECIFICATIONS.

GENERAL NOTES

1. NON-EXEMPT ACTIVITIES SHALL NOT BE CONDUCTED WITHIN THE 25 OR 50-FOOT UNDISTURBED STREAM BUFFERS AS MEASURED FROM THE POINT OF WRESTED VEGETATION OR WITHIN 25-FEET OF THE COASTAL MARSHLAND BUFFER AS MEASURED FROM THE JURISDICTIONAL DETERMINATION LINE WITHOUT FIRST ACQUIRING THE NECESSARY VARIANCES AND PERMITS.
2. WASTE MATERIALS SHALL NOT BE DISCHARGED TO WATERS OF THE STATE, EXCEPT AS AUTHORIZED BY A SECTION 404 PERMIT.

APPROVED
Date: 03/30/2020
MACON WATER AUTHORITY
By: Engineering Division

WETLAND CERTIFICATION

The design professional, whose seal appears hereon, certifies the following, The National Wetland Inventory maps have been consulted; and the appropriate plan sheet DOES NOT indicate areas of United States Army Corps of Engineers Jurisdictional Wetlands as shown on the maps; and if wetlands are indicated, the land owner or developer has been advised that land disturbance of protected wetlands shall not occur unless the appropriate federal wetlands alteration (Section 404) permit has been obtained.

STEVEN J. BENNETT, P.E.
GEORGIA REG. No. 19806
FOR THE FIRM OF TRAVIS PRUITT & ASSOCIATES, INC.
Date 3-16-20

* THE WORD "CERTIFY", AS USED IN ANY OF ITS FORMS HEREIN, IS AN EXPRESSION OF PROFESSIONAL OPINION ONLY AND SHALL NOT BE CONSTRUED OR UNDERSTOOD TO BE A STATEMENT OF FACT, A WARRANTY, OR A GUARANTEE OF ANY KIND, EXPRESSED OR IMPLIED.

I CERTIFY UNDER PENALTY OF LAW THAT THIS PLAN WAS PREPARED AFTER A SITE VISIT TO THE LOCATIONS DESCRIBED HEREIN BY MYSELF OR MY AUTHORIZED AGENT, UNDER MY DIRECT SUPERVISION.

STEVE J. BENNETT, PE
GA SWCC LEVEL II CERTIFICATION NO.: 0000010459
FOR THE FIRM - TRAVIS PRUITT & ASSOCIATES, INC.
Date 3-16-20

Order Plans @ WWW.LDILine.com

LOCATION MAP
NOT TO SCALE

OWNER
MACON-BIBB COUNTY PARKS AND RECREATION DEPARTMENT
[illegible] SMOKE GLOVER DRIVE
MACON, GA 31201
478-621-9280

24 HOUR EMERGENCY CONTACT
ROBERT WALKER
478-621-9280
E-mail: rwalker@maconbibb.us

TAX PARCEL ID: N072-0095
SITE AREA: 39.3 ACRES
DISTURBED AREA: 2.7 ACRES

PROJECT DESCRIPTION:
Replacement of existing playgrounds, construction of new pavilion and fishing pier. Existing pavilion to have roof shingles replaced and all wood surfaces refinished. Area drains will also be added to address erosion issues.

NOTE: CONSTRUCTION ENTRANCE IS LOCATED AT THE FOLLOWING LOCATION.
LAT: 32°51'01"N; LONG: 83°40'43"W

PREPARED BY: Steve J. Bennett
GSWCC LEVEL II CERTIFICATION No.: 0000010459
EXPIRATION DATE: 05/08/2021

FLOOD HAZARD NOTE:
THIS PROPERTY DOES NOT LIE WITHIN A 100 YEAR FLOOD HAZARD ZONE AS DEFINED BY THE F.E.M.A. FLOOD INSURANCE RATE MAP OF BIBB COUNTY COUNTY, GEORGIA COMMUNITY PANEL NUMBER 13021C0131F, DATED 04/02/2017.

NOTE: ALL DIMENSIONS ARE TO FACE OF CURB, FACE OF BUILDING, OR CENTER OF STRUCTURE, UNLESS OTHERWISE NOTED.

NOTE: ALL CURB RADII ARE 5 FT. UNLESS OTHERWISE NOTED.

NOTE: ALL PIPE LENGTHS ARE SCALED LENGTHS FROM CENTER OF STRUCTURE. CONTRACTOR SHALL VERIFY PRIOR TO ORDERING PIPE.

NOTE: CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING UTILITIES. CONTRACTOR SHALL HAVE ALL UTILITIES FLAGGED WITH INVERT ELEVATIONS PRIOR TO CONSTRUCTION. NOTIFY ENGINEER OF ANY/ALL DISCREPANCIES OR ADDITIONAL UTILITIES ENCOUNTERED.

INFORMATION REGARDING THE REPUTED PRESENCE, SIZE, CHARACTER AND LOCATION OF EXISTING UNDERGROUND UTILITIES AND STRUCTURES IS SHOWN HEREON. THERE IS NO CERTAINTY OF THE ACCURACY OF THIS INFORMATION AND IT SHALL BE CONSIDERED IN THAT LIGHT BY THOSE USING THIS DRAWING. THE LOCATION AND ARRANGEMENT OF UNDERGROUND UTILITIES AND STRUCTURES SHOWN HEREON MAY BE INACCURATE AND UTILITIES AND STRUCTURES NOT SHOWN MAY BE ENCOUNTERED. THE OWNER, HIS EMPLOYEES, HIS CONSULTANTS AND HIS CONTRACTORS SHALL HEREBY DISTINCTLY UNDERSTAND THAT THE SURVEYOR IS NOT RESPONSIBLE FOR THE CORRECTNESS OR SUFFICIENCY OF THIS INFORMATION.

GEORGIA811 Utilities Protection Center, Inc.
1-800-282-7411
Know what's below. Call before you dig.

© Copyright 2020
Travis Pruitt & Associates, Inc.
THESE DRAWINGS AND THEIR REPRODUCTIONS ARE THE PROPERTY OF THE ENGINEER AND MAY NOT BE REPRODUCED, PUBLISHED, OR USED IN ANY WAY WITHOUT THE WRITTEN PERMISSION OF THE ENGINEER.

NO	DATE	DESCRIPTION	BY
6			
5			
4			
3			
2			
1		ADDRESS COMMENTS	DW
0	03/30/2020	PERMITTING	SJB

REVISIONS

4317 Park Drive, Suite 400
Norcross, Georgia 30093
Phone: (770) 416-7911
Fax: (770) 416-8798
www.travispruitt.com
CONTACT PERSON: EDWARD J. ANDERSON
e-mail: landdesign@travispruitt.com

Travis Pruitt & Associates, Inc. — Engineers • Surveyors • Planners • Landscape Architects

COVER SHEET

FREEDOM PARK PHASE 3

3301 ROFF AVENUE, MACON, GA 31204 • LAND LOTS 2 AND 3 • 11TH DISTRICT • CITY OF MACON • BIBB COUNTY

GEORGIA REGISTERED LANDSCAPE ARCHITECT EDWARD J. ANDERSON

For The Firm
Travis Pruitt & Associates, Inc.

DATE: 02/14/2020
SCALE: N/A
CN: 190452PN
JN: 190452
FN: 166-D-038
SHEET NO: C0.1

W:\2019\190452\Engineering\CAD\Drawings\190452PN.dwg, COVER SHEET, Dwatson, Mar. 12, 20 2:43:22 PM, 1:1