



**Macon-Bibb County Government**  
Procurement Department  
Government Center  
700 Poplar Street, Suite 308  
Macon, Georgia 31201  
(478) 803-0550  
Fax (478) 751-7252

June 15, 2020

**ADDENDUM # 2**

To: ALL PROSPECTIVE FIRMS

Re: INVITATION FOR BIDS: 20-076-LS Freedom Park Phase 3

Questions and Answers

1. What is the model number for the polygon structure?

**I have specified Poligon as the manufacturer, but any pavilion that can match exactly the pavilion used in Phase 2 can be used if approved.**

**See attached Poligon specifications and photograph of Phase 2 pavilion.**

2. Chain link fencing black vinyl or galvanized?

**All fencing will be black vinyl.**

3. Are both play structures and swing set provided by and installed by county?

**Play equipment will be supplied by Macon/Bibb. The sand box and swing will also be supplied by Macon/Bibb.**

4. What are the specs. for the basketball court shade benches?

**There will be 4 benches located around the playground. (see plan) The Victor Stanley model shown in the detail will be used.**

5. What are the specs for the refurbished structure?

**A 25-year asphalt shingle. We will choose color as part of the submit task during construction.**

6. Can you please give some more information concerning the 20' x 20' Polygon Structure? The plans call out "see Specs" and as of yet we could not find any information that would allow us to price.

**I have specified Poligon as the manufacturer, but any pavilion that can match exactly the pavilion used in Phase 2 can be used if approved.**

**See attached Poligon specifications and photograph of Phase 2 pavilion.**

7. Is the quantity sheet accurate to the required items and considered part of the contract documents?

**The revised item sheet is attached showing quantities.**

8. On drawing C2.0 a 20' X 20' Polygon structure is listed. On the quantity sheet a 30' X 30' Polygon structure is listed. Which is the correct size? I cannot find any specifications or drawings of the Polygon structure either.

**I have specified Poligon as the manufacturer, but any pavilion that can match exactly the pavilion used in Phase 2 can be used if approved.**

**See attached Poligon specifications and photograph of Phase 2 pavilion.**

9. Will the Musco lighting be by the owner or required from the contractor?

**There is no Musco lighting per revised item list.**

10. Where do the Bike Racks and Trash Cans from the quantity sheet install?

**The one bike rack will need to be approved by Macon/Bibb.**

**There will be four trash receptacles in the park. There locations are as follows: Adjacent to the sidewalk in front of the 20'x20' pavilion, adjacent to the sidewalk at the entrance to the playground area, adjacent to the sidewalk at the entrance to the basketball courts, adjacent to the sidewalk next to the existing large pavilion.**

11. Where does the fiber optic line on the quantity sheet install?

**There is no fiber optic line.**

12. Are basketball backstops required in the project? If so, what are the specifications?

**Any reference to dugouts and backstops can be ignored.**

13. On C2.0 note 2 it calls for a water hook up and a water fountain. Where are they located?

**The water fountain will need to be commercial grade to be approved by Macon/Bibb.**

14. C2.0 states Water Hook up & water fountain. Where is the water fountain to be located and what water line does it connect to? Can you provide a model # for fountain?

**The water fountain will need to be commercial grade to be approved by Macon/Bibb.**

15. Who provides the basketball goals? If by Contractor, please issue specification.

**As approved by Macon/Bibb**

16. C6.0 shows a trash receptacle, where are they installed and how many are required?

**There will be four trash receptacles in the park. There locations are as follows: Adjacent to the sidewalk in front of the 20'x20' pavilion, adjacent to the sidewalk at the entrance to the playground area, adjacent to the sidewalk at the entrance to the basketball courts, adjacent to the sidewalk next to the existing large pavilion.**

17. C2.0 states 17,762 SF of sod in open event area. L1.0 shows Sod in 3 locations. Are we to figure 17,762 SF of sod? If not, please clarify the limits of the sod.

**The area inside 4' perimeter fence will be sodded and is 17,760 square feet. These areas will also have irrigation. (See irrigation plan)**

18. C6.7 Can GADOT CPOP be used for the SD1-S?

**Yes.**

19. I had a question regarding the pavilion for this project. It references a new pavilion and spec but I cannot find a spec or a detail on how it needs to be built. Also, I wanted to verify that the steel framing in the dugouts is a carryover from another phase and is not in this scope.

**Any reference to dugouts and backstops can be ignored.**

20. Construction Bid Item Schedule is showing 2 (Two) Bike Racks, what brand/style of Bike Rack is to be used?

**The one bike rack will need to be approved by Macon/Bibb.**

21. Are the basketball goals and post to be replaced or existing to be refurbished? If to be replaced, please specify brand and cut-sheet/design of product owner wants to use.

**As approved by Macon/Bibb.**

22. There are benches in two different locations count of 6 (six) total per Construction Bid Item Schedule, will the Victor Stanley bench specified be used in both areas?

**There will be 4 benches located around the playground. (see plan) The Victor Stanley model shown in the detail will be used.**

23. Construction bid item schedule is showing 4 (Four) Picnic Tables, what brand/style of Picnic Table is to be used?

**Macon/Bibb will supply picnic tables.**

24. There are no specifications or details for the 20' x 20' Polygon Structure. Please provide.

**I have specified Poligon as the manufacturer, but any pavilion that can match exactly the pavilion used in Phase 2 can be used if approved.**

**See attached Poligon specifications and photograph of Phase 2 pavilion.**

25. There are no details for the 20' x 20' slab under the Polygon Structure. Please provide.

**I have specified Poligon as the manufacturer, but any pavilion that can match exactly the pavilion used in Phase 2 can be used if approved.**

**See attached Poligon specifications and photograph of Phase 2 pavilion.**

26. There is a note to replace roofing on the existing Pavilion. Please provide specifications for the roofing required.

**The current roof on the pavilion needs to be replaced with shingles approved by Macon/Bibb. Any rotting plywood found during the removal of existing shingles needs to be replaced. The wood columns and roof structure will need to be sanded and a new coat of polyurethane applied.**

27. Addendum #1 states that the Playground Equipment is by the Owner. Does this include the sand box? There are no details for the sandbox.

**Play equipment will be supplied by Macon/Bibb. The sand box and swing will also be supplied by Macon/Bibb.**

28. Trash Receptacles are shown in the details but not on the plans. How many are required?

**There will be four trash receptacles in the park. There locations are as follows: Adjacent to the sidewalk in front of the 20'x20' pavilion, adjacent to the sidewalk at the entrance to the playground area, adjacent to the sidewalk at the entrance to the basketball courts, adjacent to the sidewalk next to the existing large pavilion.**

29. Specification Section 02 41 00 Demolition of Existing Facilities 3.01 – F. Dust-tight, weather tight partitions shall be erected to protect the concession stand from dust and weather while wrecking is in progress and until such time as closures have been made. Is this required for this project?

**The use of dust-tight, weather tight partitions mentioned in Section 02 41 00 of the specifications can be disregarded.**

30. Specification Section 04 22 00 Masonry is included in the Specification Manual. Where is masonry required on the project?

**There is no masonry on the project.**

31. Specification Section 05 50 00 Metal Fabrications is included in the Specification Manual. It references Steel framing for dugouts. There are no dugouts indicated in the plans.

**Any reference to dugouts and backstops can be ignored.**

32. On sheet C2.0 #10 - 6' Concrete Sidewalk references 4/C6.0. This detail is an expansion joint detail and there are no specifications for the sidewalks. Please provide specifications for the 6' sidewalks and the 4' tricycle track .

**Detail 3 on sheet C6.0 details concrete paving. Details 4 and 5 on sheet C6.0 detail expansion joints and saw cut joints.**

33. Basketball Court Detail on Sheet C6.0, Detail 6 not detailing color of court nor does it have specification for the Liquid Applied Acrylic Surface System, please provide direction.

**The basketball courts will be coated with an acrylic emulsion coating made by Sportmaster. I have included the specifications for the Neutral Concentrate, the ColorPlus Pigment Dispersion, and the white line paint. The color will be approved by Macon/Bibb. See attached SportMaster Technical Data Sheet.**

**See attached revised item sheet showing quantities.**

**See attached SportMaster Technical Data Sheet.**

**See attached Polygon specifications for 20' x 20' polygon structure.**

**See attached photograph of Phase 2 pavilion.**

Please incorporate this change into the Invitation for Bid and acknowledge receipt of this addendum on your bid form.

Sincerely,

*Lauren N. Schultz*

Lauren N. Schultz  
Procurement Officer  
[lschultz@maconbibb.us](mailto:lschultz@maconbibb.us)  
478-803-0550