



- Foundation Plan Notes**
1. FINISH FLOOR (TOP OF SLAB) ELEVATION 0'-0", UNLESS NOTED.
 2. TOP OF INTERIOR FOOTING -1'-0" BELOW FINISH FLOOR, UNLESS NOTED.
 3. TOP OF EXTERIOR FOOTING -1'-4" BELOW FINISH FLOOR, UNLESS NOTED. STORM SHELTER'S PERIMETER FOOTING IS CONSIDERED AN EXTERIOR FOOTING.
 4. FOR SLAB ON GRADE CONSTRUCTION, SEE GENERAL NOTES AND TYPICAL DETAILS.
 5. FOR SLAB RECESS AND RAMP LOCATION, SEE ARCHITECTURAL DRAWINGS.
 6. GENERAL CONTRACTOR SHALL COORDINATE TILE JOINT LOCATIONS WITH CONTROL JOINTS.
 7. FOOTING STEP ELEVATIONS AND LOCATION ARE APPROXIMATE. GENERAL CONTRACTOR SHALL COORDINATE ALL FOOTING STEPS WITH CIVIL, PLUMBING, AND UTILITY DRAWINGS.
 8. INDICATES EXTENT OF THE TORNADO STORM SHELTER DESIGN PER ICC 500-2014.

Foundation Plan
 1/8" = 1'-0"

Structural Column Schedule

DESIGNATION	SIZE	BASE PLATE	ANCHOR RODS	NOTES
C1	HSS4x4x1/4	SEE TYP DETAIL	SEE TYP DETAIL	
C2	HSS6x6x1/4	SEE TYP DETAIL	SEE TYP DETAIL	

Structural Pedestal Schedule

DESIGNATION	LENGTH	WIDTH	VERTICAL	TIES	NOTES
P1	1'-6"	1'-6"	8#7	#3@12"	

Structural Foundation Schedule

DESIGNATION	LENGTH	WIDTH	THICKNESS	TOP REINF	BOTTOM REINF	NOTES
F4	4'-0"	4'-0"	1'-4"	---	5#5 EW	
F5	5'-0"	5'-0"	1'-4"	---	6#5 EW	
F6	6'-0"	6'-0"	1'-4"	7#5 EW	7#5 EW	
F6.5	6'-0"	6'-0"	1'-6"	8#5 EW	6#5 EW	
F7	7'-0"	7'-0"	1'-6"	9#5 EW	9#5 EW	
F8	8'-0"	8'-0"	1'-6"	8#5 EW	8#5 EW	
F8.5	8'-0"	8'-0"	2'-0"	8#7 EW	6#7 EW	
F9	9'-0"	9'-0"	2'-0"	---	9#7 EW	

NEW LIBRARY FOR THE CITY OF OPELIKA
 GLENN STREET
 OPELIKA, ALABAMA 36801



SHEET TITLE:
 FOUNDATION PLAN

PROJ. MGR.: AC
 DRAWN: MBJ
 DATE: JUNE 1, 2020
 CHECKED BY: BRH
 REVISIONS:
 # Description Date

JOB NO. 19-32
 SHEET NO. S2.1
 11 OF 18
 SEQUENCE NO. 59 / 90

