ABBREVIATIONS

A	
@	AT
AB	ANCHOR BOLT
ABV	ABOVE
AC	AIR CONDITIONER
ACT	ACOUSTIC TILE CEILING
ADD	ADDENDUM
ADJ	ADJACENT
ADJT	ADJUSTABLE
AFF	ABOVE FINISHED FLOOR
ALT	ALTERNATE
ALUM	ALUMINUM
AMP	AMPERES
ANCR	ANCHOR
ANOD	ANODIZED
APPROX	APPROXIMATE
ARCH	ARCHITECT/URAL
ASPH	ASPHALT
B	
B.O.	BOTTOM OF
BD	BOARD
BLDG	BUILDING
BLK	BLOCK
BLKG	BLOCKING
BM	BEAM
BM.	BENCH MARK
BOT	BOTTOM
BP	BASE PLATE
BRG	BEARING
BRZ	BRONZE
BTU	BRITISH THERMAL UNIT
BUR	BUILT-UP ROOF
C	
CAB	CABINET
CB	CATCH BASIN
CEM.	CEMENT
CFT	CUBIC FOOT
CI	CAST IRON
CIP	CAST IN PLACE
CJ	CONTROL JOINT
CL	CENTER LINE
CLR	CLEAR(ANCE)
CMU	CONCRETE MASONRY UNIT
CO	CASED OPENING
CO	CLEAN OUT
COL	COLUMN
CONC	CONCRETE
CONN	CONNECTION
CONST	CONSTRUCTION
CONT	CONTINUOUS
CORR	CORRUGATED
CPT	CARPET(ED)
CYD	CUBIC YARD
D	
D	DRYER
DBL	DOUBLE
DEM	DEMOLITION
DEV	DEVELOPMENT
DF	DRINKING FOUNTAIN
DH	DOUBLE HUNG
DI	DROP INLET
DIA	DIAMETER
DIAG	DIAGONAL
DIM	DIMENSION
DIST	DISTRIBUTED
DIV	DIVISION
DL	DEAD LOAD
DN	DOWN
DR	DOOR
DS	DOWN SPOUT
DTL	DETAIL
DW	DISHWASHER
DWG	DRAWING
E	
E	EAST
EA	EACH
EF	EACH FACE
EIFS	EXTERIOR INSULATION FINISH SYSTEM
EJ	EXPANSION JOINT
ELEC	ELECTRICAL
ELEV	ELEVATION
EMER	EMERGENCY
EQ	EQUAL
EW	EACH WAY
EWH	ELECTRICE WATER HEATER
EXH	EXHAUST
EXP	EXPOSED
EXT	EXTERIOR
F	
FB	FACE BRICK
FBO	FURNISHED BY OTHERS
FD	FLOOR DRAIN
FDN	FOUNDATION
FE	FIRE EXTINGUISHER
FEC	FIRE EXTINGUISHER AND CABINET
FF	FINSHED FLOOR
FFE	FINISHED FLOOR ELEVATION
FIN	FINISH
FLR	FLOOR(ING)
FLSH	FLASHING
FOC	FACE OF CONCRETE
FOF	FACE OF FINISH
FOM	FACE OF MASONRY
FOS	FACE OF STUD
FR	FIRE RATED
FR GYP BD	FIRE RATED GYPSUM BOARD
FRP	FIBER REINFORCED PANEL
FRT	FIRE RETARDANT TREATED WOOD
FT	FOOT
FTG	FOOTING
G	
GA	GAUGE
GALV	GALVANIZED
GB	GRAB BARS
GC	GENERAL CONTRACTOR
GI	GALVANIZED IRON
GL	GLASS
GR	GRADE
GWH	GAS WATER HEATER
GYP BD	GYPSUM BOARD
H	
HB	HOSE BIBB
HC	HOLLOW CORE
HD	HEAD
HDN	HOLD-DOWN
HDR	HEADER
HGR	HANGER
HM	HOLLOW METAL
HMD	HOLLOW METAL DOOR
HMF	HOLLOW METAL FRAME
HORZ	HORIZONTAL
HRD	HARD
HSS	HOLLOW STRUCTURAL STEEL SECTION
HT	HEIGHT
HTG	HEATING
HVAC	HEATING/VENTILATING/ AIR CONDITIONING
I	
ID	INSIDE DIAMETER
IN	INCH(ES)
INCL	INCLUDE
INSUL	INSULATION
INT	INTERIOR
J	
JC	JANITOR CLOSET
JST	JOIST
JT	JOINT
K	
k	KIPS
KSF	KIPS PER SQUARE FOOT
L	
LAM	LAMINATED
LAV	LAVATORY
LF	LINEAL FOOT
LG	LONG
LL	LIVE LOAD
LLH	LONG LEG HORIZONTAL
LLV	LONG LEG VERTICAL
LT	LIGHT
LVR	LOUVER
LW	LIGHT WEIGHT
LWB	LIGHT WEIGHT BLOCK
M	
MAS	MASONRY
MATL	MATERIAL
MAX	MAXIMUM
MCJ	MASONRY CONTROL JOINT
MECH	MECHANICAL
MFG	MANUFACTURING
MFR	MANUFACTURER
MH	MANHOLE
MIN	MINIMUM
MIR	MIRROR
MISC	MISCELLANEOUS
MO	MASONRY OPENING
MTD	MOUNTED
MTL	METAL
MULL	MULLION
N	
N	NORTH
NIC	NOT IN CONTRACT
NO, #	NUMBER
NOM	NOMINAL
NTS	NOT TO SCALE
O	
OA	OVERALL
OC	ON CENTER
OD	OUTSIDE DIAMETER OR OVERFLOW DRAIN
OFCI	OWNER FURNISHED CONTRACTOR INSTALLED
OH	OVER HEAD
OPNG	OPENING
OPP	OPPOSITE
OVN	OVEN
OWSJ	OPEN WEB STEEL JOIST
P	
PC	PRECAST
PEJ	PREMOLDED EXPANSION JOINT
PERF	PERFORATED
PF	PRE-FINISHED
PL	PLATE
PL	PROPERTY LINE
PLAM	PLASTIC LAMINATE
PNT	PAINT(ED)
POS	POINT OF SALE
PP	POWER POLE
PR	PAIR
PSF	POUNDS PER SQUARE FOOT
PSI	POUNDS PER SQUARE INCH
PT	PRESSURE TREATED
PTD	PAPER TOWEL DISPENSER
PTR	PAPER TOWEL RECEPTOR
PVC	POLYVINYL CHLORIDE
PVMT	PAVEMENT
PWD	PLYWOOD
R	
RA	RETURN AIR
RAD	RADIUS
RB	RUBBER BASE
RD	ROOF DRAIN
REC	RECESSED
REF	REFERENCE/REFER
REFL	REFLECTED
REINF	REINFORCED
REQ'D	REQUIRED
RET	RETAINING
REV	REVISION
RM	ROOM
RO	ROUGH OPENING
ROW	RIGHT OF WAY
RS	ROUGH SAWN
RSC	ROUGH SAWN CEDAR
S	
S	SOUTH
S&V	STAIN AND VARNISH
S.DISP.	SOAP DISPENSER
SAT	SUSPENDED ACOUSTICAL CEILING
SC	SOLID CORE
SCH	SCHEDULE
SD	STORM DRAIN
SEC	SECTION
SF	SQUARE FOOT
SHT	SHEET
SHTHG	SHEATHING
SIM	SIMILAR
SOG	SLAB ON GRADE
SPA	SPACE(S)
SPEC	SPECIFICATION
SQ.	SQUARE
SS	SANITARY SEWER
SSK	SERVICE SINK
SST	STAINLESS STEEL
ST	STEEL
STD	STANDARD
STOR	STORAGE
STRUCT	STRUCTURAL
SUSP	SUSPENDED
SYM	SYMMETRICAL
SYN	SYNTHETIC
T	
T&B	TOP AND BOTTOM
T&G	TONGUE AND GROOVE
T.O.	TOP OF
T.O.S.	TOP OF STEEL
TCX	TOP CHORD EXTENSION
TEL	TELEPHONE
TEMP	TEMPERED
THK	THICK
THRD	THREADED
TV	TELEVISION
TYP	TYPICAL
U	
UNO	UNLESS NOTED OTHERWISE
UR	URINAL
V	
VA[illegible]	[illegible]
VCT	VINYL COMPOSITION TILE
VERT	VERTICAL
VIF	VERIFY IN FIELD
VR	VAPOR RETARDER
VWC	VINYL WALL COVERING
W	
W	WEST
W.FM.	WELDED FRAME
W/	WITH
W/O	WITHOUT
WB	WOOD BASE
WC	WATER CLOSET
WD	WOOD
WF	WIDE FLANGE
WH	WALL HYDRANT
WHS	WELDED HEADED STUD
WIN	WINDOW
WP	WATERPROOFING
WT	WEIGHT
WTW	WALL TO WALL
WWF	WELDED WIRE FABRIC

GENERAL NOTES

1. THESE DRAWINGS ARE THE PROPERTY OF PUBLIC STORAGE AND SHALL NOT BE USED WITHOUT PUBLIC STORAGE'S CONSENT.
2. THE CONSTRUCTION DOCUMENTS (I.E. DRAWINGS, SPECIFICATIONS) SHALL NOT BE USED FOR ISSUANCE OF BUILDING PERMITS UNLESS SIGNED AND SEALED BY THE ARCHITECT.
3. GENERAL CONTRACTOR SHALL BE RESPONSIBLE TO FIELD VERIFY ALL DIMENSIONS AND CONDITIONS THERON BEFORE COMMENCING THE WORK. REPORT ANY DISCREPANCIES AND/OR POTENTIAL PROBLEMS TO THE ARCHITECT PRIOR TO PROCEEDING.
4. CHANGES TO THE PLANS BY THE OWNER AND/OR THE CONTRACTOR SHALL BE THE RESPONSIBILITY OF THE PERSONS MAKING SUCH CHANGES, AND NOT THAT OF THE ARCHITECT.
5. THE ARCHITECT WILL NOT BE RESPONSIBLE WHERE CONSTRUCTION DEVIATES FROM THE DRAWINGS.
6. CONSTRUCTION SHOWN AND SPECIFIED SHALL CONFORM TO ALL APPLICABLE BUILDING CODES. WHERE CODES CONFLICT WITH THESE DRAWINGS, CODE REQUIREMENTS SHALL TAKE PRECEDENCE.
7. ALL WORK AND MATERIALS SHALL MEET THE REQUIREMENTS OF THE LOCAL AND STATE BUILDING CODES AND THE SPECIFICATIONS OF THE NATIONAL BOARD OF FIRE UNDERWRITERS.
8. THE INTENTION OF THE DOCUMENTS IS TO DESCRIBE, IN GENERALITY, SYSTEMS AND FINISHES. THE CONTRACTOR SHALL PROVIDE AND INSTALL COMPLETE SYSTEMS IN ACCORDANCE WITH APPLICABLE CODES, MANUFACTURERS AND ASSOCIATIONS REQUIREMENTS AND RECOMMENDATIONS, OR ACCEPTABLE BUILDING PRACTICE, WHICHEVER IS MORE STRINGENT.
9. ALL WRITTEN DIMENSIONS SHALL GOVERN. DO NOT SCALE THE DRAWINGS.
10. THE DRAWINGS SHOW THE GENERAL ARRANGEMENT AND EXTENT OF THE WORK. AS THE WORK PROGRESSES THE OWNER AND THE CONTRACTOR, AT NO EXTRA COST, SHALL MAKE MODIFICATIONS TO MAKE PARTS ALIGN AND FUNCTION PROPERLY.
11. RECHECK MEASUREMENTS AND DIMENSIONS BEFORE STARTING EACH INSTALLATION. INSPECT BOTH THE SUBSTRATE AND THE CONDITIONS FOR EACH MAJOR COMPONENT. DO NOT PROCEED UNTIL ANY UNSATISFACTORY CONDITIONS(S) HAVE BEEN CORRECTED IN AN ACCEPTABLE MANNER.
12. COMPLY WITH MANUFACTURER'S INSTALLATION INSTRUCTIONS AND RECOMMENDATIONS TO THE EXTENT THAT THOSE INSTRUCTIONS AND RECOMMENDATIONS ARE MORE EXPLICIT OR STRINGENT THAN REQUIREMENTS CONTAINED IN CONTRACT DOCUMENTS.
13. PROVIDE ATTACHMENTS AND CONNECTION DEVICES AND METHODS NECESSARY FOR SECURING WORK. SECURE WORK TRUE TO LINE AND LEVEL. ALLOW FOR EXPANSION AND BUILDING MOVEMENT.
14. PROVIDE UNIFORM JOINT WIDTHS IN EXPOSED WORK. ARRANGE JOINTS IN EXPOSED WORK TO OBTAIN THE BEST VISUAL EFFECT. REFER QUESTIONABLE CHOICES TO OWNER FOR FINAL DECISION.
15. ANY OMISSIONS FROM THE DOCUMENTS WHICH WOULD CUSTOMARILY BE PART OF THE SYSTEM OR FINISHES SHALL BE PROVIDED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER.
16. REMOVE FROM SITE EXCESS EXCAVATED MATERIALS, TRASH, DEBRIS, AND WASTE MATERIALS. DISPOSAL SHALL BE IN A MANNER APPROVED BY STATE AND LOCAL AUTHORITIES.
17. ALL WASTE MATERIALS SHALL BE REMOVED IN A MANNER WHICH PREVENTS INJURY OR DAMAGE TO PERSONS, SURROUNDING PRIVATE /PUBLIC PROPERTIES, AND PUBLIC RIGHT OF WAY.
18. THE GENERAL CONTRACTOR IS RESPONSIBLE FOR PROVIDING A CLEAN AND SAFE WORK AREA AND IS RESPONSIBLE FOR SAFETY AT THE SITE.
19. CONTRACTOR SHALL PROVIDE ANY REQUIRED PROTECTION OF WORK. NOTHING HEREIN CONTAINED SHALL BE CONSTRUED TO NULLIFY ANY RULES, REGULATIONS OR STATUTES OF STATE OR FEDERAL AGENCIES GOVERNING THE PROTECTION OF THE PUBLIC OR WORKERS FROM HEALTH OR OTHER HAZARDS INVOLVED IN THE OPERATIONS REQUIRED TO PERFORM THIS WORK.
20. CONSTRUCT AND INSTALL TEMPORARY PROTECTION MEASURES PRIOR TO START OF CONSTRUCTION. TEMPORARY PROTECTION SHALL BE REMOVED WHEN WORK IS COMPLETE. THE CONTRACTOR SHALL AT ALL TIMES PRESERVE AND PROTECT THE SITE, BUILDING OR STRUCTURE FROM DAMAGE OR INJURY.
21. ALL CONSTRUCTION EQUIPMENT AND SAFEGUARDS SHALL BE CONSTRUCTED, INSTALLED AND MAINTAINED IN A SUBSTANTIAL MANNER AND SHALL BE SO OPERATED AS TO INSURE PROTECTION TO THE WORKERS ENGAGED THEREON AND TO THE GENERAL PUBLIC. ALL EXISTING AND ADJOINING IMPROVEMENTS SHALL BE PROTECTED FROM DAMAGE INCIDENTAL TO CONSTRUCTION OPERATIONS.
22. PROTECT EXISTING ROADWAYS, WALKWAYS AND ADJOINING PROPERTY. ENCLOSE STAGING EQUIPMENT AND STORAGE AREAS WITH BARRICADES TO PREVENT ENTRY OF UNAUTHORIZED PERSONS. THE CONTRACTOR SHALL AT ALL TIMES PRESERVE AND PROTECT THE SITE, EXISTING BUILDINGS OR STRUCTURES, AND CUSTOMERS FROM DAMAGE OR INJURY.
23. MATERIALS AND EQUIPMENT REQUIRED IN CONSTRUCTION OPERATIONS SHALL BE STORED AND PLACED SO AS NOT TO ENDANGER OR OBSTRUCT THE PUBLIC, THE WORKERS OR THE ADJOINING SPACES.
24. ALL ABANDONED PIPING, CONDUITS, AND DEBRIS SHALL BE REMOVED OR CAPPED.
25. PROTECT AND CAP ALL EXISTING OR NEW UTILITIES. OBTAIN REQUIRED PERMITS AND LAYOUTS BEFORE STARTING.
26. ALL WORK SHALL COMPLY WITH THE CURRENT EDITION OF NFPA AND LOCAL BUILDING CODES.
27. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS ON THE JOB AND NOTIFY THE ARCHITECT/ENGINEER OF ANY DISCREPANCIES PRIOR TO CONTINUING WORK.
28. ALL WORK SHALL BE IN CONFORMANCE WITH THE REQUIREMENTS OF THE STATE COUNTY AND/OR LOCAL CODES HAVING JURISDICTION OF THIS PROJECT.
29. THIS BUILDING IS FIRE SPRINKLERED THROUGHOUT.
   (1) A. EXTEND THE FIRE SPRINKLER SYSTEM TO ALL AREAS OF THE BUILDING.
   B. PROVIDE SUBMITTAL OF FIRE SPRINKLER SYSTEM TO OWNER PRIOR TO FIRE DEPARTMENT REVIEW.
   C. PROVIDE PLANS FOR FIRE SPRINKLER WORK TO THE FIRE DEPARTMENT AND TO THE PLUMBING DIVISION FOR APPROVAL PRIOR TO INSTALLATION.
   D. PROVIDING PLANS FOR FIRE SPRINKLER WORK SHALL BE THE GENERAL CONTRACTOR'S RESPONSIBILITY. THE GENERAL CONTRACTOR SHALL PROVIDE A CERTIFICATE OF COMPLETION ISSUED BY THE SPRINKLER CONTRACTOR.
   E. SEPARATE PERMIT IS REQUIRED FOR FIRE SPRINKLER SYSTEM MODIFICATIONS. (PRIOR TO START OF INSTALLATION.) ARCHITECTS APPROVAL REQUIRED PRIOR TO FIRST CITY SUBMITTAL
30. ALL CONTRACTORS, SUB-CONTRACTORS GENERAL BIDDING OR CONSTRUCTING ANY PORTION OF THIS PROJECT SHALL BE HELD RESPONSIBLE TO REVIEW AND INCLUDE IN ANY BID SUBMITTED ALL OTHER DRAWING AND SPECIFICATIONS WHICH FORM A PART OF THESE CONSTRUCTION DOCUMENTS INCLUDING, BUT NOT LIMITED TO, ARCHITECTURAL GENERAL NOTES, STRUCTURAL, AIR CONDITIONING, PLUMBING, AND ELECTRICAL AND EQUIPMENT PLANS AS MAY APPLY TO SAID TRADE.
31. THE GENERAL CONTRACTOR SHALL COORDINATE THE WORK AMONG ALL TRADES TO ASSURE A SMOOTH AND HARMONIOUS FLOW OF THE JOB.
32. PROVIDE SECURITY BARRICADES AS REQUIRED.
33. THE CENTER OF THE GRIP OF THE OPERATING HANDLE OF CONTROLS & SWITCHES INTENDED TO BE USED BY OCCUPANT OF THE...
34. EXIT SIGNS SHALL BE ILLUMINATED. PROVIDE EXIT SIGNS WITH EMERGENCY BACK-UP POWER SUPPLY. TACTILE EXIT SIGN SHALL BE PROVIDED AT ALL EXIT DOORS, EXIT SIGNS, EXIT RAMPS AND EXIT ROUTES AS REQUIRED BY CODE.
35. ALL DIMENSIONS ON THE DRAWINGS TAKE PRECEDENT OVER SCALE.
   GLASS DOORS, ADJACENT PANELS AND ALL GLAZED OPEINING WITHIN 18" OF ADJACENT FLOOR SHALL BE OF GLASS APPROVED FOR IMPACT HAZARD.
36. AN APPROVED SEISMIC GAS SHUTOFF VALVE WILL BE INSTALLED ON THE FUEL GAS LINE ON THE DOWN STREAM SIDE OF THE UTILIT...
37. EXIT DOORS SHAL BE OPENABLE FROM THE INSIDE WITHOUT THE USE OF A KEY, SPECIAL KNOWLEDGE OR EFFORT. FLUSH BOLTS O...
38. POST A SIGN ADJACENT TO THE REQUIRED MAIN EXIT DOOR WITH 1" LETTERING STATING: "THIS DOOR TO REMAIN UNLOCKED WHEN...
39. THE PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR WATER, DRAIN, AND GAS CONNECTIONS TO ALL EQUIPMENT.
40. THE CITY BUILDING INSPECTOR HAS THE AUTHORITY TO REQUEST FULLY REVISED PLAN SHEETS WITH ALL FIELD CHANGES CLOUDE...
   A. APPROVED TEMPORARY SANITARY FACILITIES (I.E. CHEMICAL TOILETS SHALL BE ON THE CONSTRUCTION SITE PRIOR TO REQUEST FOR FIRST INSPECTION.) (HEALTH AND SAFTY CODE, SECTION 5416)
   B. CONTRACTOR AND/ OR OWNER SHALL PROVIDE A TRASH BIN TO INSURE PROPER CLEAN-UP OF ALL BUILDING MATERIALS.
   C. STORAGE OF BUILDING MATERIALS OR DEPRIS SHALL BE CONFINED TO THE LOT FOR WHICH THE PERMIT IS ISSUED. ADJACENT VACANT PROPERTIES MAY NOT BE UTILIZED FOR THIS PURPOSE UNLESS WRITTEN PERMISSION OF THE OWNER IS ON FILE WITH THI...
41. ALL WORK, MATERIALS, METHODS SHALL CONFORM TO ALL GOVERNING BUILDING CODES, ORDINANCES, REGULATIONS AND...
42. ALL TOILET ROOMS SHALL BE VENTILATED WITH 5 AIR CHANGES PER HOUR BY MECHANICAL MEANS. REFER TO APPLICABLE DRAWINGS.
43. THE GENERAL CONTRACTOR SHALL PROVIDE ALL NECESSARY CEILING OR WALL PANELS (OR ACCESS DOORS) AS REQUIRED BY GOVERNING AGENCIES FOR AIR CONDITIONING, PLUMBING FIRE SPRINKLER AND ELECTRICAL SYSTEMS. PROVIDE APPROVED ASSEMBLIES WITH SELF-CLOSING DEVICES IN ONE (1) HOUR RATED CONSTRUCTION.
44. ALL PENETRATIONS AT FIRE RESISTIVE CONSTUCTION SHALL BE PROTECTED WITH APPROVED FIRE ASSEMBLIES.
45. PROVIDE PEDESTRIAN OR VEHICULAR PROTECTION BARRICADES, TEMPORARY GUARD RAILS, AND/OR CANOPIES AS REQUIRED BY...
46. EXIT SIGNS WHERE NOTED OR REQUIRED SHALL BE WORDED "EXIT" IN LETTERS HAVING THE PRINCIPAL STROKE OF NOT LESS THAN 3/4" WIDE AND AT LEAST 6" HIGH AND SHALL CONFORM TO CODES AND/OR APPLICABLE REGULATIONS.
47. TACTILE EXIT SIGN SHALL BE PROVIDED AT ALL EXIT DOORS, EXIT STAIRS, EXIT RAMPS AND EXIT ROUTES AS REQUIRED BY CODE.
48. EXIT DOORS SHALL OPEN OVER A LANDING NOT MORE THAN 1/2" BELOW THE THRESHOLD.
49. CONTRACTOR SHALL COORDINATE ALL SLEEVING FOR CONDUITS UNDER SIDEWALKS, DRIVEWAYS, ETC., PRIOR TO POURING CONCRETE OR LAYING ASPHALT PAVING.
50. THE GENERAL CONTRACTOR SHALL PROVIDE AND INSTALL THE ADDRESS AND/OR SUITE UNIT NUMBERS PER CITY AND FIRE...
51. ALL ROOF WORK PENETRATION TO BE COORDINATED WITH OR COMPLETED BY OWNER'S ROOFING CONTRACTOR TO AVOID VOIDING ROOF WARRANTY
52. IN THE EVENT OF AN AMBIGUITY OR CONFLICTING REQUIREMENTS IN THE CONTRACT DOCUMENTS, THE STRICTER INTERPRETATION...
52. SUBCONTRACTORS FOR EACH TRADE ARE ADVISED THAT INFORMATION PERTINENT TO THEIR WORK MAY OCCUR IN OTHER PORTIONS OF THE CONTRACT DOCUMENTS. REFER TO STRUCTURAL, MECHANICAL, ELECTRICAL, PLUMBING, AND ADDITIONAL CONSULTANT'S DRAWINGS FOR ADDITIONAL GENERAL NOTES. ALL NOTES ARE TO BE REVIEWED AND APPLIED TO RELATED BUILDING COMPONENTS. NOTES APPEAR ON VARIOUS SHEETS FOR DIFFERENT SYSTEMS AND MATERIALS. SHEETS ARE TO BE REVIEWED AND NOTES ON ANY ONE ARE TO BE APPLIED ON RELATED DRAWINGS AND DETAILS.
53. THE MECHANICAL, ELECTRICAL, PLUMBING, AND FIRE PROTECTION DRAWINGS ARE OF EQUAL IMPORTANCE WITH THE...
54. PLUMBING CONTRACTOR RESPONSIBLE FOR CONNECTING EXTERIOR DOWNSPOUTS TO STORM LINE 5' OUTSIDE OF BUILDING.
55. GENERAL CONTRACTOR TO PROVIDE ALL SUBCONTRACTORS THE ENTIRE SET OF CONTRACT DOCUMENTS.
56. RADIO FREQUENCY TESTING TO BE PROVIDED AS REQUIRED BY THE AHJ. PROVIDE BID ALTERNATE FOR INSTALLATION OF RADIO AMPLIFICATION AS REQUIRED BY AHJ.
57. ALL FIRE RATED WALLS SHALL BE PERMANENTLY IDENTIFIED WITH A SIGN OR STENCILING PER IBC 703.7 WITH:
   - COPY READING "FIRE AND/OR SMOKE BARRIER - PROTECT ALL OPENINGS".
   - LETTERS SHALL BE AT LEAST 3" HIGH WITH 3/8" STROKE, IN CONTRASTING COLOR FROM WALL
   - IDENTIFICATION SHALL BE IN AN ACCESSIBLE, CONCEALED FLOOR/CEILING SPACE, WITHIN 15' FROM ENDS OF EACH WALL & AT INTERVALS NO LESS THAN 30'.
58. (1) USE FRT WOOD OR NON COMBUSTIBLE MATERIALS IN ALL AREAS AS REQUIRED BY 2017 FBC SEC 603
59. (2) PER NFPA 1, SECTION 11.10, BUILDINGS SHALL PROVIDE A MINIMUM RADIO SIGNAL STRENGTH FOR THE FIRE DEPARTMENT COMMUNICATIONS AND SHALL BE MAINTAINED AT THE LEVEL DETERMINED BY THE AHJ. IF IT IS DETERMINED THAT THE PROPER SIGNAL STRENTHS CANNOT BE PROVIDED UPON TESTING BY SCFD, A 2-WAY RADIO ENHANCEMENT SYSTEM WILL BE PROVIDED.

SYMBOL - LEGEND

- (1) View Name, SCALE: 1/8" = 1'-0" — VIEW TITLE
- (1 / A3.0) SIM, NUMBER, SHEET NUMBER — BUILDING SECTION
- (1 / A3.0) SIM, NUMBER, SHEET NUMBER — WALL SECTION
- (A) (1) — GRID BUBBLE
- (1 / A501) NUMBER, SHEET NUMBER — DETAIL CALLOUT
- 1 / A101 — MATCHLINE
- (1) — KEY NOTE
- (#) — REVISION TAG
- 9'-0" A.F.F. — ELEVATION
- N — NORTH ARROW
- (1 / A2.1) — EXTERIOR BUILDING ELEVATION
- A, B, C, D (A2.1) — INTERIOR ELEVATION
- W-11 — PARTITION TYPE
- RM-NAME 101 — ROOM DESIGNATION
- XXX — DOOR MARK TAG
- A — WINDOW MARK TAG
- EXIT — TACTILE EXIT SIGN - WALL MOUNTED
- (1) — EQUIPMENT TAG

SHEET INDEX

NUMBER	NAME
GENERAL	
CV.01	COVER SHEET
CV.02	GENERAL NOTES
G1.01	BARRIER FREE DETAILS
G1.02	CODE ANALYSIS / EGRESS PLAN
G3.01	PARTITION TYPES
G4.01	STANDARD INTERIOR ELEVATIONS & SECTIONS
ARCHITECTURE	
A0.01	ARCHITECTURAL SITE PLAN
A0.02	SITE DETAILS
A1.01	GROUND FLOOR PLAN
A1.02	ROOF PLAN
A1.03	ENLARGED CANOPY PLANS
A2.01	EXTERIOR ELEVATIONS
A3.01	BUILDING SECTIONS
A3.11	WALL SECTIONS
A3.21	ENVELOPE DETAILS
A4.01	LOBBY ENLARGED PLANS
A4.02	INTERIOR ELEVATIONS
A4.03	RESTROOM ENLARGED PLAN AND INTERIOR ELEVATIONS
A5.01	REFLECTED CEILING PLAN
A7.01	DOOR SCHEDULE, DETAILS & TYPES
A7.02	FINISH SCHEDULES
A8.01	SIGNAGE PLAN
A8.11	SIGNAGE TYPES
A8.12	SIGNAGE TYPES
A8.13	SIGNAGE TYPES
A8.14	SIGNAGE TYPES
STRUCTURE	
CS	COVER SHEET
CS2	BUILDING NOTES
S1	BUILDING ELEVATIONS
S2	FLOOR PLAN & NOTES
S3	CROSS SECTION & DETAILS
S4	BUILDING DETAILS
S5	BUILDING DETAILS
S6	STRAP BRACING LAYOUT
S7	FRAMING ELEVATION & DETAIL
S8	FRAMING ELEVATIONS
S9	FRAMING ELEVATION
F1	FOUNDATION PLAN & NOTES
F2	FOUNDATION DETAILS
MECHANICAL	
M0.01	MECHANICAL LEGEND AND NOTES
M0.02	MECHANICAL SCHEDULES
M1.01	MECHANICAL PLAN
M5.00	MECHANICAL DETAILS
M5.01	CONDENSING UNIT INSTALLATION
PLUMBING	
P0.01	PLUMBING LEGEND AND SCHEDULES
P1.00	PLUMBING UNDERGROUND PLAN
P1.01	PLUMBING FLOOR PLAN
P5.00	PLUMBING DETAILS
P5.01	PLUMBING RISER DIAGRAMS
ELECTRICAL	
E0.01	ELECTRICAL LEGEND AND GENERAL NOTE
E0.02	ELECTRICAL SITE PLAN
E1.01	FIRST FLOOR ELECTRICAL PLAN
E4.01	ONE-LINE DIAGRAM AND SCHEDULES
E5.01	ELECTRICAL DETAILS
E7.00	RV CANOPY LIGHTING

Galloway
6162 S. Willow Drive, Suite 320
Greenwood Village, CO 80111
303.770.8884
GallowayUS.com

STAMP

NOT FOR CONSTRUCTION

COPYRIGHT
THESE PLANS ARE AN INSTRUMENT OF SERVICE AND ARE THE PROPERTY OF GALLOWAY, AND MAY NOT BE DUPLICATED, DISCLOSED, OR REPRODUCED WITHOUT THE WRITTEN CONSENT OF GALLOWAY. COPYRIGHTS AND INFRINGEMENTS WILL BE ENFORCED AND PROSECUTED.

Public Storage

PUBLIC STORAGE
SEMINOLE COUNTY, FL

PS#28091

2431 S. Orange Blossom Trail
Apopka, FL

#	Date	Issue/Description
	03/02/2020	PERMIT SUBMITTAL
1	04/24/2020	2ND PERMIT SUBMITTAL
2	06/11/2020	3RD PERMIT SUBMITTAL

Project No:	PS0000091
Drawn By:	AT
Checked By:	KKS

GENERAL NOTES

CV.02

Order Plans @ www.LDIIline.com

BIM 360://PS91 - FL Apopka (Seminole County)/PS091_SeminoleCntyFL_Apopka_ARCH_CENTRAL.rvt
6/11/2020 2:45:26 PM