

GENERAL NOTES:


1. CONTRACTOR TO SURVEY ALL ELECTRICAL CIRCUITS AND OUTLETS PRIOR TO RE-CIRCUITING. CIRCUITS WITH EXISTING DEVICES TO REMAIN SHALL BE LEFT IN PLACE. USE SPARE CIRCUITS OR SPACES IN PANELBOARD FOR NEW CIRCUITS. BALANCE LOADS IN PANELBOARD AS NECESSARY.
2. SEE MECHANICAL AND PLUMBING PLANS FOR HVAC & PLUMBING EQUIPMENT TO BE REMOVED OR RELOCATED. REMOVE OR RELOCATE ELECTRICAL EQUIPMENT, DEVICES AND BRANCH CIRCUIT TO THE EQUIPMENT ACCORDINGLY.
3. CONTRACTOR SHALL SURVEY PANEL BOARDS AND TEST CIRCUITS ACCORDINGLY. DISCONNECT CIRCUITS FOR EQUIPMENT TO BE REMOVED AFTER EQUIPMENT REMOVAL.
4. EXISTING CIRCUITS TO REMAIN SHALL BE TESTED AND WIRING REPLACED IF NECESSARY.
5. CONTRACTOR SHALL REMOVE ALL UNUSED CONDUIT, WIRING, FIXTURES, ETC. AND DISCARD OFFSITE. ABANDONED ITEMS LEFT ABOVE CEILING/ONSITE SHALL NOT BE ACCEPTABLE.

DEMOLITION POWER NOTES

- ① ALL OUTLETS AND COMMUNICATION DEVICES THAT ARE EXISTING TO REMAIN ARE SHOWN LIGHT, SOLID. ALL OUTLETS AND COMMUNICATION DEVICES TO BE REMOVED ARE SHOWN HEAVY, DASHED.
- ② REMOVE EXISTING RECEPTACLE/DATA DEVICE AND ALL ASSOCIATED WIRING BACK TO SOURCE.
- ③ EXISTING EXHAUST FAN TO BE REMOVED AND ALL ASSOCIATED WIRING BACK TO SOURCE.
- ④ EXISTING PANELBOARD (SI & S2) TO BE REMOVED AND RELOCATED IN NEW WORK PHASE. SEE SHEET 94.01, FOR ADDITIONAL INFORMATION.
- ⑤ EXISTING PANELBOARD (P) TO BE REMOVED AND ALL ASSOCIATED FEEDERS BACK TO SOURCE. REFER TO POWER RISER ON SHEET 94.02 FOR ADDITIONAL INFORMATION.
- ⑥ EXISTING ELECTRICAL EQUIPMENT TO REMAIN. REFER TO POWER RISER ON SHEET 94.01 FOR ADDITIONAL INFORMATION.
- ⑦ EXISTING EQUIPMENT (HEATERS, ROOFTOP CONDENSERS, KITCHEN MAKEUP UNIT) TO BE REMOVED (BY MECHANICAL/ELECTRICAL CONTRACTOR SHALL DISCONNECT BRANCH CIRCUIT WIRING AND MAKE SHUT OFF COORDINATE IN THE FIELD).
- ⑧ EXISTING ROOFTOP CONDENSER TO BE REMOVED (BY OTHERS). CONTRACTOR SHALL DISCONNECT BRANCH CIRCUIT WIRING, REMOVE BACK TO SOURCE AND MAKE EQUIPMENT SAFE FOR REMOVAL.
- ⑨ EXISTING GAS FIRE WATER WARMER (DWH) TO BE REMOVED. COORDINATE WITH MECHANICAL.
- ⑩ EXISTING DUCT SMOKE DETECTOR SIGNALING DEVICE TO BE REMOVED AND ALL ASSOCIATED WIRING BACK TO SOURCE.
- ⑪ EXISTING FIRE SUPPRESSION SYSTEM (MANUAL PULL STATIONS, CYLINDERS, NOZZLES, GAS SHUT-OFF VALVES AND ALL OTHER COMPONENTS) TO BE REMOVED. COORDINATE IN THE FIELD.
- ⑫ REMOVE EXISTING CEILING/WALL MOUNTED FIRE ALARM DEVICE AND ALL ASSOCIATED WIRING BACK TO SOURCE.
- ⑬ EXISTING FIRE ALARM CONTROL PANEL (FACP) TO BE REMOVED AND RELOCATED IN NEW WORK PHASE.
- ⑭ REMOVE EXISTING SMOKE DETECTOR AND ALL ASSOCIATED WIRING BACK TO SOURCE.
- ⑮ EXISTING RECEPTACLE TO REMAIN.
- ⑯ NOTE: ALL CONDUIT AND CABLE SHALL BE REMOVED IN ITS ENTIRETY SO THAT EXPOSED CEILING IN NEW WORK PHASE SHALL BE FREE AND CLEAR OF ALL VISIBLE CABLE AND CONDUIT. EXISTING CONDUIT/CABLE SERVING ADJACENT TENANT SPACES SHALL BE DISCONNECTED FROM THEIR SOURCE AND REROUTED CONCEALED ALONG EXISTING JOISTS/BEAMS, AS NOT VISIBLE FROM GROUND. COORDINATE RECONNECTION/EXTENSION OF NEW WIRING WITH ADJACENT TENANTS. COORDINATE EXTENT OF THE TENANT WIRING/CABLING WITH VERIZON REPRESENTATIVE IN THE FIELD.

Order Plans @

⑯ DEMOLITION POWER PLAN
SCALE: 1/4" = 1'-0"



NO.	REVISION	DATE
FILE	20013J	DRAWN CBH
		ISSUED 06/19/2020

SHEET TITLE
Demolition Power Plan

SHEET NUMBER

91.02