

GENERAL SITE NOTES:

- PRIOR TO CONSTRUCTION DEVELOPER SHALL PROVIDE DOLLAR GENERAL STORE DESIGN DEPARTMENT A COMPLETE SET OF CIVIL SITE WORK DRAWINGS STAMPED BY A CIVIL ENGINEER LICENSED IN THE STATE IN WHICH THE DEVELOPMENT IS PROPOSED. DOLLAR GENERAL SHALL APPROVE ENGINEER DRAWINGS PRIOR TO THE DEVELOPER STARTING CONSTRUCTION. ANY MAJOR MODIFICATIONS OF THE DRAWINGS, AFTER INITIAL APPROVAL, SHALL BE RESUBMITTED TO DOLLAR GENERAL FOR PRIOR APPROVAL. ANY CHANGES MADE THAT ARE NOT APPROVED BY DOLLAR GENERAL STORE DESIGN DEPARTMENT, MAY NOT BE ACCEPTABLE, AND MAY REQUIRE RECONSTRUCTION.
- PRIOR TO STARTING CONSTRUCTION CONTRACTOR SHALL BE RESPONSIBLE TO MAKE SURE THAT ALL REQUIRED PERMITS AND APPROVALS HAVE BEEN OBTAINED. NO CONSTRUCTION OR FABRICATION SHALL BEGIN UNTIL THE CONTRACTOR HAS RECEIVED AND THOROUGHLY REVIEWED ALL PLANS AND OTHER DOCUMENTS APPROVED BY ALL OF THE PERMITTING AUTHORITIES.
- ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THESE PLANS AND SPECIFICATIONS AND THE REQUIREMENTS AND STANDARDS OF THE LOCAL GOVERNING AUTHORITY.
- THE BOUNDARY INFORMATION WAS TAKEN FROM BOUNDARY AND TOPOGRAPHIC SURVEY CONDUCTED BY ROCHESTER & ASSOCIATES, INC. FIELD DATA WAS COLLECTED IN MAY 2020.
- THE LOCATIONS OF UNDERGROUND FACILITIES SHOWN ON THIS PLAN ARE BASED ON FIELD SURVEYS AND LOCAL UTILITY COMPANY RECORDS. IT SHALL BE THE CONTRACTOR'S FULL RESPONSIBILITY TO CONTACT THE VARIOUS UTILITY COMPANIES TO LOCATE THEIR FACILITIES PRIOR TO STARTING CONSTRUCTION. NO ADDITIONAL COMPENSATION SHALL BE PAID TO THE CONTRACTOR FOR DAMAGE AND REPAIR TO THESE FACILITIES CAUSED BY HIS WORK FORCE.
- ALL DIMENSIONS AND GRADES SHOWN ON THE PLANS SHALL BE FIELD VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION. CONTRACTOR SHALL NOTIFY THE OWNER'S CONSTRUCTION MANAGER IF ANY DISCREPANCIES EXIST PRIOR TO PROCEEDING WITH CONSTRUCTION FOR NECESSARY PLAN OR GRADE CHANGES. NO EXTRA COMPENSATION SHALL BE PAID TO CONTRACTOR FOR WORK HAVING TO BE REDONE DUE TO DIMENSIONS OR GRADES SHOWN INCORRECTLY ON THESE PLANS IF SUCH NOTIFICATION HAS NOT BEEN GIVEN.
- ALL DIMENSIONS ARE TO THE BACK OF CURB UNLESS OTHERWISE NOTED.
- ANY CHANGES OR ALTERATIONS MADE TO THESE CONSTRUCTION DRAWINGS WITHOUT THE WRITTEN APPROVAL OF ROCHESTER AND ASSOCIATES, INC. VOIDS THE SEAL SHOWN HERE ON AND ANY LIABILITY ASSOCIATED WITH THIS PROJECT. THE ORIGINAL DRAWINGS ARE KEPT ON FILE FOR VERIFICATION OF ANY CHANGES.
- ALL CONSTRUCTION SHALL CONFORM TO CURRENT APPLICABLE CARROLL COUNTY STANDARDS AND SPECIFICATIONS.
- SITE IS LOCATED IN LAND LOT 195, CARROLL COUNTY, GA.
- PROPOSED USE: DOLLAR GENERAL STORE
- DEVELOPER: SW VILLA RICA, LLC
- UTILITY SERVICE:
 - ATLANTA GAS LIGHT
 - CITY OF VILLA RICA UTILITIES
 - AT&T, COMCAST, WINDSTREAM
 - CARROLL EMC
 - CITY OF VILLA RICA UTILITIES
- 24 HOUR CONTACT: BRIAN SULLIVAN
 OFFICE: (404) 475-9000
 MOBILE: (770) 883-1702
- ENGINEERING CONTACT: ERIC HUFFINE, P.E. (770) 718-0800
 GSWCC EROSION CONTROL LEVEL II CERTIFICATION: #15201
- NO PORTION OF THIS PROPERTY IS LOCATED IN A FLOOD HAZARD ZONE AS PER F.E.M.A. FLOOD INSURANCE RATE MAP OF CARROLL COUNTY, GEORGIA COMMUNITY PANEL NUMBER 1304500156D DATED SEPTEMBER 19, 2007.
- THERE ARE NO STREAMS OR WETLANDS ON OR WITHIN 200' OF THIS PROJECT SITE.
- IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ENSURE THAT ANY GROUND CONTROL AND/OR BENCHMARKS AS SHOWN HAVE NOT BEEN DISTURBED FROM THEIR ORIGINAL POSITION AND ARE CHECKED AGAINST EXISTING FEATURE ELEVATIONS TO ENSURE ACCURACY. IF A DISCREPANCY IS DISCOVERED THE LAND SURVEYOR AND/OR ENGINEER SHOULD NOTIFIED IMMEDIATELY AND PRIOR TO ANY CONSTRUCTION ACTIVITIES. THIS INFORMATION IS FURNISHED AS A COURTESY AND ROCHESTER AND ASSOCIATES, INC. CANNOT ASSUME ANY LIABILITY FOR INACCURATE GROUND CONTROL OR BENCHMARKS RELATED TO THIS PROJECT.

EROSION CONTROL NOTES:

- DESCRIPTION: THE PROPOSED DEVELOPMENT IS A PROPOSED DOLLAR GENERAL STORE ON A 7.41 ACRE SITE.
- EXISTING CONDITIONS: THE EXISTING SITE IS DEVELOPED AS AN EXISTING COMMERCIAL DEVELOPMENT.
- ADJACENT AREAS: THE ADJACENT AREAS ARE COMMERCIAL DEVELOPMENT.
- THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES PRIOR TO LAND DISTURBING ACTIVITIES.
- EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE.
- ANY DISTURBED AREA LEFT EXPOSED FOR A PERIOD GREATER THAN 14 DAYS SHALL BE STABILIZED WITH MULCH OR TEMPORARY SEEDING.
- ANY AMENDMENT TO THE EROSION CONTROL PLANS WHICH HAVE A SIGNIFICANT EFFECT ON BMPs WITH A HYDRAULIC COMPONENT MUST BE CERTIFIED BY THE DESIGN PROFESSIONAL.
- SOIL CLEAN UP AND CONTROL PRACTICES:
 - LOCAL, STATE AND MANUFACTURER'S RECOMMENDED METHODS FOR SPILL CLEANUP WILL BE CLEARLY POSTED AND PROCEDURES WILL BE MADE AVAILABLE TO SITE PERSONNEL.
 - MATERIAL AND EQUIPMENT NECESSARY FOR SPILL CLEANUP WILL BE KEPT IN THE MATERIAL STORAGE AREAS. TYPICAL MATERIAL AND EQUIPMENT INCLUDES, BUT IS NOT LIMITED TO, BROOMS, DUSTPANS, MOPS, GLOVES, GOGGLES, CAT LITTER, SAND, SAWDUST AND PROPERLY LABELED PLASTIC AND METAL WASTE CONTAINERS.
 - SPILL PREVENTION PRACTICES AND PROCEDURES WILL BE REVIEWED AFTER A SPILL AND ADJUSTED AS NECESSARY TO FUTURE SPILLS.
 - ALL SPILLS WILL BE CLEANED UP IMMEDIATELY UPON DISCOVERY. ALL SPILLS WILL BE REPORTED AS REQUIRED BY LOCAL, STATE AND FEDERAL REGULATIONS.
 - FOR SPILLS THAT IMPACT SURFACE WATER (LEAVE A SHEEN ON SURFACE WATER), THE NATIONAL RESPONSE CENTER (NRC) WILL BE CONTACTED WITHIN 24 HOURS AT 1-800-424-8802.
 - FOR SPILLS OF AN UNKNOWN AMOUNT, THE NATIONAL CENTER (NRC) WILL BE CONTACTED WITHIN 24 HOURS AT 1-800-424-8802.
 - FOR SPILLS GREATER THAN 25 GALLONS AND NO SURFACE WATER IMPACTS, THE GEORGIA EPD WILL BE CONTACTED WITHIN 24 HOURS.
 - FOR SPILLS LESS THAN 25 GALLONS AND NO SURFACE WATER IMPACTS, THE SPILL WILL BE CLEANED UP AND LOCAL AGENCIES WILL BE CONTACTED AS REQUIRED.
 - THE CONTRACTOR SHALL NOTIFY THE LICENSED PROFESSIONAL WHO PREPARED THIS PLAN IF MORE THAN 1320 GALLONS OF PETROLEUM IS STORED ONSITE (THIS INCLUDES CAPACITIES OF EQUIPMENT) OR IF ANY ONE PIECE OF EQUIPMENT HAS A CAPACITY GREATER THAN 500 GALLONS. THE CONTRACTOR WILL NEED A SPILL PREVENTION CONTAINMENT AND COUNTER MEASURES PLAN BY THAT LICENSED PROFESSIONAL.
- INSPECTIONS & RECORD KEEPING (GAR100001-IV.D.4.a)
 - Permittee requirements.
 - Each day when any type of construction activity has taken place at a primary permittee's site, certified personnel provided by the primary permittee shall inspect: (a) all areas at the primary permittee's site where petroleum products are stored, used, or handled for spills and leaks from vehicles and equipment and (b) all locations at the primary permittee's site where vehicles enter or exit the site for evidence of off-site sediment tracking. These inspections must be conducted until a Notice of Termination is submitted.
 - Measure and record rainfall within disturbed areas of the site that have not met final stabilization once every 24 hours except any non-working Saturday, non-working Sunday and non-working Federal holiday. The data collected for the purpose of compliance with this permit shall be representative of the monitored activity. Measurement of rainfall may be suspended if all areas of the site have undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region.
 - Certified personnel (provided by the primary permittee) shall inspect the following at least once every seven (7) calendar days and within 24 hours of the end of a storm that is 0.5 inches rainfall or greater (unless such storm ends after 5:00 PM on any Friday, Saturday, or Sunday, in which case the inspection shall be completed by the end of the next business day and working day, whichever occurs first): (a) disturbed areas of the primary permittee's construction site; (b) areas used by the primary permittee for storage of materials that are exposed to precipitation; and (c) structural control measures. Erosion and sediment control measures identified in the Plan applicable to the primary permittee's site shall be observed to ensure that they are operating correctly. Where discharge locations or points are accessible, they shall be inspected to ascertain whether erosion control measures are effective in preventing significant impacts to receiving water(s). For areas of a site that have undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region, the permittee must comply with Part IV.D.4.a.(4). These inspections must be conducted until a Notice of Termination is submitted.
 - Certified personnel (provided by the primary permittee) shall inspect at least once per month during the term of this permit (i.e., until a Notice of Termination has been submitted) the areas of the site that have undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region. These areas shall be inspected for evidence of, or potential for, pollutants entering the drainage system and the receiving water(s). Erosion and sediment control measures identified in the Plan shall be observed to ensure that they are operating correctly. Where discharge locations or points are accessible, they shall be inspected to ascertain whether erosion control measures are effective in preventing significant impacts to receiving water(s).
 - Based on the results of each inspection, the site description and the pollution prevention and control measures identified in the Erosion, Sedimentation and Pollution Control Plan shall be revised as appropriate not later than seven (7) calendar days following each inspection. Implementation of such changes shall be made as soon as practical but in no case later than seven (7) calendar days following each inspection.
 - A report for each inspection that includes the name(s) of certified personnel making each inspection, the date(s) of each inspection, construction phase (i.e., initial, intermediate or final), major observations relating to the implementation of the Erosion, Sedimentation and Pollution Control Plan, and actions taken in accordance with Part IV.D.4.a.(5) of the permit shall be made and retained at the site or be readily available at a designated alternate location until the entire site or that portion of a construction site that has been phased has undergone final stabilization and a Notice of Termination is submitted to EPD. Such reports shall be readily available by end of the second business day and/or working day and shall identify all incidents of best management practices that have not been properly installed and/or maintained as described in the Plan. Where the report does not identify any incidents, the inspection report shall contain a certification that the best management practices are in compliance with the Erosion, Sedimentation and Pollution Control Plan. The report shall be signed in accordance with Part V.G.2. of this permit.

NO MATERIAL IS TO BE BURNED ON SITE. ALL WASTE MATERIAL SHALL BE DISPOSED OF AT A PERMITTED OFFSITE LANDFILL

THE INSTALLATION OF EROSION CONTROL MEASURES SHALL TAKE PLACE PRIOR TO OR CONCURRENT WITH LAND DISTURBING ACTIVITIES

ALL IMPROVEMENTS TO CONFORM WITH CARROLL COUNTY CONSTRUCTION STANDARDS

NOTIFY CARROLL COUNTY 24 HOURS BEFORE STARTING EACH PHASE OF CONSTRUCTION

MAXIMUM CUT OR FILL SLOPES ARE 2 HORIZONTAL TO 1 VERTICAL

ALL EROSION AND SEDIMENT CONTROL MEASURES WILL BE INSPECTED DAILY AND ANY DEFICIENCIES NOTED WILL BE CORRECTED BY THE END OF EACH DAY. ADDITIONAL EROSION CONTROL MEASURES WILL BE INSTALLED IF DEEMED NECESSARY BY ON-SITE INSPECTOR.

SITE AREA: 7.41 ACRES
DISTURBED AREA: 3.06 ACRES

EARTHWORK ESTIMATE:
CUT: 2463 CY
FILL: 3671 CY
DIFFERENCE: 1208 CY FILL
 *ASSUMES 12" SUBGRADE FOR ONSITE PAVEMENT AREAS
 *ASSUMES 6" SUBGRADE FOR BUILDING
 *NO ADJUSTMENTS MADE FOR TOP SOIL
 EARTHWORK ESTIMATE PROVIDED FOR CONVENIENCE TO CONTRACTOR ONLY.
 CONTRACTOR IS TO VERIFY QUANTITIES.

ADDITIONAL EROSION CONTROL NOTES:

THE DESIGN PROFESSIONAL WHO PREPARED THE ES&S PLAN IS TO INSPECT THE INSTALLATION OF THE INITIAL SEDIMENT STORAGE REQUIREMENTS AND PERIMETER CONTROL BMPS WITHIN 7 DAYS AFTER INSTALLATION.

NON-EXEMPT ACTIVITIES SHALL NOT BE CONDUCTED WITHIN THE 25-FOOT 50-FOOT UNDISTURBED STREAM BUFFERS AS MEASURED FROM THE POINT OF WRESTED VEGETATION OR WITHIN 25-FEET OF THE COASTAL MARSHLAND BUFFER AS MEASURED FROM THE JURISDICTIONAL DETERMINATION LINE WITHIN THE FIRST 100 FEET DURING THE NECESSARY VARIANCES AND PERMITS.

AMENDMENTS/REVISIONS TO THE ES&S PLAN WHICH HAVE A SIGNIFICANT EFFECT ON BMPs WITH A HYDRAULIC COMPONENT MUST BE CERTIFIED BY THE DESIGN PROFESSIONAL.

WASTE MATERIALS SHALL NOT BE DISCHARGED TO WATERS OF THE STATE, EXCEPT AS AUTHORIZED BY A SECTION 404 PERMIT.

THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND ACTIVITIES PRIOR TO LAND DISTURBING ACTIVITIES.

EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE.

ANY DISTURBED AREA LEFT EXPOSED FOR A PERIOD GREATER THAN 14 DAYS SHALL BE STABILIZED WITH MULCH OR TEMPORARY SEEDING.

GSWCC GEORGIA SOIL AND WATER CONSERVATION COMMISSION
 ERIC M. HUFFINE, P.E.
 LEVEL II CERTIFICATION DESIGN PROFESSIONAL
 CERTIFICATION NUMBER: 0000015201
 ISSUED: 09/25/2019 EXPIRES: 09/25/2022

GRADING NOTES:

COMPACTION:
 COMPACTION OF THE BACKFILL OF ALL TRENCHES SHALL BE COMPACTED TO THE DENSITY OF 100% OF MODIFIED PROCTOR MAXIMUM DENSITY PER A.S.T.M. TEST D-698. BACKFILL MATERIAL SHALL BE FREE FROM ROOTS, STUMPS, OR OTHER FOREIGN DEBRIS, AND SHALL BE PLACED AT OR NEAR OPTIMUM MOISTURE. CORRECTION OF ANY TRENCH SETTLEMENT WITHIN A YEAR FROM THE DATE OF APPROVAL WILL BE THE RESPONSIBILITY OF THE CONTRACTOR.

BEDDING:
 ALL STORM DRAIN AND SANITARY SEWER PIPES SHALL HAVE A CLASS "C" BEDDING AS A MINIMUM UNLESS NOTED OTHERWISE. EXCAVATE AND SHAPE BOTTOM OF TRENCH TO THE PROPER GRADE AND TO FIT THE LOWER PART OF THE PIPE EXTERIOR FOR A WIDTH OF A LEAST 50 PERCENT OF THE OUTSIDE DIAMETER OF THE PIPE. SIDES AND AREA OVER THE PIPE SHALL THEN BE FILLED WITH COMPACTED BACKFILL.

PAVING:
 PAVING SHALL BE DONE IN ACCORDANCE WITH THE SPECIFICATIONS PROVIDED IN THESE PLANS. ALL PAVEMENT WITHIN THE GDOT R/W MUST CONFORM TO ALL GDOT PAVING STANDARDS.

CONCRETE:
 3000 PSI COMPRESSIVE STRENGTH AT 28 DAYS, REINFORCING BARS SHALL CONFORM TO THE REQUIREMENTS OF ASTM A 615 GRADE 60.

FIELD CONDITIONS:
 CONTRACTOR SHALL VERIFY FIELD CONDITIONS AFFECTING CONSTRUCTION, PARTICULARLY UTILITIES, PRIOR TO CONSTRUCTION. CHANGES IN CONSTRUCTION NECESSITATED BY FIELD CONDITIONS SHALL BE APPROVED BY THE OWNER'S ENGINEER PRIOR TO CONSTRUCTION. IN ACCORDANCE WITH STATE LAW, CONTRACTOR SHALL CALL 800-288-7411 AT LEAST THREE (3) WORKING DAYS PRIOR TO CONSTRUCTION FOR LOCATION OF UNDERGROUND UTILITIES.

CONSTRUCTION STAKING:
 PRIOR TO ANY CONSTRUCTION, STORM SEWER MANHOLES ARE TO BE STAKED BY THE CONTRACTOR. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTION OF THESE STAKES AND ALL OTHER CONSTRUCTION STAKING.

CONSTRUCTION NOTES:

1. NO ADDITIONAL CONSTRUCTION OR IMPROVEMENTS, INCLUDING BUT NOT LIMITED TO WALLS, FENCES, SIGNS, SPRINKLER SYSTEMS, LIGHTS, TRESS, ETC., WILL BE ALLOWED ON THE ROAD RIGHT-OF-WAY.

2. CARROLL COUNTY SHALL BE NOTIFIED 24 HOURS PRIOR TO ANY CONSTRUCTION.

3. GEORGIA DOT INSPECTOR SHALL BE NOTIFIED 24 HOURS PRIOR TO ANY CONSTRUCTION WITHIN DOT RIGHT-OF-WAY.

4. ALL WATER MATERIALS AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH CITY OF VILLA RICA UTILITIES.

5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING A MARKED-UP SET OF DESIGN DRAWINGS SHOWING ALL "AS-BUILT" CONDITIONS. THESE "RECORD DRAWINGS" SHALL BE MADE AVAILABLE TO THE DESIGNER AND/OR THE COUNTY INSPECTOR UPON REQUEST. THE MARK-UPS SHALL BE AT THE SITE AT ALL TIMES AND SHALL BE UTILIZED TO DEVELOP FINAL RECORD DRAWINGS.

6. ANY CHANGES IN THE HORIZONTAL ALIGNMENT SHOWN HEREON SHALL BE APPROVED BY THE DESIGN ENGINEER AND CARROLL COUNTY PRIOR TO CONSTRUCTION.

7. THE CONTRACTOR IS RESPONSIBLE FOR THE INSTALLATION & MAINTENANCE OF ALL REQUIRED SEDIMENT CONTROL STRUCTURES.

8. ALL DISTURBED AREAS SHALL BE GRASSED IMMEDIATELY UPON COMPLETION OF BACK FILLING TRENCHES.

9. CLEARING LIMITS SHALL BE CLEARLY DELINEATED WITH TREE SAVE FENCE OR OTHER SUITABLE MEANS.

10. CONTRACTOR IS RESPONSIBLE FOR THE ADJUSTMENTS TO ALL EXISTING UTILITIES ON SITE TO FINAL GRADE.

11. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL UTILITY LOCATIONS. CONTRACTOR SHOULD NOTIFY THE UTILITY PROTECTION CENTER, INC. AT (800) 282-7411 THREE WORKING DAYS BEFORE CONSTRUCTION IS TO BEGIN.

Order Plans

REVISION HISTORY CHART

REVISION NUMBER	DATE	AFFECTED SHEETS	DESCRIPTION	P.E./ R.L.S. INITIAL

SUBMITTAL HISTORY CHART

DATE	AGENCY	DEPARTMENT	DESCRIPTION	PERMIT TYPE	PERMIT NUMBER	PERMIT APPROVAL DATE

Rochester & Associates, Inc.
 286 Highway 314, Suite A + Fayetteville, Georgia 30214
 (770)716-8125 (770)716-8124 Fax • www.rochester-assoc.com

GENERAL NOTES FOR:
DOLLAR GENERAL VILLA RICA
 LAND LOT 195
 6TH DISTRICT
 CARROLL COUNTY, GA

REV	DATE	DESCRIPTION

ANY CHANGES OR ALTERATIONS MADE TO THESE CONSTRUCTION DRAWINGS WITHOUT THE WRITTEN APPROVAL OF THE SEAL SHOWN HEREON AND ANY LIABILITY ASSOCIATED WITH THIS INFORMATION IS FURNISHED AS A COURTESY AND ROCHESTER AND ASSOCIATES, INC. CANNOT ASSUME ANY LIABILITY FOR INACCURATE GROUND CONTROL OR BENCHMARKS RELATED TO THIS PROJECT.

REGISTERED PROFESSIONAL ENGINEER
 No. 28858
 ERIC M. HUFFINE

SHEET 2 OF 16
 DATE: 07/24/20
 SCALE: N.T.S.
 JOB NO.: G220052.DWG
 REV'D BY: EWH
 DRAWN BY: JRS