

### GENERAL NOTES


- CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS AND SITE CONDITIONS BEFORE COMMENCING WORK.
- THIS CONTRACT REQUIRES COMPLETE, FINISHED WORKABLE PROJECT OF THE AREAS INDICATED BY THE CONTRACT DOCUMENTS, AND SHALL INCLUDE ALL MATERIALS AND LABOR NECESSARY TO COMPLETE SAME, REGARDLESS OF WHETHER OR NOT EACH AND EVERY NECESSARY WORK OR ITEM IS SPECIFICALLY INDICATED ON ANY OTHER PORTION OF THE DRAWING AND/OR NOTES.
- ALL DETAILS AND SECTIONS SHOWN ON THE DRAWINGS ARE INTENDED TO BE TYPICAL AND SHALL BE CONSTRUED TO APPLY TO ANY SIMILAR SITUATION ELSEWHERE ON THE PROJECT, EXCEPT WHERE A DIFFERENT DETAIL IS SHOWN.
- CONTRACTOR SHALL FURNISH ALL ADDITIONAL DATA AND DOCUMENTATION TO SECURE ALL REQUIRED PERMITS AND SHALL COORDINATE THIS DATA WITH THE CONSTRUCTION DOCUMENTS WHERE REQUIRED.
- AS A MINIMUM, ALL WORK SHALL CONFORM TO THE APPLICABLE BUILDING CODE ADOPTED BY THE JURISDICTION OF THE WORK. WHERE MORE STRINGENT CODES ARE ADOPTED, THEY SHALL GOVERN THE WORK.
- ALL WORK SHALL CONFORM TO APPLICABLE FEDERAL, STATE, COUNTY AND LOCAL CODES AND ORDINANCES.
- TO PROVIDE ACCESSIBILITY FOR THE PHYSICALLY HANDICAPPED, ALL WORK SHALL CONFORM TO PUBLIC LAW 101-336 (AMERICANS WITH DISABILITIES ACT OF 1993).
- ALL WORK SHALL CONFORM TO THE APPLICABLE NFPA 101 LIFE SAFETY CODE ADOPTED BY THE JURISDICTION OF THE WORK.
- AROUND ALL EXPOSED PIPES, CONDUIT OR DUCTS, INSTALL ENCLOSURES OF THE SAME MATERIAL AND FINISH AS ADJACENT WORK, UNLESS NOTED OTHERWISE.
- FIELD CHECK ALL ROUGH AND/OR FINISH DIMENSIONS FOR ACCURATE FITTING OF EQUIPMENT, CABINETS, COUNTERS, FIXTURES AND ACCESSORIES BEFORE FABRICATION. PROVIDE AND INSTALL ALL NECESSARY FILLERS, SCRIBE STRIPS, PANELS, BASES OR TRIM TO COMPLETE AND FINISH INSTALLATION.
- PROVIDE AND INSTALL ALL NECESSARY HARDWARE, BRACKETS, BUSHINGS, ANCHORS, INSERTS, BLOCKING, FURRING OR OTHER SUPPLEMENTARY ITEMS NEEDED TO COMPLETE INSTALLATION OF EQUIPMENT, FIXTURES AND ACCESSORIES.
- ALL CONTRACTORS ARE TO COORDINATE THE WORK OF CONTRACTORS OF ALL TRADES ON THE PROJECT AND SCHEDULE ARE NOT IMPEDED. SCHEDULE WORK PROGRESS THROUGHOUT THE ENTIRE PROJECT TO PREVENT CONFLICTS AND INTERFERENCE. OBTAIN ALL NECESSARY PERMISSIONS SUCH AS SITES, LOCATIONS, TEMPLATES, LAYOUT, DIMENSIONS AND ALL OTHER INFORMATION NECESSARY FOR A PROPER AND WELL COORDINATED INSTALLATION. PROVIDE TO INSTALLATION OF ITEMS, CONFER WITH EACH CONTRACTOR EXACT LOCATION OF ALL ITEMS.
- WHERE MATERIALS REFERENCED ON DRAWINGS, OR NOT SPECIFIED, COMPLETE THE WORK OF THIS CONTRACT ARE NOT SPECIFIED HERE, PROVIDE BEST QUALITY MATERIALS. WHERE MATERIALS ARE INTENDED TO MATCH EXISTING, PROVIDE CLOSEST POSSIBLE MATCH, SUBJECT TO OWNERS APPROVAL. ALL ITEMS AND WORK ON DRAWINGS ARE TO BE PROVIDED UNLESS INDICATED OTHERWISE. ALL WORK WHICH HAS BEEN DAMAGED OR IMPAIRED OR WHERE ITEM CANNOT BE REPAIRED TO A "NEW CONDITION", OR WHERE STRUCTURAL INTEGRITY HAS BEEN AFFECTED, ITEM SHALL BE REPLACED.

### DRAWING NOTES

- PROVIDE NEMA-3R, 100A, 480V, 3-POLE, UNIT MOUNTED NFSS FOR AHU-1.
- PROVIDE BRANCH CIRCUIT AS INDICATED; ELECTRICAL CONVENIENCE RECEPTACLE PROVIDED WITH UNIT.
- PROVIDE DUCT SMOKE DETECTOR IN SUPPLY AND RETURN DUCT, COORDINATE INSTALLATION WITH DIV. 23. CONNECT TO EXISTING FIRE ALARM PULLSTATION LOCATED NEXT TO MAIN ENTRANCE. DEVICE SHALL MATCH EXISTING SIMPLEX FIRE ALARM SYSTEM. PROVIDE REPROGRAMMING AS NECESSARY TO FIRE ALARM SYSTEM TO ACCOMMODATE DEVICE.
- EXISTING SIMPLEX FIRE ALARM PULLSTATION.
- BRANCH CIRCUIT FOR AHU-1 TO BE FED FROM EXISTING MAIN SWITCHBOARD "PA" LOCATED IN THE BOILER ROOM APPROXIMATELY 150' NORTH EAST OF NEW AHU-1. PROVIDE DIRECT BURIED BRANCH CIRCUIT FOR AHU-1 IN SCHED 40 PVC AT MINIMUM 18 INCHES TO TOP OF DUCT BELOW FINISHED GRADE. ELBOWS AND FITTINGS SHALL BE ORC AT CHANGES OF DIRECTION IN DUCT RUN. RUN CONDUIT AS DIRECTLY AS POSSIBLE MINIMIZING DISTURBANCES TO HARDSCAPE. PROVIDE FULL BOXES OR HANDHOLES AS REQUIRED TO COMPLY WITH NEC 358.26. FIELD VERIFY EXACT ROUTING LOCATION; COORDINATE WITH EXISTING UTILITIES. REFER TO SHEETS E-501 AND E-601.

Order Plans @ [www.LDIILine.com](http://www.LDIILine.com)

**LEVEL 1 ELECTRICAL POWER PLAN**  
SCALE: 1/4" = 1'-0"



20	100% CD SET	01/06/2020

**KITTRIDGE MAGNET SCHOOL  
GYM HVAC DESIGN**  
1633 E. Nancy Creek Drive  
Atlanta, Georgia 30319

**STANLEY  
LOVE  
STANLEY  
P O C O**

ARCHITECTURE  
INTERIORS PLANNING  
PROGRAM MANAGEMENT

1196 SPRING STREET, N.W.  
ATLANTA, GEORGIA 30309-3013  
404.576.0286  
404.576.0487 fax  
www.stanleylove-stanley.com

DRAWING TITLE  
**ELECTRICAL LEVEL 1  
POWER PLAN**

PROFESSIONAL SEAL

**GEORGIA**  
REGISTERED  
No. PE2227630  
PROFESSIONAL  
ELECTRICAL ENGINEER  
ANN CRUTCHFIELD

CONSULTANT

SCALES AS STATED HEREON ARE VALID ON THE ORIGINAL DRAWING. THE DIMENSIONS OF WORK ARE SHOWN HEREIN. THE SCALES OF THE DRAWING ARE SUBJECT TO CHANGE IF THE RATIO OF THE OVERALL SHEET DIMENSIONS TO THE PRINT IS UNDESIRABLE.

THIS DRAWING IS THE PROPERTY OF STANLEY LOVE-STANLEY, P.C. AND IS NOT TO BE REPRODUCED, COPIED, WHOLE OR IN PART, OR USED FOR THE DESIGN OF THE PROJECT AND ITS CONSTRUCTION. ANY REUSE OF THIS DRAWING WITHOUT THE WRITTEN PERMISSION OF STANLEY LOVE-STANLEY, P.C. IS STRICTLY PROHIBITED.

COPYRIGHT © 2019. ALL RIGHTS RESERVED BY STANLEY LOVE-STANLEY, P.C.

DRAWING NO  
DATE  
01/06/2020

PROJECT NO  
6919.4

DRAWING NO  
E-101