MINIMUM WIRE SIZE CHART

BREAKER SIZE	MIN. CONDUC TOR	MIN. CONDUIT	MAX. CONDUCTOR LENGTH (FT) FOR VOLTAGE DROP NOT TO EXCEED 3% P.E.C. (PANDA'S RED LOAD ASSUMED) - SINGLE/LINE RATING		
			VOLTAGE/PHASE		
			120/1*	208/1*	208/3**
15	#12	1/2"	75	130	
20	#12	1/2"	59	98	
30	#10	3/4"	63	108	
40	#8	1"	72	125	
50	#6	1"	92	159	
60	#6	1"	77	133	
70	#4	1 1/4"		150	138
80	#4	1 1/4"		167	121
90	#3	1 1/4"		173	133
100	#3	1 1/4"		156	120
110	#1	1 1/2"		222	171
125	#1	1 1/2"		195	150
150	1/0	1 1/2"			167
175	2/0	2"			172
200	3/0	2"			190
225	4/0	2 1/2"			212
250	250 MCM	2 1/2"			222
275	300 MCM	2 1/2"			243
300	350 MCM	3"			257
350	2/0	EA. OF (2) 2"			172
400	3/0	EA. OF (2) 2"			190
500	250 MCM	EA. OF (2) 2 1/2"			222
600	350 MCM	EA. OF (2) 3"			257
700	500 MCM	EA. OF (2) 3 1/2"			318
800	500 MCM	EA. OF (3) 3"			250
1000	400 MCM	EA. OF (3) 3"			273
1200	350 MCM	EA. OF (4) 3"			263
3000	500 MCM	EA. OF (6) 3 1/2"			297
4000	600 MCM	EA. OF (8) 3"			328

CONTRACTOR TO VERIFY VOLTAGE DROP IF CONDUCTOR/BREAKER COMBINATION INSTALLED IS NOT AS LISTED ABOVE

CONTRACTOR TO UP-SIZE CONDUIT & CONDUCTORS TO ALLOW MAX. VOLTAGE DROP OF 2% FOR FEEDER CIRCUITS AND MAX. OF 3% FOR BRANCH CIRCUITS IF INSTALLED LENGTHS EXCEEDS THOSE LISTED ABOVE.

* DISTANCES INDICATED ALLOW FOR A MAX. OF 3% VOLTAGE DROP FOR BRANCH CIRCUITS IN COMPLIANCE WITH 2014 FLORIDA ENERGY CODE.

** DISTANCES INDICATED ALLOW FOR A MAX. OF 2% VOLTAGE DROP FOR FEEDER CIRCUITS IN COMPLIANCE WITH 2014 FLORIDA ENERGY CODE.

FAULT CURRENT STUDY

UTILITY VOLTAGE: 208 | TRANSFORMER KVA: 750 | UTILITY ORIGIN FAULT: 34285

FEEDER ORIGIN	FEEDER DESTINATION	FEEDER LENGTH	FEEDER WIRE	FEEDER SIZE	FEEDER SETS	SOURCE	ORIGIN X/R RATIO	ORIGIN FAULT	DESTINATION X/R RATIO	DESTINATION FAULT
UTILITY	MDP	35	CU	500	8	UTILITY	15.00	34285	11.02	32970
MDP	SFL	20	CU	40	1	UTILITY	11.02	32970	3.15	26897
MDP	A	95	CU	40	1	UTILITY	11.02	32970	1.28	14295
MDP	B	95	CU	1	1	UTILITY	11.02	32970	0.55	8374
MDP	C	225	CU	1	1	UTILITY	11.02	32970	0.39	7017
MDP	D	20	CU	40	1	UTILITY	11.02	32970	3.15	26897
MDP	ATS-E.QUIP.	20	CU	10	1	UTILITY	11.02	32970	1.81	24480
ATS-EQUIP.	E	5	CU	10	1	UTILITY	1.81	24480	1.55	22613
E	EA	180	CU	10	1	UTILITY	1.55	22613	0.49	4960
E	SCP	110	CU	8	1	UTILITY	1.55	22613	0.17	2466
MDP	ATS-EM	10	CU	1	1	UTILITY	11.02	32970	2.45	28012
ATS-EM	EM	5	CU	1	1	UTILITY	2.45	28012	1.83	25447
MDP	F	105	CU	40	1	UTILITY	11.02	32970	1.22	13595
MDP	H	95	CU	1	1	UTILITY	11.02	32970	0.55	8374
MDP	K	135	CU	500	1	UTILITY	11.02	32970	2.58	16446
MDP	M	105	CU	40	1	UTILITY	11.02	32970	1.22	13595
MDP	P	30	CU	40	1	UTILITY	11.02	32970	2.45	24337
MDP	Q	180	CU	40	1	UTILITY	11.02	32970	0.87	9230
MDP	R	225	CU	40	1	UTILITY	11.02	32970	0.90	7532
MDP	MC1	135	CU	350	3	UTILITY	11.02	32970	2.91	22590
MDP	MC2	75	CU	350	3	UTILITY	11.02	32970	3.98	26440

VOLTAGE DROP STUDY

FEEDER

ORIGIN	DESTINATION	VOLTAGE	PHASE	LENGTH	LOAD	SETS	SIZE	TYPE	VOLTAGE DROP (%)
UTILITY	MDP	208	3	35	2218	8	500	CU	0.17
MDP	SFL	208	3	20	89	1	40	CU	0.25
MDP	A	208	3	95	126	1	40	CU	0.68
MDP	B	208	3	95	45	1	1	CU	0.62
MDP	C	208	3	225	23	1	1	CU	0.73
MDP	D	208	3	20	74	1	40	CU	0.24
MDP	ATS-E.QUIP.	208	3	20	137	1	10	CU	0.41
ATS-E.QUIP.	E	208	3	5	137	1	10	CU	0.47
E	E.A	208	3	180	68	1	10	CU	1.54
E	SCP	208	3	110	18	1	6	CU	1.14
MDP	ATS-EM	208	3	10	27	1	1	CU	0.20
ATS-E.M.	E.M.	208	3	5	27	1	1	CU	0.22
MDP	F	208	3	105	80	1	40	CU	0.53
MDP	H	208	3	95	28	1	1	CU	0.46
MDP	K	208	3	135	214	1	500	CU	0.58
MDP	M	208	3	105	153	1	40	CU	0.86
MDP	P	208	3	30	133	1	40	CU	0.34
MDP	Q	208	3	180	90	1	40	CU	0.87
MDP	R	208	3	225	110	1	40	CU	1.23
MDP	MC1	208	3	135	646	3	350	CU	0.92
MDP	MC2	208	3	75	302	3	350	CU	0.37

SUMMARY OF LOADS

	Description	Connected (kVA)	Demand Factor	Demand (kVA)
1	Lighting	140.4	1.00	140.4
2	Air Conditioning	140.4	1.00	140.4
3	Refrigeration (units)	220.8		
	(cases)	52.5		
	(non-coincident)	76.6		
	(Total)	379.9	1.00	303.9
4	Kitchen Equipment	259.4	0.65	168.6
5	Misc. Equipment	110.1	1.00	110.1
6	Receptacles (1st 10.0 kW)	10.0	1.00	10.0
	(Remaining)	22.7	0.50	11.3
	(Total)	32.7		21.3
	Total kVA	992.9	0.85	795.5
	Total Amps	2664		2216

ELECTRICAL CHARACTERISTICS

VOLTAGE : 120/208 VOLTS 3PH, 4 WIRE LOADS
MAIN SWITCHGEAR RATING: 100,000 A.I.C.
MIN. FEEDER BREAKER RATING TO BE 100,000 A.I.C.

MAXIMUM AVAILABLE FAULT CURRENT VALUE PROVIDED BY LOCAL UTILITY IS 34,285 AMPS
THE CURRENT SYSTEM IS DESIGNED AND BRACED FOR A FAULT CURRENT OF 100,000 AMPS SYMM.

MAIN SWITCHBOARD SCHEDULE

SQUARE 'D' 3000 AMP FRAME SWITCHBOARD RATED 100,000 AIC SYM

CKT NO	OVERCURRENT DEVICE FRAME	TRIP	POLES	DEVICE SERVED	CONNECTED VA PHASE A	PHASE B	PHASE C	TOTAL CONNECTED
	3000	3000	3	MAIN CIRCUIT BREAKER	330738	319773	315886	966131
1	225	225	3	PANEL 'A'	31296	37984	37940	107220
2	100	100	3	PANEL 'B'	34568	41184	42952	118704
3	225	225	3	PANEL 'D'	8648	8418	9251	26312
4	600	600	3	PANEL 'MC1'	78924	79116	78448	236488
5	600	600	3	PANEL 'MC2'	38228	38228	38228	108684
6	225	150	3	PANELS 'E' & 'EA'	17406	16848	16930	49184
7	225	125	3	PANEL 'EM'	2520	2520	1680	7824
8	225	225	3	SPARE				0
9	225		3	SPACE ONLY				0
10	225	225	3	PANEL 'F'	12999	9478	8095	29572
11	100	100	3	PANEL 'H'	2774	2680	2940	8394
12	100	100	3	PANEL 'K'	10641	10003	8124	28868
13	225	225	3	SPARE				0
14				BUSSED SPACE(S)/NUSABLE)				0
15	100	100	3	SPARE				0
16	400	400	3	PANEL 'L'	39520	39520	39520	118560
17	100	100	3	SPARE				0
18	225		3	SPACE ONLY				0
19	100	60	3	SPD				0
20	225	225	3	PANEL 'M'	31493	16972	24999	73464
21	225	225	3	PANEL 'P'	22911	24422	21466	68799
22	225	225	3	PANEL 'Q'	9988	12048	10481	32517
23	225	225	3	PANEL 'R'	13648	4000	13927	31575
24	225	225	3	PANEL 'SFL'	9667	3000	9822	26812
25				BUSSED SPACE(S)/NUSABLE)				0
26	225		3	SPACE ONLY				0
27	225		3	SPACE ONLY				0
28	225		3	SPACE ONLY				0
29	225		3	SPACE ONLY				0
30	225		3	SPACE ONLY				0
31	225		3	SPACE ONLY				0

NOTE:
COORDINATE ALL ELECTRICAL CONNECTIONS TO MOTOR CENTER WITH MANUFACTURER REPRESENTATIVES

* THIS UNIT IS SUPPLIED WITH DISCONNECT SWITCH TO BE WIRED BY CONTRACTOR. CONTRACTOR TO VERIFY EXACT EQUIPMENT REQUIREMENTS PRIOR TO ROUGH-IN AND CONTACT ENGINEER FOR DIRECTIONS IF REQUIREMENTS ARE DIFFERENT THAN IN THESE DOCUMENTS.

NOTES:

1. ALL CONDUCTORS SHALL BE COPPER UNLESS NOTED OTHERWISE.
   - ALL CONDUCTORS IN DRY/DAMP LOCATIONS SHALL BE THHN OR EQUAL.
   - ALL CONDUCTORS UNDERGROUND OR IN WET LOCATIONS SHALL BE THWN-2 OR EQUAL.
2. CONTRACTOR TO VERIFY MAXIMUM BREAKER SIZES WITH ACTIVE EQUIPMENT NAME PLATES, PRIOR TO ORDERING BREAKERS.
3. CONTRACTOR TO PROVIDE PLAQUES AT ALL LOCATIONS AS REQUIRED BY CODE OF SERVICE DISCONNECTING MEANS.
4. *AUTOMATIC TRANSFER SWITCHES SHALL BE OPEN TRANSITION MDP CIRCUIT BREAKER FEEDING RESPECTIVE ATS SHALL BE SELECTED TO PROVIDE SOURCE SIDING SIDE) "ACCEPTABLE BREAKER" AS REQUIRED BY MANUFACTURER:*

   FOR 3000 SW'S BASED ABOVE SIZES:
   MDP: ALL AL BKRS. ALL AL L & LI
   ATS'S: GE(QL,QT,QC,QS,QD,QE,QF,QG,QH,QJ,QK,QL,QM,QN,QP,QR,QS) SIEMENS: ALL AL W/ LSI, LSIG, LSIA, LSIGA, & LSIGS
   SEL: SEL-751, 751A, 751A-Y, 751A-Z, 751A-R, 751A-S, 751A-T, 751A-W, & 751A

   FOR 1200 SW'S BASED ABOVE SIZES:
   MDP: ALL AL W/ LSI, LSIG, LSIA, LSIGA, & LSIGS
   ATS'S: GE(QD,QE,QF,QG,QH,QJ,QK,QL,QM,QN,QP,QR,QS) SIEMENS: ALL AL W/ LSI, LSIG, LSIA, LSIGA, & LSIGS
   SEL: SEL-751, 751A, 751A-Y, 751A-Z, 751A-R, 751A-S, 751A-T, 751A-W, & 751A

5. SEE PANELBOARD SCHEDULE SHEET E-16 FOR PANELBOARD AIC MINIMUM RATING.
6. NO REMOTAL CONTACTORS PERMITTED
7. UTILITY TRANSFORMER SHOWN HERE IS PROTOTYPIC DESIGN. ELECTRICAL CONTRACTOR TO SEE CIVIL UTILITY PLANS FOR EXACT LOCATION FOR BIDDING AND INSTALLATION. ELECTRICAL CONTRACTOR TO COORDINATE ALL UTILITY REQUIREMENTS.
8. EDCO SURGE SUPPRESSION UNIT BY ELECTRICAL CONTRACTOR MODEL: HP2061-WA1100, CONTACT KENCH, INC 1 800-362-9997 REFERENCE PUBLIX STORE NUMBER WITH ORDER.
9. ELECTRICAL CONTRACTOR FIELD MARK ALL SWITCHGEAR AND PANELBOARDS WITH A WARNING CONCERNING THE POTENTIAL ARC FLASH HAZARD, PER NFPA 70 SECTION 110-16. COORDINATE REQUIREMENTS WITH THE AHJ.
10. ELECTRICAL CONTRACTOR TO COORDINATE WITH GENERATOR FIELD REP. THAT THE GENERATOR PHASE ROTATION MATCHES THE UTILITY SERVICE.
11. GENERATOR OUTPUT BREAKERS ARE SQ 'D' TYPE HCL. CONTRACTOR TO SELECT PANEL EM BREAKERS TO PROVIDE SELECTIVE COORDINATION PER NFPA-70-700.27.
12. ALL CIRCUIT BREAKERS TO BE ARRANGED AS INDICATED ON PANEL SCHEDULE. ANY DEVIATION MUST BE APPROVED BY THE ENGINEER.
13. *WHERE SERIES RATING IS APPLIED, THE SERIES RATING COMBINATION INTERRUPTING RATING SHALL BE FIELD MARKED ON THE RESPECTIVE PANELBOARD PER NFPA 70, 240.86 AND 110.22. SUBMITTALS SHALL INCLUDE MANUFACTURERS SERIES RATING CHART. CHARTS SHALL INCLUDE VOLTAGE RATING FOR EACH TYPE OF BREAKER INVOLVED f.e. 120/208 OR SIMILAR FOR 1 PH.)*
14. ALL PANELBOARD BUSSING, NEUTRAL/GROUND BUSSES TO BE COPPER. USE OF BRANCH MOUNTED MAIN CIRCUIT BREAKER IS NOT ALLOWED.
15. *ALL BREAKERS IN AN 800 AMP FRAME OR LARGER SHALL BE ELECTRONIC TRIP UNIT SHALL PROVIDE LTD, LTPU, STD, STPU, AND INST. ADJUSTMENTS. SUBMITTALS SHALL INCLUDE TIME/CURRENT CURVES (TCC) AND TCC No. FOR ALL ADJUSTABLE BREAKERS.*
16. SELECTIVE COORDINATION IS A REQUIREMENT FOR ALL ELECTRONIC/ADJUSTABLE CIRCUIT BREAKERS AS WELL AS ANY MOLDED CASE BREAKER (MCCB) BREAKERS ASSOCIATED WITH THE ELECTRONIC ADJUSTABLE CIRCUIT BREAKERS. ADDITIONALLY, THE SERVICE ENTRANCE SHALL BE SELECTIVELY COORDINATED WITH THE UTILITY COMPANY PER NFPA 70-2017. ELECTRICAL CONTRACTOR SHALL CONTACT PUBLIX REPRESENTATIVE TO PROVIDE ENGINEER OF RECORD THE INSTALLED UTILITY XFMR KVA, TRANSFORMER SIZE AND SERVICE LATERAL CONDUCTOR TYPE AND QTY. AT WHICH TIME A SELECTIVE COORDINATION STUDY WILL BE PERFORMED BY PUBLIX THE BREAKER SETTINGS WILL BE PROVIDED TO THE ELECTRICAL CONTRACTOR FOR FINAL ADJUSTMENT WITHIN TWO WEEKS AFTER RECEIPT OF THE FIELD INFORMATION. THE REQUEST FOR THE CIRCUIT BREAKER SETTINGS SHALL BE AFTER PERMANENT POWER AND INSTALLATION OF THE REFRIGERATION MACHINE ROOM UPON COMPLETION OF THE COORDINATION STUDY ANY CIRCUIT BREAKERS PROVIDED BY THE ELECTRICIAN THAT DO NOT COORDINATE, SHALL BE CHANGED (AT NO COST TO PUBLIX) TO CIRCUIT BREAKERS THAT PROVIDE PROPER SELECTIVE COORDINATION. THE ELECTRICAL CONTRACTOR SHALL COORDINATE THE FINAL ADJUSTMENTS AND HAVE THE PUBLIX ELECTRICAL REPRESENTATIVE WITNESS THE TESTS AND CONFIRM PROPER ADJUSTMENT PRIOR TO TCO/CO.
17. ELECTRICAL CONTRACTOR TO PROVIDE INDEPENDENT, 3RD PARTY INSULATION MEGGER TESTING ON ALL SERVICE LATERAL AND GENERATOR FEEDERS. THE TEST SHOULD BE PERFORMED AFTER THE CONDUCTOR INSTALLATION IN THE CONDUIT AND BEFORE ANY CONDUCTOR TERMINATION. MEGGER INSULATION TESTING SHALL BE IN ACCORDANCE TO RECOGNIZED ANSI/NETA STANDARDS. MEGGER INSULATION TEST RESULTS SHALL BE RECORDED IN A SPREADSHEET FORMAT ALONG WITH RECORDING DATE, TIME, AMBIENT TEMPERATURE, AND HUMIDITY AT THE TIME OF TEST. THE SPREADSHEET SHALL BE SENT TO THE ENGINEER OF RECORD FOR REVIEW AND THE FIELD INFORMATION TO BE USED IN THE SELECTIVE COORDINATION STUDY. ANY RESISTANCE VALUES OF TEST CABLES FOUND OUTSIDE OF CABLE MANUFACTURER'S/ANSI/NETA STANDARDS SHALL BE REPLACED AT NO COST TO THE OWNER IF ANY CABLES ARE REPLACED, ALL CABLES IN THE RESPECTIVE SERVICE LATERAL AND FEEDER SHALL BE RETESTED. SEE ADDITIONAL REQUIREMENTS IN ELECTRICAL SPECIFICATION, DIVISION 26 00 00, SECTION 1.4.5 AND SECTION 2.21.
18. ELECTRICAL CONTRACTOR TO PROVIDE AND INSTALL THE FOLLOWING HARDWARE FOR PROPER INSTALLATION OF CONDUCTORS FOR THE 500KW GENERATOR, WHEN 500KW GENERATOR IS USED:

    BURNDY YA50A2 COMPRESSION CONNECTORS FOR 600 MCM CONDUCTORS

    BURNDY YA30A2 COMPRESSION CONNECTORS FOR 400 MCM CONDUCTORS

    ½"x2" STAINLESS STEEL BOLTS

    ½" STAINLESS STEEL NUTS, WASHERS, AND LOCK WASHERS
19. ELECTRICAL CONTRACTOR TO PROVIDE SIGNAGE AT THE MDP INDICATING THE 500KW NATURAL GAS EMERGENCY GENERATOR AND 300KW DIESEL OPTIONAL STANDBY GENERATOR SIZE AND LOCATION IN ACCORDANCE WITH NFPA 70-700.7A AND 70-702.7A. ELECTRICAL CONTRACTOR TO PROVIDE SIGNAGE AT MDP PER NFPA 70-700.7B AND 70-702.7B FOR BOTH GENERATORS.
20. ELECTRICAL CONTRACTOR TO PROVIDE A FAULT CURRENT PLADUE AT THE MDP PER NFPA 70-110.24. PRIOR TO ENERGIZING THE SERVICE, CONFIRM EXACT FAULT CURRENT WITH THE UTILITY AND PROVIDE IN WRITING TO THE ENGINEER OF RECORD ALONG WITH THE CABLE INSULATION MEGGER TEST REQUIREMENTS FROM NOTE 17 AND SELECTIVE COORDINATION REQUIRED FIELD INFORMATION OF NOTE 16.
21. ALL CIRCUIT BREAKERS 1200 AMPS OR HIGHER SHALL COMPLY WITH NFPA 70-240.87 ARC ENERGY REDUCTION. THE ONLY ACCEPTABLE METHOD TO REDUCE CLEARING TIME IS 240.87(B)(3), AN ENERGY REDUCING MAINTENANCE SWITCH WITH LOCAL STATUS INDICATOR.
22. APT SURGE SUPPRESSION UNIT BY ELECTRICAL CONTRACTOR, MODEL TEQ2XAS90D1-RM. CONTACT ROBERT STANLEY WITH EMERSON/APT AT 1-800-237-4367.



SCALE = 1/8" = 1'-0"

APOLLO ENGINEERING, LLC
CONSULTING ENGINEERS
FES#0008833
6544 U.S. Hwy 41 North, Suite 8008, Apollo Beach, FL 33572
Phone: 813.938.5903 / Fax: 813.938.5905
Job # 18113

Copyright 2020 - All rights reserved.

Order Plans @ www.LDIFile.com

"ALL DRAWINGS, AND ALL INFORMATION CONTAINED HEREIN, IN ANY FORM OR MEDIUM, ARE AND SHALL REMAIN THE PROPERTY OF FISHER AND ASSOCIATES, P.A. AND ARCHITECTS PLANNERS INTERIOR DESIGNERS, LLC. AND SHALL NOT BE USED IN WHOLE OR IN PART FOR ANY PURPOSE WHATSOEVER WITHOUT THE WRITTEN PERMISSION OF FISHER AND ASSOCIATES, P.A. AND ARCHITECTS PLANNERS INTERIOR DESIGNERS, LLC. ANY REUSE WITHOUT SUCH PERMISSION WILL BE UNLAWFUL."

"IF THIS SET IS 24" HORIZONTAL, THE DRAWINGS ARE SCALED. IF LESS THAN 24" HORIZONTAL, THE DRAWINGS ARE NOT SCALED. VERIFY SCALE BEFORE USE."

PUBLIX PROTOTYPE BASIS OF DESIGN
20M
EXPANDED
RECEIVED: 09.14.18

FISHER AND ASSOCIATES, P.A.
ARCHITECTS
PLANNERS
INTERIOR DESIGNERS
LLC
2055 SELLEARS CLEARWATER, FL. 33764 727.443.4456

CORPORATE OFFICES, FACILITIES DESIGN
BOX 407, LAKELAND, FL. 33802
(863) 680-5295
PHYSICAL ADDRESS:
3320 AIRPORT RD., LAKELAND, FL. 33811

Publix
SUPER MARKETS

ELECTRICAL RISER DIAGRAM
EAST COBB PUBLIX - #1745
EAST COBB CROSSING SHOPPING CENTER
ROSEWELL ROAD
MARIETTA, GA. 30062

RELEASED FOR:	
BID	
PERMIT	07/16/20
CONSTR.	

REVISIONS:

HAROLD A SCOTT
GEORGIA P.E. #027908

E-9

Issue Date: 04-01-20
Project No.: 220006