## LIGHTING FIXTURE SCHEDULE - INTERIOR/BOH

| TAG | DESCRIPTION | MANUFACTURER | MODEL | LAMP | VOLTAGE | WATTAGE | MOUNTING | DIMMING TYPE | NOTES |
|---|---|---|---|---|---|---|---|---|---|
| A1 | 2X2 RECESSED LED GASKETED A19 LENS | METALUX | 22GR-FA-LED5.0-3200-A19-L835-G2 | 3500K LED | 120 V | 33.0 W | GRID RECESSED | NON-DIMM | |
| A1E | 2X2 RECESSED LED GASKETED A19 LENS-W/BATTERY BACKUP | METALUX | 22GR-FA-LED5.0-3200-A19-L835-G2-EL7W | 3500K LED | 120 V | 33.0 W | GRID RECESSED | NON-DIMM | |
| C1E | 4FT LENSED LED STRIP | METALUX | SNLED-LED5.0-32HL-LN-L835 | 3500K LED | 120 V | 21.7 W | SURFACE | NON-DIMM | |
| C2 | 4' ENCLOSED & GASKETED LED LUMINAIRE WITH SHALLOW ACRYLIC LINEAL RIBBED FROSTED LENS WITH 90 MINUTE BATTERY BACKUP | METALUX | 4VT3-LED5.0-4000-G-120-EL10W-L835 | 4000K LED | 120 V | 32.0 W | SURFACE | NON-DIMM | ELEVATOR PIT AND HOISTWAY LIGHTING |
| EM1 | DUAL HEAD DAMP LOCATION LED EMERGENCY LIGHT | EMERGI-LITE | XEL-2LED | 4000K LED | 120 V | 5.0 W | SURFACE | EMERGENCY | COORDINATE CEILING/WALL MOUNT REQUIREMENTS WITH FLOOR PLAN. FINAL FINISH TO BE COORDINATED WITH INTERIORS. |
| EM2 | WET LOCATION ARCHITECTURAL EMERGENCY EGRESS LIGHT | EMERGI-LITE | LUX-RAY SERIES XX-LUX-SD | 4000K LED | 120 V | 5.0 W | SURFACE | EMERGENCY | FINAL FINSH TO BE COORDINATED WITH INTERIORS. FIXTURE TO BE MOUNTED AT 9FT. |
| G1E | 4" DIA., 4" DEEP, CEILING RECESSED LED DOWNLIGHT, WHEAT REFELECTOR WITH 90 MIN. BATTERY BACKUP | PORTFOLIO | LD4B-15-D010/EU4B-1020-80-27/4LB-W-2-WH-IEM14 | 2700K LED | 120 V | 16.0 W | RECESSED | 0-10V | |
| G2 | 6" DIA LENSED DOWNLIGHT | PATHWAY | 6VLF2X-1500-27K-E1DM-6VLEDFL | 2700K LED | 120 V | 14.0 W | RECESSED | ELV | |
| G3 | 6 INCH BRIDGLUX RECESSED DOWNLIGHT WITH DECORATIVE DISK | PORTFOLIO | 6LBV-40-27K-E1-N30-DA/6PLED-SWT-X/IFE6 | 2700K LED | 120 V | 42.0 W | RECESSED | 0-10V | |
| G5E | 4" APERATURE WET LOCATION RECESSED DOWNLIGHT | PORTFOLIO | LD4B10D010 EU4B10209024 4LBMMW1-IEM14 | 2400K LED | 120 V | 11.0 W | RECESSED | 0-10V | |
| H1 | BELOW BAR LED TAPE LIGHT-2700K-W/EXTRUSION MOUNT | MODA-LITE | STARFLEX,175LU/FT,27K-ELV DIM,1/4"DIM LED | 2700K LED | 120 V | 1.4 W | SURFACE | ELV | |
| H2 | LEVEL 2 BAR LED COVE LIGHT | MODA-LITE | FLATFLEX INTERIOR AMBER | AMBER LED | 120 V | 1.6 W | SURFACE | ELV | |
| H3 | SHELF LED TAPE LIGHT-2700K-W/EXTRUSION MOUNT | MODA-LITE | STARFLEX,175LU/FT,27K-ELV DIM,1/4"DIM LED | 2700K LED | 120 V | 2.1 W | SURFACE | ELV | |
| H4 | GRAND STAIR COVE AIMABLE COVE LIGHT | AMETRIX | LC-1-27K-1-D10-120-24-00 | 2700K LED | 120 V | 8.9 W | COVE | ELV | |
| H5 | BAR SHELVING STRIP LIGHT | LUMINII | KM-HE-X-27K-LO-C-FC-SA-E-1-BLS | 2700K LED | 120 V | 3.0 W | SURFACE | ELV | |
| H6 | PRIVATE DINING RECESSED LINEAR WALL WASH | TROV | L50-I-X-02-27-80-MULT-9x9 | 2700K LED | 120 V | 2.0 W | RECESSED | ELV | |
| H7 | DECORATIVE DEVIDER VERTICAL STRIP LIGHT | KLIK USA | LSECO16SURXX30K500XX0-10 | 2700K LED | 120 V | 1.3 W | SURFACE | ELV | |
| J2 | STAIR LOW PROFILE FULL CUT OFF LED WALLPACK WITH 90 MIN BATTERY BACKUP AND INTEGRAL OCCUPANCY SENSOR | EATON LUMARK | AXCS2ARL-W-AP-MSP/DIM-L12-SMALL WALL MOUNT | 3000K LED | 120 V | 21.0 W | SURFACE | NON-DIMM | STAIR LIGHTING TO DIM TO 50% DURING UNOCCUPIED MODE. FIXTURES TO BE MOUNTED AT 7'6" A.F.F. |
| K1 | PENDANT MTD. TRACK-4 HEAD LENGTH AS SHOWN-PAR30LED | WAC LIGHTING | HT-X-DB/HTK-798-AB | LED | 120 V | 120.0 W | TRACK | TRIAC | PROVIDE WITH 1A CURRENT LIMITER FOR EACH LENGTH OF TRACK. |
| X1 | EDGE LIT LED EXIT SIGN WITH 90 MINUTE BATTERY BACKUP | LITHONIA EDG SERIES | EDG(R) (1/2) X EL | LED | 120 V | 5.0 W | PER RCP | NON-DIMM | COORDINATE REQUIRED FACES AND CHEVRONS WITH FLOOR PLAN. FINAL FINISHES AND LAMPING SHALL BE BY ARCHITECT/INTERIORS. |
| X2 | EXTERIOR WET LOCATION RATED EXIT SIGN WITH 90 MINUTE BATTERY BACKUP | LITHONIA | WLTE X X X EL | LED | 120 V | 5.0 W | PER RCP | NON-DIMM | COORDINATE REQUIRED FACES AND CHEVRONS WITH FLOOR PLAN. FINAL FINISHES AND LAMPING SHALL BE BY ARCHITECT/INTERIORS. |

NOTE:
1. EMERGENCY BATTERY BACKUP SHALL PROVIDE A MINIMUM OF 1000 LUMENS.

## LIGHTING FIXTURE SCHEDULE - EXTERIOR/LANDSCAPE

| TAG | DESCRIPTION | MANUFACTURER | MODEL | LAMP | VOLTAGE | WATTAGE | MOUNTING | DIMMING TYPE | NOTES |
|---|---|---|---|---|---|---|---|---|---|
| B1 | SINGLE SIDED SOLID WOOD BOLLARD | MAC | MAC-X-L27SO-X-120-STD | 2700K LED | 120 V | 12.0 W | GRADE MTD | 0-10V | |
| B2 | DOUBLE SIDED SOLID WOOD BOLLARD | MAC | MACII-X-L27SO-X-120-STD | 2700K LED | 120 V | 12.0 W | GRADE MTD | 0-10V | |
| F1 | HAIKU OUTDOOR RATED FAN WITH LIGHT KIT | BIG ASS FANS | FR127A-X-F1-X | 2700K LED | 120 V | 39.5 W | PENDANT | ELV | COORDINATE FINSHES AND MOUNTING HEIGHTS WITH INTERIORS. PROVIDE WITH MANUFACTURER 0-10V CONTROL INTERFACE. |
| F2 | HAIKU OUTDOOR RATED FAN WITH LIGHT KIT | BIG ASS FANS | FR127A-X-F1-X | 2700K LED | 120 V | 39.5 W | PENDANT | ELV | LEVEL 2 FANS WILL REQUIRE LONGER PENDANT MOUNT. PROVIDE WITH MANUFACTURER 0-10V CONTROL INTERFACE. |
| J1 | LOW PROFILE FULL CUT OFF LED WALLPACK WITH 90 MIN BATTERY BACKUP | EATON LUMARK | ISS-AF-350-LED-E1-T2-7027-BBB | 2700K LED | 120 V | 25.5 W | SURFACE | NON-DIMM | |
| J3 | LOW PROFILE FULL CUT OFF LED WALLPACK WITH 90 MIN BATTERY BACKUP | LITHONIA | WDGE2 LED P2 27K 90CRI VW-E10WH | 2700K LED | 120 V | 15.0 W | SURFACE | NON-DIMM | |
| LS | WET LOCATION POLYESTER POWDER COAT FINISH LANDSCAPE LIGHT | VISTA | PR-7210-DZ-10T3 | 2700K LED | 120 V | 10.0 W | STAKE MTD | NON-DIMM | |
| P1 | FULLY GASKETED EXTERIOR POLE LAMPS | BEGA-US | 84120-K3 BRONZE | 3000K LED | 120 V | 24.0 W | POLE | 0-10V | PROVIDE WITH MANUFACTURER 20FT POLE |
| R1 | STAIR RAIL LIGHTING SPACED AT 12IN O.C. | KLIK | LP4027AXXDIM | 2700K LED | 120 V | 3.0 W | RECESSED | ELV | COORDINATE FINAL MOUNTING REQUIREMENTS WITH RAILING SHOP DRAWINGS. CONTRACTOR TO PROVIDE DRIVER WITH BATTERY PACK FOR RAIL LIGHT, IOTA#ILB1826 WITH-IN REMOTE FIXTURE DRIVER LOCATION. PROVIDE NEMA3R BOX LARGE ENOUGH TO FIT ALL NECESSARY EQUIPMENT FOR COMPLETE OPERATION. |
| S2 | EXTERIOR FACADE GOOSENECK BARN LIGHT | SPECTRUM | WS1611-TD10L-DS2W1-TF2-CP6/RMD-CC-CC | DUAL LED | 120 V | 16.0 W | SURFACE | NON-DIMM | DUAL CIRCUIT FIXTURE 3000K AND AMBER ONLY. TO BE CONTROLLED THROUGH LIGHTING SYSTEM. |
| S3 | EXTERIOR ENTRY WALL SCONCE | WAC LIGHTING | P1541004 | 2700K LED | 120 V | 10.0 W | SURFACE | ELV | |

## LIGHTING FIXTURE SCHEDULE - INTERIOR DESIGNER

| TAG | DESCRIPTION | MANUFACTURER | MODEL | LAMP | VOLTAGE | WATTAGE | MOUNTING | DIMMING TYPE | NOTES |
|---|---|---|---|---|---|---|---|---|---|
| IF-300 | INTERIOR DECORATIVE WALL SCONCE | MAGNI | LAGUNA SCONCE | 2700K INC | 120 V | 40.0 W | SURFACE | ELV | |
| IF-301 | ENTRY DECORATIVE SURFACE MOUNT | LIGHTOLOGY | 30" GRASS CLOTH #MAX670046 | 3000K LED | 120 V | 30.0 W | SURFACE | ELV | |
| IF-302 | BAR DECORATIVE PENDANT | SHADES OF LIGHT | YOUNG HOUSE LOVE WICKER BELL PENDANT | 3000K LED | 120 V | 8.5 W | PENDANT | ELV | |
| IF-303 | OUTDOOR DECORATIVE WALL SCONCE | MODERN FORMS | BALTHUS #MFMP90982 | 3000K LED | 120 V | 10.0 W | SURFACE | ELV | PROVIDE ROSCO #321 AMBER LIGHT FILTER AFFIXED TO INTERIOR OF FIXTURE SHADE. COORDINATE WITH FILTER MANUFACTURER FOR DETAILS. |
| IF-304 | PRIVATE DINING DECORATIVE PENDANT | GRAYPANTS | AUSI SCRAPLIGHT #GRPP137527 - LARGE | 3000K HAL | 120 V | 53.0 W | PENDANT | ELV | |
| IF-304.1 | PRIVATE DINING DECORATIVE PENDANT | GRAYPANTS | AUSI SCRAPLIGHT #GRPP137527 - SMALL | 3000K LED | 120 V | 12.0 W | PENDANT | ELV | |
| IF-305 | GENERAL DINING DECORATIVE PENDANT | SHADES OF LIGHT | FIBER WEAVE LARGE #PE15334 | 3000K LED | 120 V | 15.0 W | PENDANT | ELV | |
| IF-306 | RESTROOM DECORATIVE WALL SCONCE | SONNEMAN | CHELSEA 1 LIGHT BATH BAR #4286.25 | 2200K INC | 120 V | 60.0 W | SURFACE | ELV | |
| IF-307 | ENTRY DECORATIVE SURFACE MOUNT | REJUVENATION | CEDAR&MOSS 24" FLUSH #A0854 | 2700K INC | 120 V | 120.0 W | SURFACE | ELV | |
| IF-308 | GENERAL DINING DECORATIVE PENDANT | REJUVENATION | CEDAR&MOSS 13" PENDANT #A0852 | 2700K INC | 120 V | 120.0 W | PENDANT | ELV | |
| IF-308.1 | GENERAL DINING DECORATIVE PENDANT | REJUVENATION | CEDAR&MOSS 18" PENDANT #A0364 | 2700K INC | 120 V | 120.0 W | PENDANT | ELV | |
| IF-308.2 | GENERAL DINING DECORATIVE PENDANT | REJUVENATION | CEDAR&MOSS 24" PENDANT #A0365 | 2700K INC | 120 V | 180.0 W | PENDANT | ELV | |
| IF-309 | INTERIOR DECORATIVE WALL SCONCE | FEISS | SILO WALL SCONCE #FSSP160580 | 2700K INC | 120 V | 60.0 W | SURFACE | ELV | |
| IF-310 | BAR DECORATIVE PENDANT | SONNEMAN | SUSPENDERS #SLS0157 | 3000K LED | 120 V | 45.0 W | PENDANT | ELV | |
| IF-311 | PRIVATE DINING DECORATIVE PENDANT | REJUVENATION | 30" TIERED DRUM #A7551 | 2700K INC | 120 V | 300.0 W | PENDANT | ELV | |
| IF-312 | RESTROOM DECORATIVE WALL SCONCE | KICHLER | CLYDE WALL SCONCE #456943OZ | 2430K INC | 120 V | 60.0 W | SURFACE | ELV | |

## ELEC - MECHANICAL EQUIPMENT SCHEDULE - DOAS

| TYPE | UNIT NUMBER | UNIT DESCRIPTION | HEATER W | HP | FLA | TOTAL VA | VOLTAGE | POLES | PANEL | CIRCUIT NUMBER | CIRCUIT DESCRIPTION | DISCONNECT | STARTER | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DOAS | 1 | DEDICATED OUTSIDE AIR UNIT | 0 W | 3 | 136.2 A | 49032 VA | 208 V | 3 | MDP | 9 | 3#2/0,1#6G,2"C | 200A/3/3R | W/EQUIP | |

## ELEC - MECHANICAL EQUIPMENT SCHEDULE - DX SPLIT SYSTEM AIR HANDLERS

| TYPE | UNIT NUMBER | UNIT DESCRIPTION | HEATER W | HP (W) | FLA | TOTAL VA | VOLTAGE | POLES | PANEL | CIRCUIT NUMBER | CIRCUIT DESCRIPTION | DISCONNECT | STARTER | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| AC | 101 | LEVEL 1 DINING EAST | 3375 W | 1 | 24.2 A | 5034 VA | 208 V | 2 | M1 | 21,23 | 2#8,1#10G,3/4"C | 60A/2/1 | W/EQUIP | |
| AC | 102 | LEVEL 1 DINING SOUTH | 2250 W | 1 | 17.7 A | 3682 VA | 208 V | 2 | M1 | 24,26 | 2#10,1#10G,3/4"C | 30A/2/1 | W/EQUIP | |
| AC | 103 | LEVEL 1 DINING INTERIOR | 2250 W | 1/3 | 13.7 A | 2850 VA | 208 V | 2 | M1 | 25,27 | 2#12,1#12G,3/4"C | 30A/2/1 | W/EQUIP | |
| AC | 104 | LEVEL 1 ENTRY | 2250 W | 1/3 | 12.6 A | 2621 VA | 208 V | 2 | M1 | 16,18 | 2#12,1#12G,3/4"C | 30A/2/1 | W/EQUIP | |
| AC | 105 | LEVEL 1 KITCHEN | 0 W | 2 | 7.5 A | 2700 VA | 208 V | 3 | M1 | 46,48,50 | 3#12,1#12G,3/4"C | 30A/3/1 | W/EQUIP | |
| AC | 106 | MECHANICAL 119 AIR HANDLER | 0 W | (46) | 0.3 A | 63 VA | 208 V | 2 | M1 | 20,22 | 2#12,1#12G,3/4"C | W/EQUIP | W/EQUIP | CIRCUITED THROUGH EXTERIOR CONDENSING UNIT |
| AC | 201 | LEVEL 2 DINING EAST | 3375 W | 1 | 24.2 A | 5034 VA | 208 V | 2 | M2 | 7,9 | 2#8,1#10G,3/4"C | 60A/2/1 | W/EQUIP | |
| AC | 202 | LEVEL 2 DINING SOUTH | 3375 W | 1 | 24.2 A | 5034 VA | 208 V | 2 | M2 | 10,12 | 2#8,1#10G,3/4"C | 60A/2/1 | W/EQUIP | |
| AC | 203 | LEVEL 2 DINING INTERIOR | 2250 W | 1 | 17.7 A | 3682 VA | 208 V | 2 | M2 | 11,13 | 2#10,1#10G,3/4"C | 30A/2/1 | W/EQUIP | |
| AC | 204 | LEVEL 2 KITCHEN | 0 W | 1 | 6.9 A | 1436 VA | 208 V | 2 | M2 | 14,16 | 2#12,1#12G,3/4"C | 30A/2/1 | W/EQUIP | |
| AC | 205 | IT/AV 210 AIR HANDLER | 0 W | (46) | 0.3 A | 63 VA | 208 V | 2 | M2 | 15,17 | 2#12,1#12G,3/4"C | W/EQUIP | W/EQUIP | CIRCUITED THROUGH EXTERIOR CONDENSING UNIT |
| AC | 301 | ELECTRICAL 306 AIR HANDLER | 0 W | (46) | 0.3 A | 63 VA | 208 V | 2 | M2 | 1,3 | 2#12,1#12G,3/4"C | W/EQUIP | W/EQUIP | CIRCUITED THROUGH EXTERIOR CONDENSING UNIT |
| AC | 302 | MECHANICAL ROOM 305 | 3375 W | 1/3 | 19.1 A | 3983 VA | 208 V | 2 | M2 | 6,8 | 2#10,1#10G,3/4"C | 30A/2/1 | W/EQUIP | |
| AC | 303 | ELEVATOR HOISTWAY | 0 W | (130) | 0.6 A | 76 VA | 208 V | 2 | M2 | 30,32 | 2#12,1#12G,3/4"C | 30A/2/1 | W/EQUIP | CIRCUITED THROUGH EXTERIOR CONDENSING UNIT |

## ELEC - MECHANICAL EQUIPMENT SCHEDULE - DX SPLIT SYSTEM CONDENSING UNITS

| TYPE | UNIT NUMBER | UNIT DESCRIPTION | HEATER W | HP (W) | FLA | TOTAL VA | VOLTAGE | POLES | PANEL | CIRCUIT NUMBER | CIRCUIT DESCRIPTION | DISCONNECT | STARTER | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CU | 101 | LEVEL 1 DINING EAST | 0 W | 1/4 | 27.7 A | 5762 VA | 208 V | 2 | M1 | 43,45 | 2#4,1#10G,1"C | 60A/2/3R | W/UNIT | |
| CU | 102 | LEVEL 1 DINING SOUTH | 0 W | 1/4 | 27.7 A | 5762 VA | 208 V | 2 | M1 | 33,35 | 2#4,1#10G,[illegible] | 60A/2/3R | W/UNIT | |
| CU | 103 | LEVEL 1 DINING INTERIOR | 0 W | 1/6 | 17.8 A | 3703 VA | 208 V | 2 | M1 | 29,31 | 2#8,1#10G,3/4"C | 30A/2/3R | W/UNIT | |
| CU | 104 | LEVEL 1 ENTRY | 0 W | 1/6 | 7.0 A | 1446 VA | 208 V | 2 | M1 | 10,12 | 2#12,1#12G,3/4"C | 30A/2/3R | W/UNIT | |
| CU | 105 | LEVEL 1 KITCHEN | 0 W | 1 | 38.2 A | 13752 VA | 208 V | 3 | M1 | 47,49,51 | [illegible] | 60/3/3R | W/UNIT | |
| CU | 106 | MECHANICAL ROOM 119 | 0 W | (58) | 12.4 A | 2575 VA | 208 V | 2 | M1 | 20,22 | [illegible] | 30A/2/3R | W/UNIT | |
| CU | 201 | LEVEL 2 DINING EAST | 0 W | 1/4 | 27.7 A | 5762 VA | 208 V | 2 | M1 | [illegible] | [illegible] | [illegible] | W/UNIT | |
| CU | 202 | LEVEL 2 DINING SOUTH | 0 W | 1/4 | 27.7 A | 5762 VA | 208 V | 2 | M1 | [illegible] | 2#4,1#10G,1"C | 60/2/3R | W/UNIT | |
| CU | 203 | LEVEL 2 DINING INTERIOR | 0 W | 1/4 | 27.7 A | 5762 VA | 208 V | 2 | M1 | 28,30 | 2#4,1#10G,1"C | 60/2/3R | W/UNIT | |
| CU | 204 | LEVEL 2 KITCHEN | 0 W | 1/4 | 27.7 A | 5762 VA | 208 V | 2 | M1 | 36,38 | 2#4,#10G,1"C | 60/2/3R | W/UNIT | |
| CU | 205 | IT/AV ROOM 210 | 0 W | (58) | 12.4 A | 2575 VA | 208 V | 2 | M2 | 15,17 | 2#12,1#12G,3/4"C | 30A/2/3R | W/UNIT | |
| CU | 301 | MAIN ELECTRICAL ROOM 306 | 0 W | (58) | 12.4 A | 2575 VA | 208 V | 2 | M2 | 1,3 | 2#12,1#12G,3/4"C | 30A/2/3R | W/UNIT | |
| CU | 302 | MECHANICAL ROOM 305 | 0 W | 1/6 | 7.0 A | [illegible] | 208 V | 2 | M1 | [illegible] | 2#12,1#12G,3/4"C | 30A/2/3R | W/UNIT | |
| CU | 303 | ELEVATOR HOISTWAY | 0 W | (39) | 7.6 A | [illegible] | 208 V | 2 | M2 | [illegible] | 2#12,1#12G,3/4"C | 30A/2/3R | W/UNIT | |

## ELEC - MECHANICAL EQUIPMENT SCHEDULE - ELEVATOR SUMP PUMP

| TYPE | UNIT NUMBER | UNIT DESCRIPTION | HEATER W | HP (W) | FLA | TOTAL VA | VOLTAGE | POLES | PANEL | CIRCUIT NUMBER | CIRCUIT DESCRIPTION | DISCONNECT | STARTER | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| ESP | 1 | ELEVATOR SUMP PUMP | 0 W | [illegible] | 12.0 A | [illegible] | [illegible] | 1 | M1 | 6 | 2#12,1#12G,3/4"C | $M | W/EQUIP | |

## ELEC - MECHANICAL EQUIPMENT SCHEDULE - FANS

| TYPE | UNIT NUMBER | UNIT DESCRIPTION | HEATER W | HP (W) | FLA | TOTAL VA | VOLTAGE | POLES | PANEL | CIRCUIT NUMBER | CIRCUIT DESCRIPTION | DISCONNECT | STARTER | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| F | 101 | LEVEL 1 HOOD EXHAUST FAN | 0 W | 3 | 10.6 A | 3960 VA | 208 V | 3 | M2 | 18,20,22 | 3#12,1#12G,3/4"C | 30A/3/3R | W/EQUIP | INTERLOCKED WITH HOOD CONTROL PANEL |
| F | [illegible] | LEVEL 1 RESTROOM EXHAUST | [illegible] | (97) | 3.2 A | 384 VA | 120 V | 1 | M1 | 5 | 2#12,1#12G,3/4"C | $M | NEMA 0 | INTERLOCKED WITH TIME CLOCK |
| F | [illegible] | LEVEL 1 DISHWASHER EXHAUST | 0 W | 1/6 | 1.4 A | 166 VA | 120 V | 1 | M1 | 1 | 2#12,1#12G,3/4"C | $M | NEMA 0 | INTERLOCKED WITH DISHWASHER OPERATION |
| F | 201 | LEVEL 2 HOOD EXHAUST [illegible] | 0 W | 1/2 | 6.5 A | 780 VA | 120 V | 1 | M2 | 19 | 2#12,1#12G,3/4"C | 30A/2/3R | W/EQUIP | INTERLOCKED WITH HOOD CONTROL PANEL |
| F | 202 | LEVEL 2 RESTROOM EXHAUST | 0 W | (97) | 3.2 A | 384 VA | 120 V | 1 | M2 | 21 | 2#12,1#12G,3/4"C | $M | NEMA 0 | INTERLOCKED WITH TIME CLOCK |
| F | [illegible] | LEVEL 2 DISHWASHER EXHAUST | 0 W | 1/6 | 1.4 A | 166 VA | 120 V | 1 | M2 | 23 | 2#12,1#12G,3/4"C | $M | NEMA 0 | INTERLOCKED WITH DISHWASHER OPERATION |

## ELEC - MECHANICAL EQUIPMENT SCHEDULE - HOT WATER SYSTEM

| TYPE | UNIT NUMBER | UNIT DESCRIPTION | HEATER W | HP (W) | FLA | TOTAL VA | VOLTAGE | POLES | PANEL | CIRCUIT NUMBER | CIRCUIT DESCRIPTION | DISCONNECT | STARTER | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| [illegible] | 01 | GAS FIRED WATER HEATER | 0 W | - | 16.0 A | 1920 VA | 120 V | 1 | M2 | 4 | 2#12,1#12G,3/4"C | W/EQUIP | W/EQUIP | |
| GWH | 02 | GAS FIRED WATER HEATER | 0 W | - | 16.0 A | 1920 VA | 120 V | 1 | M2 | 2 | 2#12,1#12G,3/4"C | W/EQUIP | W/EQUIP | |
| HWRP | 01 | HW RECIRCULATING PUMP | 0 W | 1/6 | 2.0 A | 240 VA | 120 V | 1 | M2 | 6 | 2#12,1#12G,3/4"C | $M | W/EQUIP | PROVIDE ALL FINAL CONNECTIONS TO TEMPERATURE SENSOR AND AQUASTAT PER MANUFACTURERS SPECIFICATIONS. |

## ELEC - MECHANICAL EQUIPMENT SCHEDULE - MAKE-UP AIR UNIT

| TYPE | UNIT NUMBER | UNIT DESCRIPTION | HEATER W | HP | FLA | TOTAL VA | VOLTAGE | POLES | PANEL | CIRCUIT NUMBER | CIRCUIT DESCRIPTION | DISCONNECT | STARTER | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| MAU | 1 | LEVEL 1 HOOD MAKE-UP AIR FAN | 0 W | 3 | 58.8 A | 21168 VA | 208 V | 3 | M2 | 24,26,28 | 3#4,1#8G,1"C | 100A/3/3R | W/EQUIP | INTERLOCKED WITH HOOD CONTROL PANEL |

## ELEC - MECHANICAL EQUIPMENT SCHEDULE - UNHEATED AIR CURTAINS

| TYPE | UNIT NUMBER | UNIT DESCRIPTION | HEATER W | HP (W) | FLA | TOTAL VA | VOLTAGE | POLES | PANEL | CIRCUIT NUMBER | CIRCUIT DESCRIPTION | DISCONNECT | STARTER | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| UAC | 1 | LEVEL 1 KITCHEN AIR CURTAIN | 0 W | 1/6 | 2.4 A | 288 VA | 120 V | 1 | M1 | 2 | 2#12,1#12G,3/4"C | W/EQUIP | W/EQUIP | |
| UAC | 2 | LEVEL 1 KITCHEN AIR CURTAIN | 0 W | (2) 1/6 | 2.6 A | 312 VA | 120 V | 1 | M1 | 2 | 2#12,1#12G,3/4"C | W/EQUIP | W/EQUIP | |
| UAC | 201 | LEVEL 2 KITCHEN AIR CURTAIN | 0 W | 1/6 | 2.4 A | 288 VA | 120 V | 1 | M2 | 25 | 2#12,1#12G,3/4"C | W/EQUIP | W/EQUIP | |

## ELEC - MECHANICAL EQUIPMENT SCHEDULE - ELECTRIC WALL HEATER

| TYPE | UNIT NUMBER | UNIT DESCRIPTION | HEATER W | HP (W) | FLA | TOTAL VA | VOLTAGE | POLES | PANEL | CIRCUIT NUMBER | CIRCUIT DESCRIPTION | DISCONNECT | STARTER | NOTES |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| EH | 301 | DECK LEVEL VESTIBULE | 1500 W | - | 12.5 A | 1500 VA | 120 V | 1 | M2 | 31 | 2#12,1#12G,3/4"C | W/EQUIP | W/EQUIP | |

Order Plans @ WWW.LDILine.com

PLOT DATE: 5/28/2020 3:43:37 PM TEMPLATE VERSION:

Thompson Ehle Company
www.teceng.org
Tel (713) 518-1426
TEC Project #219018

© 2016 HKS ARCHITECTS, INC.

HKS

**ARCHITECT**
HKS ARCHITECTS, INC.
#AA F000119
201 ALHAMBRA CIRCLE, SUITE 800
CORAL GABLES, FL 33134

**CIVIL ENGINEER**
KIMLEY-HORN
12740 GRAN BAY PARKWAY WEST
SUITE 2350
JACKSONVILLE, FL 32258

**STRUCTURAL CONSULTANT**
THORNTON TOMASETTI
101 NE THIRD AVE., SUITE 1170
FORT LAUDERDALE, FL 33301-1199

**MEP CONSULTANT**
THOMPSON EHLE
50 TECHNOLOGY PKWY S. PEACHTREE CORNERS, GA 30092

**KITCHEN CONSULTANT**
INNOVATIVE FOOD SERVICE
11101 NORTH 46TH STREET, TAMPA, FL 33617

**WATERPROOFING CONSULTANT**
CDC USA
8070 Park Ln., Suite 400 Dallas, TX 75231

**CODE & LIFE SAFETY CONSULTANT**
HOWE ENGINEERS
101 LONGWATER CIR, NORWELL, MA 02061

# MARRIOTT SAWGRASS CABANA CLUB

**OWNER**
WATERMARK CAPITAL PARTNERS, LLC
150 NORTH RIVERSIDE PLAZA SUITE 4200
CHICAGO, IL 60606

**OWNER'S CONSULTANT**
THE JOHN HARDY GROUP INC.
6085 BARFIELD RD. SUITE 200
ATLANTA, GA 30328

Benjamin Kowalczyk, State of Florida, Professional Engineer, License No. 77831

This item has been electronically signed and sealed by Benjamin Kowalczyk, on the Date and/or Time Stamp using a digital signature.

Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copy.

KEY PLAN




REVISION
NO. DESCRIPTION DATE

HKS PROJECT NUMBER
**22808.001**
DATE
**05/22/2020**
ISSUE
**PERMIT SET**

SHEET TITLE
**SCHEDULES - ELECTRICAL**

SHEET NO.
**E0.02**