

Order Plans @ WWW.LDILine.com

- KEYNOTES**
- 1 CONTRACTOR TO VERIFY ABOVE CEILING MEP TO REMAIN IN EXPOSED CEILING AND COORDINATE WITH NC STATE FACILITIES TO IDENTIFY ABANDONED PIPING AND CONTROLS.
 - 2 CONTRACTOR TO REMOVE EXISTING RETURN AIR GRILLE IN FLOOR AND PATCH CONCRETE FLOOR PENETRATION TO MATCH SURROUNDING FLOOR STRUCTURE AND FINISH (TYPICAL).
 - 3 EXISTING THERMOSTAT TO BE RELOCATED. SEE SHEET M101 FOR NEW LOCATION.
 - 4 EXISTING FIRE DAMPER IN AIR TRANSFER OPENING TO BE DEMOLISHED AND AIR TRANSFER OPENING IN WALL TO REMAIN.

1 LEVEL 01 - DEMOLITION MECHANICAL FLOOR PLAN
1/8" = 1'-0"

ARCHITECTURE
INTERIORS
PLANNING

WTS
WATSON TATE SAVORY

NC STATE
UNIVERSITY



Jordan Hall Library Renovation
Watson Tate Savory
NCSU Jordan Hall



ISSUE DATE	08/24/2020	
PHASE	Bid Set	
#	DATE	REVISION

DEMOLITION
MECHANICAL
PLAN - LEVEL 01

19244
A/E PROJECT NO. SHEET
Optima # 19-0360 Sheet 3 of 5

