

CEILING GRID#2 TO BE INSTALLED CENTERED ABOVE DINING ROOM SPACE

SPECIFICATIONS: **DIVISION 9: FINISHES**

SECTION 9C: SUSPENDED CEILING

GENERAL PROVISIONS

1. SCOPE: FURNISH AND INSTALL ACOUSTICAL TILE PANELS WITH MANUFACTURER'S SUSPENSION SYSTEM.

PERFORMANCE

INSTALLATION. GRID SHALL BE INSTALLED AS SHOWN AND IN STRICT ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS. LEVEL ACCURATELY AND HANG FROM #9 GAUGE ANNEALED WIRE NOT OVER 4' ON CENTERS. PROVIDE HOLD-DOWN CLIPS. COOPERATE IN FITTING AROUND AIR CONDITIONING AND VENTILATION OUTLETS. TRY TO AVID FITTING RECESSED LIGHT FIXTURES WITHIN 3" OF EDGE OF TILE.

GENERAL NOTES

CEILING GRID SHALL BE SUPPORTED FROM STRUCTURAL MEMBERS ONLY, GRID SHALL NOT BE SUPPORTED FROM OTHER TRADES WORK. COORDINATE GRID INSTALLATION WITH LOCATION OF MECHANICAL EQUIPMENT AS INDICATED ON SHEET M-1 AND E-1.

3) HANGER WIRES FOR GRID SHALL BE INSTALLED AT NOT MORE TO O.C. AND AT EACH CORNER OF LAYIN LIGHT FIXTURES. SEE ELECT PLANS FOR FIXTURE LOCATIONS.

4) CEILING GRID SHOULD BE CENTERED AT

15/16" DBL. WEBB HOT DIPPED GALV. STEEL TEE, ALUMINUM CAP #ZXA BY U.S.G.-COLOR: WHITE

U.S.G. SHEETROCK BRAND LAY-IN CEILING TILE -"CLIMAPLUS" #3270, WHITE VINYL 24"x48"x1/2"


DX26 15/16" EXPOSED GRID SYSTEM, ALUMINUM CAP #ZXA U.S.G. -COLOR: WHITE.

U.S.G. "RADAR CLIMAPLUS" # 2220, STL EDGES, 24"x24" WHITE

ACOU2 U.S.G. "RADAR CLIMAPLUS" # 2420

CONSTRUCTION KEY NOTES

- ONTRACTOR SHALL PROVIDE AND INSTALL STAINLESS STEEL CEILING PANELS (20 GAUGE) AT HOOD AREA. INSTALLATION SHALL EXTEND A MINIMUM 18" BEYOND THE EDGE OF THE HOOD, UNLESS SPECIFIED OTHERWISE.
- 2 INSTALL A STAINLESS STEEL CAP ALONG THE BOTTOM EDGE OF THE BULKHEAD TO A HEIGHT OD 3" UP THE SIDES.
- PAINT THE UNDERSIDE OF THE FUR-DOWN AT THE FRONT COUNTER P-8 AS SPECIFIED ON THE INTERIOR FINISH SCHEDULE.
- 4 GC SHALL COORDINATE THE INSTALL OF THE MENU BOARD WITH SICOM AT THE LOCATION SHOWN. COORDINATE WITH THE POPEYES CONSTRUCTION MANAGER AND SICOM FOR INSTALLATION TIMELINES AND REQUIREMENTS.
- 5 THE LIGHTING FIXTURES BELOW THE CANOPY SHALL BE PREINSTALLED BY THE CANOPY MANUFACTURER. CONTACT THE MANUFACTURER TO VERIFY ELECTRICAL REQUIREMENTS.
- 6 THE "E" FIXTURE LIGHTS ARE CENTERED ABOVE THE GLAZING AT THE CENTER LINE. THE GC SHALL ENSURE THAT THE AWNING INSTALLERS ADJUST THE AWNING STRUTS TO AVOID THE FIXTURES.
- CONTRACTOR SHALL INSTALL THE PENDANT LIGHTS AT THE SELF SERVE DRINK STATION AFTER ALL THE EQUIPMENT HAS BEEN INSTALLED AND SHOWN TO BE OPERATIONAL.



SECTION @ MENUBOARD


7 ressive

Q 9 a



POPeyes

LEBLON FRANCHISING
HOLDINGS, LLC.
POPEYE'S
LOUISIANA KITCHEN
221 CONCORD PARKWAY SOU



51348

FOR CONSTRUCTION

ISSUANCE PERMIT SUBMITTAL 08/14/2020

REVISIONS

NO. DATE DESCRIPTION

FILENLIMBER PROJECT MANAGER PROFESSIONAL DRAWN BY CHECKED BY

REFLECTED **CEILING PLAN**