

DEMOLITION LEGEND & NOTES

- NO WORK AREA - NOT IN SCOPE (does not indicate mechanical, fire protection, or data scope - see map and I/P drawings for further information)
- WORK AREA
- WORK NOT PERFORMED IN THIS PHASE
- NEW WORK:
RED - (CUT VIEW)
PINK - (PROJECTION VIEW)
- DEMOLITION

- DASHED LINES TO BE DEMOLISHED. SEE DEMOLITION NOTES
- SOLID LINES AND SHADED ELEMENTS TO REMAIN
- NO WORK AREA NOT IN SCOPE
- EXST. F.F. ELEV. THIS AREA
- EXST. BUILDING PHOTO LOCATION

GENERAL DEMOLITION NOTES:

- A. VERIFY WITH OWNER ANY ITEMS TO BE SALVAGED & DISPOSITION OF SUCH ITEMS
- B. CLEAN AND PREPARE INTERIOR SURFACES AND MATERIALS AFFECTED BY DEMOLITION TO ACCOMMODATE NEW CONSTRUCTION. GC SHALL BE RESPONSIBLE FOR PATCHING AND/OR PROVIDED NEW FINISH TO ALL SURFACES REWORKED OR DISTURBED INTERIOR SURFACES THAT WILL REMAIN.
- C. REVIEW PLANS AND REFLECTED CEILING PLANS TO COORDINATE EXISTING WALL AND CEILING DEMOLITION REQUIRED FOR NEW CONSTRUCTION.
- D. REF. STRUCT. PLUMBING DRAWINGS FOR PROTECTIVE DEMOLITION AND REMOVAL OF EXISTING STRUCTURAL BEAMS, MECHANICAL AND ELECTRICAL BUILDING ELEMENTS NOT NECESSARILY SHOWN IN THIS DRAWING.
- E. ALL EXISTING PLUMBING AND ELECTRICAL WORKERS TO REVIEW U.N.O. REF PLUMBING DRAWINGS.
- F. REF. SPECIFICATIONS FOR PROTECTIVE DEMOLITION AND INSPECTION REQUIRED BY CONTRACTOR PRIOR TO BIDDING AND COMMENCEMENT OF WORK. OWNER DOES NOT GUARANTEE THAT EXISTING CONDITIONS ARE THE SAME AS THOSE IN THE ABOVE DOCUMENTS.

RCP DEMO KEYNOTES

- 01 DEMOLISH GYP. ARCHED CANOPY
- 02 DEMOLISH ALL BUILT-IN ROOM ENTRY CASINGS
- 03 EXISTING RADIUS GYP. CEILING TO REMAIN
- 04 DEMOLISH REFERENCE DESK BUILT-IN DESK & CANOPY
- 05 DEMOLISH LIGHTS
- 06 REMOVE ROTTEN CEILING AND REPLACE WITH SIMILAR

NOTES:


1. OVERALL PLANS ARE PROVIDED FOR COORDINATION PURPOSES ONLY - REFERENCE ENLARGED REFLECTED CEILING PLANS FOR SPECIFIC DESIGN INFORMATION.
2. REFERENCE MECHANICAL, ELECTRICAL, AND ALL DRAWINGS FOR ADDITIONAL INSTALLED EQUIPMENT NOT SHOWN THIS PLAN.

- 2X2 ACOUSTICAL SUSPENDED CEILING SYSTEM (ACT-1) - REPLACE DAMAGED TILES WITH NEW - (5% OF TOTAL)
- N-PLACE PRESSED TIN CEILING
- GWB BOARD CEILING OR SOFFIT (GWB)
- PENDANT LED LINEAR LIGHT FIXTURE, 4" WIDTH, LENGTH VARIES PER PLAN
- RECESSED LINEAR DOWNLIGHT, 4" WIDTH WHEN HOSTED IN 2X4, AND 6" WIDTH WHEN HOSTED IN 2X4, LENGTH VARIES PER PLAN
- SQUARE PENDANT LED FIXTURE, LENGTH AND WIDTH VARIES PER PLAN
- 2x4 LED RECESSED LIGHT FIXTURE
- WALL SCONCE INDIRECT LED FIXTURE
- RCP KEYNOTE SYMBOL, SEE BELOW
- EXISTING TONGUE AND GROOVE WOOD CEILING - PAINT - SEE FINISH SCHEDULE

RCP LEGEND
1/8" = 1'-0"

KEYPLAN WITH FUNDING DEFINED

- NEW ACCESSIBLE ENTRANCE & ADA ELEVATOR AREA
50% FUNDING AIKEN CO. 50% FRIENDS OF THE LIBRARY
- LIBRARY
23% FUNDING AIKEN CO. 1/3% FRIENDS OF THE LIBRARY
- NORTH WING
100% FUNDING AIKEN CO.



AIKEN PUBLIC LIBRARY RENOVATION PHASE II & PHASE III



CONSULTANT LOGO

SEAL



AIKEN COUNTY
AIKEN PUBLIC LIBRARY & NORTH WING RENOVATION
 314 CHESTERFIELD ST. S, AIKEN, SC

SHEET ISSUE			
NO.	DATE	DESCRIPTION	BY
B	03/06/2020	DD SET	
D	04/10/2020	PERMIT SET	
E	07/02/2020	ISSUED FOR BIDS	

ISSUED FOR BIDS 07/02/2020
 PRINCIPAL IN CHARGE DRM
 PROJECT ARCHITECT TA
 DRAWN BY JTP

SHEET TITLE:
**SECOND FLOOR
 DEMOLITION
 REFLECTED CEILING
 PLANS**

PROJ. NO. 019477.01

A044

