

ROOM FINISH SCHEDULE - PHASE I												
ROOM NO.	ROOM NAME	FLOOR		WALLS				CEILING		MILLWORK		COMMENTS
		FINISH	BASE	N	E	S	W	MATERIAL	FINISH	C'TOPS	CABINETS	
ADA LOBBY												
021	LOBBY	WOF-1	WB	P-2.3'	P-2.3'	P-2.3'	P-2.3'	GYP BD	P-1	-	-	REF PAINT TYPICAL DETAIL FOR LIBRARY ON WALL FINISH PLAN
LEVEL 1												
150	CORRIDOR	EXP PLVWD	ETR	P-2.2TR	P-2.2TR	P-2.2TR	P-2.2TR	-	-	-	-	REF WALL FINISH PLAN FOR EXACT EXTENT **PATCH TO MATCH EXISTING BASE AS NEEDED
153	FUTURE TENANT	EXP PLVWD	ETR	P-2	P-2	P-2	P-2	-	-	-	-	REF WALL FINISH PLAN FOR EXACT EXTENT **PATCH TO MATCH EXISTING BASE AS NEEDED
154	CORRIDOR	EXP PLVWD	ETR	P-2.2TR	P-2.2TR	P-2.2TR	P-2.2TR	-	-	-	-	REF PAINT TYPICAL DETAIL FOR NORTH WING ON WALL FINISH PLAN
155	TOILET	CT-1	TR-1.2"	P-2	P-2	P-2	P-2	GYP BD	P-1	-	-	CT-2 SHALL BE INSTALLED FULL HEIGHT OF WALL **TR-1 SHALL BE USED TO TRANSITION WALL TILE TO FLOOR TILE. REMAINING WALLS SHALL RECEIVE TR-2
156	ELEV MACHINE ROOM	EXP PLVWD	ETR	P-2	P-2	P-2	P-2	GYP BD	P-1	-	-	REF WALL FINISH PLAN FOR EXACT EXTENT **PATCH TO MATCH EXISTING BASE AS NEEDED
159	NW LOBBY	EXP PLVWD	ETR	P-2	P-2	P-2	P-2	-	-	-	-	REF WALL FINISH PLAN FOR EXACT EXTENT **PATCH TO MATCH EXISTING BASE AS NEEDED
LEVEL 2												
200	ELEV VESTIBULE	ETR	ETR	ETR	ETR	ETR	ETR	WD	P-1	-	-	ADD ALTERNATE DEMO EXISTING TILE PREP SUBFLOOR AND INSTALL CARPET TILE FROM ATTIC STOCK OR DEMO CARPET ON FIRST FLOOR. PATCH TO MATCH EXISTING WOOD BASE AS NEEDED **PAINT WALLS P-2 AS PART OF ADD ALTERNATE
201	CORRIDOR	ETR	ETR	P-2.3'	P-2.3'	P-2.3'	P-2.3'	WD	P-1	-	-	REF PAINT TYPICAL DETAIL FOR LIBRARY ON WALL FINISH PLAN **PATCH EXISTING CARPET AS NEEDED
202	GROUP STUDY	ETR	WB	P-2	P-2	P-2	P-2	ACT	-	-	-	PATCH EXISTING CARPET AS INDICATED ON THE FLOOR FINISH PLAN
203	GROUP STUDY	ETR	WB	P-2	P-2	P-2	P-2	ACT	-	-	-	PATCH EXISTING CARPET AS INDICATED ON THE FLOOR FINISH PLAN
207	READING ROOM	ETR	WB	P-2.3"	P-2.3"	P-2.3"	P-2.3"	ACT	-	SS-1	WS-1 PLUM-2"	REF PAINT TYPICAL DETAIL FOR LIBRARY ON WALL FINISH PLAN **REF MILLWORK VIEWS FOR LOCATION OF EACH FINISH
208	CONFERENCE ROOM	ETR	WB	P-2	P-3	P-2	P-2	ACT	-	-	-	PATCH EXISTING CARPET AS INDICATED ON THE FLOOR FINISH PLAN **PAINT FOR GYP ONLY. DO NOT PAINT EXISTING DISPLAY CASE
213	CAROLINA ROOM	ETR	ETR	P-3	P-3	P-3	P-3	ETR	ETR	-	-	PATCH EXISTING CARPET AS INDICATED ON THE FLOOR FINISH PLAN
214	CORRIDOR	ETR	WB	P-2	P-2	P-2	P-2	ETR	ETR	-	-	PATCH EXISTING CARPET AS INDICATED ON THE FLOOR FINISH PLAN
216	BRANCH MANAGER OFFICE	ETR	ETR	P-2	P-2	P-2	P-2	ETR	ETR	-	-	PATCH EXISTING CARPET AS INDICATED ON THE FLOOR FINISH PLAN **TOUCH UP MATCH EXISTING BASE AS NEEDED
218	STUDY AREA	ETR	WB	P-3	P-3	P-3	P-3	ACT	ACT	ACT	ACT	REF WALL FINISH PLAN FOR EXACT EXTENT **PATCH TO MATCH EXISTING BASE AS NEEDED
250	CORRIDOR	EXP PLVWD	ETR	P-2.2TR	P-2.2TR	P-2.2TR	P-2.2TR	-	-	-	-	REF PAINT TYPICAL DETAIL FOR NORTH WING ON WALL FINISH PLAN
261	FUTURE TENANT	EXP PLVWD	ETR	P-2	P-2	P-2	P-2	-	-	-	-	REF PAINT TYPICAL DETAIL FOR NORTH WING ON WALL FINISH PLAN
264	ELEV LOBBY	EXP PLVWD	ETR	P-2.2TR	P-2.2TR	P-2.2TR	P-2.2TR	-	-	-	-	REF WALL FINISH PLAN FOR EXACT EXTENT **PATCH TO MATCH EXISTING BASE AS NEEDED

ROOM FINISH SCHEDULE - PHASE II												
ROOM NO.	ROOM NAME	FLOOR		WALLS				CEILING		MILLWORK		COMMENTS
		FINISH	BASE	N	E	S	W	MATERIAL	FINISH	C'TOPS	CABINETS	
LEVEL 1												
100	VESTIBULE	WOF-1	WB	P-2.3'	P-2.3'	P-2.3'	P-2.3'	EXP WD	P-3	-	-	REF PAINT TYPICAL DETAIL FOR LIBRARY ON WALL FINISH PLAN
101	MULTIPURPOSE ROOM	CPT-1.3'	WB	P-2.3"	P-2.3"	P-2	P-2	ACTEXP WD	P-1	-	-	INSTALL RANDOM MIX OF CPT-1 (50%) AND CPT-3 (50%) **REF WALL FINISH PLAN FOR EXACT EXTENT
102	STORAGE	CPT-1	WB	P-2	P-2	P-2	P-2	ACT	-	-	-	REF WALL FINISH PLAN FOR EXACT EXTENT
103	CORRIDOR	CPT-1	WB	P-2.3'	P-2.3'	P-2.3'	P-2.3'	EXP WD	P-3	-	-	REF PAINT TYPICAL DETAIL FOR LIBRARY ON WALL FINISH PLAN
104	ELEV VESTIBULE	ETR	ETR	ETR	ETR	ETR	ETR	EXP WD	-	-	-	ADD ALTERNATE DEMO EXISTING TILE PREP SUBFLOOR. INSTALL CPT-1 AND PATCH TO MATCH EXISTING WOOD BASE **PAINT WALLS P-2 AS PART OF ADD ALTERNATE
107	KITCHENETTE	LVT-1	WB	P-2	P-2	P-2	P-2	ETR	ETR	ETR	ETR	REF WALL FINISH PLAN FOR EXACT EXTENT **PATCH TO MATCH EXISTING BASE AS NEEDED
111	WORKROOM	CPT-1.3'	WB	P-3	P-2.3"	P-2	P-2	ACT	-	SS-2	PLUM-1.2"	INSTALL RANDOM MIX OF CPT-1 (50%) AND CPT-3 (50%) **PLUM-1 SHALL BE USED FOR BASE CABINETS. PLUM-2 SHALL BE USED FOR UPPER CABINETS **REF WALL FINISH PLAN FOR EXACT EXTENT
112	OFFICE	CPT-1	WB	P-2	P-2	P-2	P-2	ACT	-	-	-	REF WALL FINISH PLAN FOR EXACT EXTENT
113	OFFICE	CPT-1	WB	P-2	P-2	P-2	P-2	ACT	-	-	-	REF WALL FINISH PLAN FOR EXACT EXTENT
114	PROGRAM ROOM	FRT-1.2'	WB	P-2	P-2	P-2	P-2	ACTEXP WD	P-1	SS-2	PLUM-4	INSTALL RANDOM MIX OF FRT-1 (75%) AND FRT-2 (25%)
115	EARLY COLLECTION	CPT-4	WB	P-3	P-4"	-	P-2.3"	ACT	-	SS-1	-	REF FLOOR FINISH PLAN FOR EXACT EXTENT OF MATERIALS **REF WALL FINISH PLAN FOR EXACT EXTENT. EXPOSED BRCA SHALL NOT BE PAINTED. WOOD COLUMNS SHALL NOT BE PAINTED.
116	NURSING	FRT-1	WB	P-2	P-2	P-2	P-2	ACT	-	SS-2	PLUM-1	REF FLOOR FINISH PLAN FOR EXACT EXTENT OF MATERIALS **REF WALL FINISH PLAN FOR EXACT EXTENT. EXPOSED BRCA SHALL NOT BE PAINTED. WOOD COLUMNS SHALL NOT BE PAINTED.
118	JUVENILE COLLECTION	CPT-4	WB	P-3	P-2.3"	-	P-2.3"	ACT	-	SS-1	-	REF FLOOR FINISH PLAN FOR EXACT EXTENT OF MATERIALS **REF WALL FINISH PLAN FOR EXACT EXTENT. EXPOSED BRCA SHALL NOT BE PAINTED. WOOD COLUMNS SHALL NOT BE PAINTED.
119	JUVENILE ROOM	CPT-1.3'	WB	P-2	P-2	P-2	P-2	ACTEXP WD	P-1	-	-	INSTALL RANDOM MIX OF CPT-1 (50%) AND CPT-3 (50%)
122	CIRCULATION / LOUNGE	CPT-1.2'	WB	P-2.3"	P-2.3"	P-2.3"	P-2.3"	ACTEXP WD	P-3	-	-	REF FLOOR FINISH PLAN FOR EXACT EXTENT OF MATERIALS **REF TYPICAL PAINT DETAIL FOR LIBRARY ON WALL FINISH PLAN
122A	CIRC. DESK	CPT-1	WB	-	-	-	P-2.3"	ACT	-	SS-1	WS-1 SS-1	REF MILLWORK VIEWS FOR LOCATION OF EACH FINISH TYPE **REF TYPICAL PAINT DETAIL FOR LIBRARY ON WALL FINISH PLAN
123	YOUNG ADULT ROOM	CPT-1.4'	WB	P-2	P-3	P-2	P-2	ACTEXP WD	P-3	-	-	INSTALL RANDOM MIX OF CPT-1 (50%) AND CPT-4 (50%)
124	CORRIDOR	CPT-1	WB	P-2.3'	P-2.3'	P-2.3'	P-2.3'	EXP WD	P-3	-	-	REF PAINT TYPICAL DETAIL FOR LIBRARY ON WALL FINISH PLAN
125	THE HUB	LVT-1	WB	P-2	P-2.3'	P-2	P-2	ACTEXP WD	P-1	-	-	REF WALL FINISH PLAN FOR EXACT EXTENT
126	MEET SPACE	LVT-1	WB	P-2	P-2	P-2	P-2	ACTEXP WD	P-1	-	-	REF WALL FINISH PLAN FOR EXACT EXTENT

WALL ORIENTATION BASED ON PLAN NORTH

FINISHES AND MATERIALS SCHEDULE									
MARK	MANUFACTURER	PATTERN / ITEM NO	COLOR	SIZE	FINISH	INSTALLATION METHOD	NOTES	CONTACT	
06 41 00 ARCHITECTURAL WOOD CASEWORK									
PLAM-1	WILSONART	STANDARD HPL	STEEL MESH (4879)	-	FINE VELVET FINISH (58)	-	-	MELISSA KATES: 803-238-3813 MKATES@ALPINESALESINC.COM	
PLAM-2	WILSONART	STANDARD HPL	FASHION GREY (2381)	-	MATTE FINISH (60)	-	-	MELISSA KATES: 803-238-3813 MKATES@ALPINESALESINC.COM	
09 30 00 CERAMIC TILING									
CT-1	MILESTONE	HERITAGE	SILVER	12" X 24" X 8MM	MATTE	1/8 OFFSET	GROUT: LATOCRETE SPECTRA LOCK 200G, COLOR: 78 STERLING SILVER. GROUT THICKNESS: 1/8"	KIMBERLY GRAY: 803-319-7476 KIMBERLY@PALMETTOTILE.COM	
CT-2	MILESTONE	HERITAGE	WHITE	12" X 24" X 8MM	MATTE	REF INTERIOR ELEVATION FOR PATTERN	GROUT: LATOCRETE SPECTRA LOCK 200G, COLOR: 78 STERLING SILVER. GROUT THICKNESS: 1/8"	KIMBERLY GRAY: 803-319-7476 KIMBERLY@PALMETTOTILE.COM	
TR-1	SCHLUTER	DILEX-AHK	SATIN ANODIZED ALUMINUM (AE)	-	-	-	TRANSITION BETWEEN WALL TILE AND FLOOR TILE	JOE TRUNCIELLO: 704-617-9248 JTRUNCIELLO@SCHLUTER.COM	
TR-2	SCHLUTER	DESIGNBASE-SL	BRUSHED STAINLESS STEEL (EB)	4.38" H	-	-	-	JOE TRUNCIELLO: 704-617-9248 JTRUNCIELLO@SCHLUTER.COM	
TR3-3	SCHLUTER	RENO-UJ	SATIN ANODIZED ALUMINUM (AE)	-	-	-	CT TO EXP PWD	JOE TRUNCIELLO: 704-617-9248 JTRUNCIELLO@SCHLUTER.COM	
09 85 10 RESILIENT TILE FLOORING									
FRT-1	FORBO	FLOTEK PLANKS METRO	GREY (948006)	25CM X 100CM	-	VERTICAL ASHLAR	-	JOHN ROBERT FOSTER: 803-403-4448 JOHN.FOSTER@FORBO.COM	
FRT-2	FORBO	FLOTEK PLANKS METRO	CITRUS (948019)	25CM X 100CM	-	VERTICAL ASHLAR	-	JOHN ROBERT FOSTER: 803-403-4448 JOHN.FOSTER@FORBO.COM	
LVT-1	MILLIKEN	NATURAL'S LOOSE LAY TANGIBLE	DAWN	9" X 60" X 5MM	-	VERTICAL ASHLAR	-	HEIDI BURMEISTER: 704-661-1078 HEIDI.BURMEISTER@MILLIKEN.COM	
RS-1	TARKETT	BASEWORKS TS RUBBER BASE WITH TOE	CHARCOAL (20)	6" X 100' COL	-	-	-	ANA OMEO: 704-422-8711 ANA.OMEO@FISHMAN.COM	
TRS-1	TARKETT	ELM LINE TRANSITION	CHARCOAL (20)	-	-	-	CPT TO EXP PWD	ANA OMEO: 704-422-8711 ANA.OMEO@FISHMAN.COM	
TRS-2	TARKETT	ELM LINE TRANSITION	CHARCOAL (20)	-	-	-	CPT TO ETR	ANA OMEO: 704-422-8711 ANA.OMEO@FISHMAN.COM	
09 85 13 TILE CARPETING									
CPT-1	MILLIKEN	EDGE LIT	MERCURY	25CM X 100CM	INTEGRAL CUSHION BACKING	VERTICAL ASHLAR	-	HEIDI BURMEISTER: 704-661-1078 HEIDI.BURMEISTER@MILLIKEN.COM	
CPT-2	MILLIKEN	EDGE LIT	BLACKLIGHT	1M X 1M	INTEGRAL CUSHION BACKING	MONOLITHIC REF FLOOR FINISH PLAN	-	HEIDI BURMEISTER: 704-661-1078 HEIDI.BURMEISTER@MILLIKEN.COM	
CPT-3	MILLIKEN	EDGE LIT	BLACKLIGHT	25CM X 100CM	INTEGRAL CUSHION BACKING	VERTICAL ASHLAR	-	HEIDI BURMEISTER: 704-661-1078 HEIDI.BURMEISTER@MILLIKEN.COM	
CPT-4	MILLIKEN	EDGE LIT	INCANDESCENT	25CM X 100CM	INTEGRAL CUSHION BACKING	VERTICAL ASHLAR	-	HEIDI BURMEISTER: 704-661-1078 HEIDI.BURMEISTER@MILLIKEN.COM	
WOF-1	PATCRAFT	MOVING	CORRIDOR	24" X 24"	-	MONOLITHIC	-	JORDAN WHITE: 803-241-4014 JORDAN.WHITE@PATCRAFT.COM	
09 91 21 INTERIOR PAINTING									
BP-2	PPG	PIIT GLAZE WB ACRYLIC EPOXY	TORNADO (1039-2)	-	SEMI-GLOSS	BESTROOM NEUTRAL	-	STUART S. BROWN: 803-267-0287 SSBROWN@PPG.COM	
BP-1	PPG	DIAMOND 350 INTERIOR LATEX	COMMERCIAL WHITE (1025-1)	-	FLAT	CEILING WHITE	-	STUART S. BROWN: 803-267-0287 SSBROWN@PPG.COM	
P-2	PPG	DIAMOND 350 INTERIOR LATEX	TORNADO (1039-2)	-	EGGSHELL	FELD NEUTRAL	-	STUART S. BROWN: 803-267-0287 SSBROWN@PPG.COM	
P-3	PPG	DIAMOND 350 INTERIOR LATEX	GRAY STONE (1039-4)	-	FLA EGG SHELL	DARK NEUTRAL	FLAT WHEN USED ON CEILING	STUART S. BROWN: 803-267-0287 SSBROWN@PPG.COM	
P-4	PPG	DIAMOND 350 INTERIOR LATEX	LIME GREEN (1222-5)	-	EGGSHELL	COOL ACCENT	-	STUART S. BROWN: 803-267-0287 SSBROWN@PPG.COM	
P-5	PPG	DIAMOND 350 INTERIOR LATEX	ADVENTURE (1161-6)	-	EGGSHELL	COOL ACCENT	-	STUART S. BROWN: 803-267-0287 SSBROWN@PPG.COM	
P-6	PPG	DIAMOND 350 INTERIOR LATEX	KNIGHTS ARMOR (1001-4)	-	SEMI-GLOSS	EXISTING AND NEW WOOD TRIM AND BASES AND HM DOOR TRIM	-	STUART S. BROWN: 803-267-0287 SSBROWN@PPG.COM	
P-7	PPG	DIAMOND 350 INTERIOR LATEX	CANYON BLUE (1155-6)	-	EGGSHELL	COOL ACCENT	-	STUART S. BROWN: 803-267-0287 SSBROWN@PPG.COM	
P-8	PPG	DIAMOND 350 INTERIOR LATEX	BLUE FORD (1163-6)	-	EGGSHELL	COOL ACCENT	-	STUART S. BROWN: 803-267-0287 SSBROWN@PPG.COM	
12 36 00 COUNTERTOPS									
SS-1	DUPONT	CORIAN SOLID SURFACE	ANTARCTICA	1/2" THICK	-	SEE EDGE	-	BARBARA DAVIS: 704-301-8078 BDAVIS@CHRRGGG.COM	
SS-2	DUPONT	CORIAN SOLID SURFACE	PEARL GRAY	1/2" THICK	-	SEE EDGE	-	BARBARA DAVIS: 704-301-8078 BDAVIS@CHRRGGG.COM	
WOOD STAIN									
WS-1	CUSTOM STAIN TO MATCH PLAM	BASIS OF DESIGN - FORMICA	CHESTNUT WOOD-L	-	-	-	FINISH COLOR FOR WOOD ENCASED OPENINGS AND WOOD DOORS	-	-


EXISTING FINISH REFURBISHMENT NOTES

- TO SUPPLEMENT ATTIC STOCK. PRESERVE EXISTING CARPET TILES DEMOED ON FIRST LEVEL AND PREP THE CARPET BACKING FOR RE-INSTALLATION TO PATCH AREAS INDICATED ON SECOND LEVEL FLOOR FINISH PLAN
- PRESERVE EXISTING WINDOW TREATMENTS. CLEAN AND REINSTALL
- EXISTING TO REMAIN FLOORING SHALL RECEIVE DEEP CLEANING
- PRESERVE EXISTING WOOD BASE, CLEAN AND PREP TO RECEIVE PAINT
- PRESERVE AND STORE DEMOED EXISTING WOODWORK

GENERAL FINISH NOTES

- REF FINISHES AND MATERIAL SCHEDULE FOR MATERIAL AND COLOR INFORMATION AND ROOM FINISH SCHEDULES FOR SELECTIONS. ROOM FINISH SCHEDULES ARE BASED ON PLAN NORTH. REF FLOOR AND WALL FINISH PLAN FOR EXTENT OF FINISH ACCENT LOCATIONS AND PATTERNS
- ALL ACCESS PANELS, SPRINKLER HEADS, AND OTHER SIMILAR ITEMS SHALL BE PAINTED TO MATCH THE COLOR OF THE SURROUNDING WALL OR CEILING UNLESS PRE-FINISHED BY MANUFACTURER OR UNO
- REF RCP FOR MATERIAL EXTENT AND TYPES. REF 'CEILING' COLUMN OF ROOM FINISH SCHEDULE FOR APPLICABLE CEILING, SOFFIT, AND BULKHEAD FINISHES
- CONTRACTOR SHALL NOTIFY ARCHITECT OF ANY EXPOSED SURFACE NOT HAVING A FINISH SPECIFIED BEFORE SUBMITTING B.D.
- IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO CHECK LEAD TIMES ON FINISHES IN ORDER TO AVOID DELAYING WORK.

Order Plans @ www.LDOnline.com



AIKEN COUNTY
AIKEN PUBLIC LIBRARY & NORTH WING
RENOVATION
314 CHESTERFIELD ST. AIKEN, SC

SHEET ISSUE	NO.	DATE	DESCRIPTION	BY
B	03/06/2020	DD SET		
D	04/10/2020	PERMIT SET		
E	07/02/2020	ISSUED FOR BIDS		

ISSUED FOR BIDS 07/02/2020
PRINCIPAL IN CHARGE: DRM
PROJECT ARCHITECT: TA
DRAWN BY: MNW
SHEET TITLE: FINISHES & MATERIALS SCHEDULE

SHEET NO. 015477.01

ID800