

1 DEMOLITION PLAN
AD102
1/4" = 1'-0"

- GENERAL DEMOLITION NOTES**
- A. THE CONTRACTOR SHALL CHECK AND VERIFY EXISTING FIELD CONDITIONS AND DIMENSIONS BEFORE STARTING WORK.
 - B. SEE PLUMBING, MECHANICAL, ELECTRICAL AND FIRE PROTECTION DRAWINGS FOR DEMOLITION OF THOSE ITEMS.
 - C. PROVIDE TEMPORARY SHORING AND BRACING AS REQUIRED FOR REMOVAL OF EXISTING MASONRY, LINTELS, AND LOAD BEARING PARTITIONS FOR INSTALLATION OF NEW WORK.
 - D. REMOVE ALL SIGNAGE, TACKBOARDS, MARKERBOARDS, TOILET PARTITIONS, TOILET ACCESSORIES, CABINETS, COUNTERS, VANITIES, SHELVING, FIRE EXTINGUISHERS, FIRE EXTINGUISHER CABINETS, ELECTRIC DRINKING FOUNTAINS, AND SIMILAR MISCELLANEOUS ITEMS THROUGHOUT WORK AREA, UNLESS SUCH ITEMS ARE INDICATED TO REMAIN.
 - E. REMOVE ALL ITEMS SCHEDULED FOR REMOVAL OR REQUIRED TO BE REMOVED. PATCH FLOORS, WALLS, AND CEILINGS TO MATCH EXISTING SURFACES WHERE EXISTING SURFACES ARE TO BE EXPOSED-TO-VIEW IN NEW WORK.
 - F. ALL EXISTING SURFACES TO REMAIN THAT ARE DAMAGED DURING DEMOLITION OR NEW CONSTRUCTION WORK SHALL BE REPAIRED TO MATCH EXISTING ADJACENT SURFACES.
 - G. ALL SURFACES TO HAVE FINISHES OR FINISH MATERIAL REMOVED AND NEW FINISHES OR FINISH MATERIALS INSTALLED SHALL BE PROPERLY CLEANED OF SOIL, ADHESIVES OR OTHER MATERIALS WHICH MIGHT IMPAIR APPLICATION OF NEW FINISHES AND/OR NEW FINISH MATERIALS.
 - H. ANY ITEM NOT INDICATED TO BE REMOVED, BUT INFERRED TO BE REMOVED BY REQUIREMENTS OF NEW CONSTRUCTION, SHALL BE REMOVED AS IF NOTED TO BE REMOVED.


- DEMOLITION LEGEND**
- EXISTING DOOR/FRAME TO BE REMOVED
 - EXISTING PARTITION TO BE REMOVED
 - EXISTING CHAINLINK FENCE TO BE REMOVED
 - FLOOR SLAB OR ROOF COVERING TO BE REMOVED
 - TEMPORARY CONSTRUCTION PARTITION
 - DEMOLITION KEY NOTE

DEMOLITION KEYNOTES	
Number	DESCRIPTION
1	REMOVE EXISTING RESILIENT SHEET FLOORING INCLUDING ADHESIVE DOWN TO CONC. FLOOR. PREPARE FLOOR TO RECEIVE NEW FINISHES
2	REMOVE EXISTING LAY-IN CEILING IN ITS ENTIRETY INCLUDING GRID, PANELS, AND SUPPORTS
3	REMOVE EXISTING RUBBER BASE AND ADHESIVE DOWN TO GYP. BD. SUBSTRATE. PREPARE WALL TO RECEIVE NEW BASE
4	REMOVE EXISTING MET. STUD AND GYPSUM BOARD WALL
5	REMOVE EXISTING DOOR, FRAME, AND HARDWARE. TURN OVER DOOR HARDWARE TO OWNER
6	REMOVE EXISTING HOLLOW METAL FRAME AND GLAZING
7	REMOVE EXISTING TRANSACTION COUNTER
8	REMOVE EXISTING RAISED ACCESS FLOORING, FRAMING, AND SUPPORTS
9	REMOVE EXISTING WOOD FRAMED STAIR AND SUPPORTS IN ITS ENTIRETY
10	REMOVE EXISTING TOILET ACCESSORIES INCLUDING GRAB BARS, MIRRORS, AND DISPENSERS
11	REMOVE EXISTING HORIZONTAL LOUVER BLINDS

Order Plans @ www.LDILine.com

Biloba Architecture, PLLC
 8801 JM Keynes Drive
 Suite 365
 Charlotte, NC 28262
 704.248.2022
 www.biloba.co

Mechanical and Electrical Engineer
McKnight Smith Ward Griffin Engineers
 4223 South Boulevard
 Charlotte, NC 28209
 704.527.2112
 NC Certificate of Licensure: F-0595



Drawn CADD
 Checked IWP
 Date August 7, 2020
 Revisions

Copyright 2020. All rights reserved. Printed or electronic drawings and documentation may not be reproduced in any form without written permission from Biloba Architecture, PLLC.

Brown Hall Renovation
 Laurel Street, Brown Hall
 Greensboro, NC 27411
 SCO ID No. 20-22082-01A

Project Number 106
 Title
Demolition Plan

Sheet
AD102
 Plate of