

1 PLUMBING PLAN - DWV, WASTE & VENT
 1/8" = 1'-0"

GENERAL NOTES

- CONTRACTOR IS RESPONSIBLE FOR HAVING A THOROUGH KNOWLEDGE OF ALL DRAWINGS, SPECIFICATIONS AND EXISTING CONDITIONS FOR BIDDING PURPOSES. FAILURE TO ACQUAINT THEMSELVES WITH THIS KNOWLEDGE DOES NOT RELIEVE THE RESPONSIBILITY OF PERFORMING THEIR WORK.
- NOT ALL EXISTING EQUIPMENT, PIPING, DUCTWORK, ETC. IS SHOWN ON THE PLANS. ALL EXISTING EQUIPMENT AND PIPING SHOWN DOES NOT REFLECT ALL OFFSETS, LENGTHS AND LOCATIONS. CONTRACTOR SHALL FIELD VERIFY ALL EQUIPMENT AND PIPING TO BE REMOVED AND DISCONNECTED PRIOR TO BID.
- FIELD VERIFY LOCATIONS AND QUANTITY OF ALL EXISTING EQUIPMENT, FIXTURES, DUCTWORK AND PIPING NECESSARY TO COMPLETE SCOPE OF WORK.
- CONCRETE CUTS SHALL BE STRAIGHT AND CLEAN. REPLACE REBAR WITH CONCRETE PATCH AND SMOOTH WITH ADJACENT.
- WASTE & VENT PIPING BELOW GRADE AND THRU FLOOR SHALL BE MINIMUM 3\"/>

PLUMBING SANITARY KEYNOTES


- CONNECT NEW 6\"/>

Order Plans @ WWW.LDDLINE.COM

PROTOTYPE TEMPLATE:
NORTHLAKE
 v.2020.1.08.TKD

PROJECT INFORMATION:

WHEEL TIRE KINGDOM.
 STORE # 945
 10520 COLONIAL BLVD
 FT MEYERS, LEE COUNTY, FLORIDA



PROJECT NO.: 2020-0095
 DRAWN BY:
 CHECKED BY:

ISSUE	DATE
PERMIT PLAN REVIEW	11-AUG-2020

REVISION	DATE

SHEET TITLE:
PLUMBING PLAN

SHEET NUMBER:
P-1