



1 THEATER - LEVEL 02 FLOOR PLAN
SCALE: 1/8" = 1'-0"

Order Plans @

WWW.LDILine.com

NOTES:

ALL CONTROL RECEPTACLES RUN TO JUNCTION BOX ABOVE THE NEW EQUIPMENT RACK (IN LIGHTING ROOM #165) VIA 3/4" CONDUIT UNLESS OTHERWISE NOTED.

ALL PERFORMANCE LIGHTING CIRCUITS TERMINATE AT THE PERFORMANCE LIGHTING MOTORIZED BREAKER PANEL (IN LIGHTING ROOM #165). WIRE AND CONDUIT SIZE AS PER ENGINEERING DOCUMENTS. EACH CIRCUIT REQUIRES A DEDICATED NEUTRAL WIRE. ALL CIRCUITS ARE FULLY RATED.

"GANG" BACK BOXES ARE A MINIMUM OF 3" DEEP.

SEE ELECTRICAL DOCUMENTS FOR ENGINEERING INFORMATION.

Notes:

- Conduit 3/4" / 21mm unless otherwise noted.
- Electrical Contractor supplied backboxes 2 1/2" deep unless otherwise noted.
- Field ganged gangable boxes are not acceptable.
- Where 1 gang flush mounted back boxes are required employ 2 gang back boxes with reducer rings.
- For surface mount conditions employ cast boxes.
- Control wire and cable is provided by Performance Lighting Control (PLC) contractor.
- Wire and cable carrying more than 100V provided by Electrical Contractor including all terminations.
- Power from the breakers to the electronics racks is provided by Electrical Contractor and terminated in the electronics racks by PLC contractor.
- Power in the electronics racks is provided by PLC contractor.
- Dimmer racks, relay panels, motorized breaker panels and company switches are supplied by PLC and installed by Electrical Contractor.
- Back boxes are supplied by PLC contractor unless otherwise noted, except of "Gang" boxes which are supplied by the Electrical Contractor. All back boxes are installed by the Electrical Contractor.
- Conduit with pull lines is provided by Electrical Contractor.
- Control faceplates are provided by PLC contractor. Faceplates with terminations above 100V are supplied by PLC contractor to Electrical Contractor for installation by Electrical Contractor.

FLEISCHMANGARCIA

TAMPA OFFICE: 34 HYDE PARK AVENUE, SUITE 300, TAMPA, FL 33606, PHONE (813) 291-4400, FAX (813) 291-4400
 HUNTERS VILLAGE OFFICE: 8550 HUNTERS VILLAGE RD., TAMPA, FL 33647, PHONE (813) 752-8888, FAX (813) 752-8888
 MIAMI OFFICE: 1300 N.W. 107th AVE., SUITE 100, MIAMI, FL 33187, PHONE (305) 444-4444, FAX (305) 444-4444
 MIAMI OFFICE: 1300 N.W. 107th AVE., SUITE 100, MIAMI, FL 33187, PHONE (305) 444-4444, FAX (305) 444-4444
 MIAMI OFFICE: 1300 N.W. 107th AVE., SUITE 100, MIAMI, FL 33187, PHONE (305) 444-4444, FAX (305) 444-4444
 MIAMI OFFICE: 1300 N.W. 107th AVE., SUITE 100, MIAMI, FL 33187, PHONE (305) 444-4444, FAX (305) 444-4444

**HILLSBOROUGH COUNTY
NEW TAMPA PERFORMING ARTS
CENTER**

8550 HUNTERS VILLAGE RD.
TAMPA FL, 33647

THIS DESIGN AND DRAWING IS THE SOLE PROPERTY OF FLEISCHMANGARCIA. NO PART OF THIS WORK MAY BE REPRODUCED WITHOUT PRIOR WRITTEN PERMISSION FROM FLEISCHMANGARCIA.

I CERTIFY TO THE BEST OF MY KNOWLEDGE THAT THESE DRAWINGS COMPLY WITH ALL RELEVANT BUILDING CODES.

PERMIT SET

FGA PROJECT NUMBER
19048

ISSUE DATE
04-15-2020

| NO. | DATE | NOTES |
|-----|------|-------|
| | | |
| | | |
| | | |

SHEET NAME
**PERFORMANCE
LIGHTING
SYSTEM - 2FP**

SHEET NUMBER
TP 1.02