



1 RIGGING FLOOR PLAN
SCALE: 1/8" = 1'-0"

LINESET DRAPERY	DESCRIPTION FINISHED DIMENSIONS	OVERALL LENGTH	ARBOR COUNTERWEIGHT WIDTH	ARBOR LIVE CAPACITY (LBS)	NUMBER OF LIFT LINES	COMMENTS
1	MAIN BORDER	7'-0"	6	1550	6	
2	MAIN CURTAIN	7'-0"	6	1550	6	
-	OPEN					
3	ELECTRICS #1	7'-0"	6	1550	6	PROVIDE CABLE MANAGEMENT AND AN ADDITIONAL LIFT LINE FOR CABLE CRADLE. COORDINATE WITH PERFORMANCE LTG CONTRACTOR AND DIV. 26.
-	OPEN					
4	GENERAL PURPOSE	7'-0"	6	1550	6	
5	GENERAL PURPOSE	7'-0"	6	1550	6	
6	BORDER #1	7'-0"	6	1550	6	
7	MID-STAGE TRAVELER	7'-0"	6	1550	6	
8	GENERAL PURPOSE	7'-0"	6	1550	6	
9	ELECTRICS #2	7'-0"	6	1550	6	PROVIDE CABLE MANAGEMENT AND AN ADDITIONAL LIFT LINE FOR CABLE CRADLE. COORDINATE WITH PERFORMANCE LTG CONTRACTOR AND DIV. 26.
10	GENERAL PURPOSE	7'-0"	6	1550	6	
11	GENERAL PURPOSE	7'-0"	6	1550	6	
12	BORDER #2	7'-0"	6	1550	6	
13	LEGS #1	7'-0"	6	1550	6	
14	ELECTRICS #3	7'-0"	6	1550	6	PROVIDE CABLE MANAGEMENT AND AN ADDITIONAL LIFT LINE FOR CABLE CRADLE. COORDINATE WITH PERFORMANCE LTG CONTRACTOR AND DIV. 26.
15	GENERAL PURPOSE	7'-0"	6	1550	6	MOUNT HEAVY DUTY DRAPERY TRACK BELOW PIPE BATTEN.
16	BORDER #3	7'-0"	6	1550	6	
17	LEGS #2	7'-0"	6	1550	6	
18	ELECTRICS #4	7'-0"	6	1550	6	PROVIDE CABLE MANAGEMENT AND AN ADDITIONAL LIFT LINE FOR CABLE CRADLE. COORDINATE WITH PERFORMANCE LTG CONTRACTOR AND DIV. 26.
19	GENERAL PURPOSE	7'-0"	6	1550	6	
20	BORDER #4	7'-0"	6	1550	6	
21	LEGS #3	7'-0"	6	1550	6	
22	GENERAL PURPOSE	7'-0"	6	1550	6	
23	GENERAL PURPOSE	7'-0"	6	1550	6	
24	GENERAL PURPOSE	7'-0"	6	1550	6	
25	BORDER #5	7'-0"	6	1550	6	
26	LEGS #4	7'-0"	6	1550	6	
-	OPEN					
27	ELECTRICS #5	7'-0"	6	1550	6	PROVIDE CABLE MANAGEMENT AND AN ADDITIONAL LIFT LINE FOR CABLE CRADLE. COORDINATE WITH PERFORMANCE LTG CONTRACTOR AND DIV. 26.
-	OPEN					
28	SCRM	7'-0"	6	1550	6	TIE DRAPERY TO PIPE BATTEN
29	CYCLORAMA	7'-0"	6	1550	6	TIE DRAPERY TO PIPE BATTEN
30	BLACKOUT DRAPERY	7'-0"	6	1550	6	TIE DRAPERY TO PIPE BATTEN

2 RIGGING SCHEDULE
NO SCALE

NOTES:

1. EXPOSED ELEMENTS FINISHED IN FLAT BLACK (UNLESS NOTED OTHERWISE).
2. VERIFY FIELD CONDITIONS AND DIMENSIONS.
3. PROVIDE ALL FASTENERS WITH SELF LOCKING HARDWARE.

FLEISCHMANGARCIA
 TAMPA OFFICE
 3300 W. GULF BLVD., SUITE 100
 TAMPA, FLORIDA 33609
 PHONE: (813) 941-1888
 FAX: (813) 941-1888
 REGISTRATION NUMBER: PA 000123
 www.fleischmangarcia.com

**HILLSBOROUGH COUNTY
 NEW TAMPA PERFORMING ARTS
 CENTER**
 8550 HUNTERS VILLAGE RD.
 TAMPA, FL 33647

THIS DESIGN AND DRAWING IS THE SOLE PROPERTY OF FLEISCHMANGARCIA. NO PART OF THIS WORK MAY BE REPRODUCED WITHOUT PRIOR WRITTEN PERMISSION FROM FLEISCHMANGARCIA.

I CERTIFY TO THE BEST OF MY KNOWLEDGE THAT THESE DRAWINGS COMPLY WITH ALL RELEVANT BUILDING CODES

PERMIT SET

FGA PROJECT NUMBER
19048

ISSUE DATE
04-15-2020

REVISIONS		
NO	DATE	NOTES

SHEET NAME
**RIGGING &
 DRAPERIES
 1FP**

SHEET NUMBER
TR 1.01