



3 ELEVATION - MED. GAS EVACUATION PUMP STORAGE
1/2" = 1'-0"

EQUIPMENT GENERAL NOTES

- A. PER ADA GUIDELINES, AT LEAST 5% OF TOTAL LOCKERS TO BE ADA COMPLIANT (WHICH IS TO INCLUDE RECESSED PULL)
- B. GENERAL CONTRACTOR IS RESPONSIBLE FOR BLOCKING ONLY. COORDINATE WITH EQUIPMENT SUPPLIER.
- C. ALL WALL MOUNTED EQUIPMENT TO BE ANCHORED TO WALL. REFER TO EQUIPMENT SPECIFICATIONS FOR ANY BLOCKING REQUIREMENTS. NOTE: ALL WALL MOUNTED EXAM TABLES ARE TO RECEIVE FULL PANEL WOOD BLOCKING BETWEEN STUDS (2 BAYS WIDE).
- D. 1-1/2" STAINLESS STEEL CORNER & END GUARDS TO BE PROVIDED & INSTALLED BY G.C. ON ALL OUTSIDE CORNERS OF GYPSUM BOARD WALLS. LOCATE ABOVE WALL BASE, GUARD TO BE 48" HIGH. MFR: C3 ACROVYN, MODEL: CO SERIES, STYLE: CO-8. (NOTE: AT END WALL LOCATIONS, PROVIDE END WALL GUARD IN STAINLESS STEEL FINISH).
- E. G.C. TO PROVIDE W HANGERS (BOTTLE HOLDERS) FOR THE IV TRACK - GC PROVIDED; MFR: AIR NELSON, MODEL: TELESCOPING #400, CONTACT PH. NUMBER: (800) 377-6625; VISIT WEBSITE: www.airnelson.com/usa/iv-hangers.aspx; VERIFY QUANTITY WITH HOSPITAL.
- F. FOR EQUIPMENT / CASEWORK ELEVATION TAGS, REFER TO ARCHITECTURAL FLOOR PLAN FOR INFORMATION.
- L. AT EACH EYE WASH STATION, GENERAL CONTRACTOR TO HANG REQUIRED WALL SIGNAGE ABOVE SINK ON WALL.

EQUIPMENT WORK REQUIREMENTS

- A. GENERAL CONTRACTOR TO COORDINATE WITH HOSPITAL TO RESEARCH (EXISTING TO REMAIN) MED GAS OUTLETS AND THEIR PLUG-IN CONFIGURATION TO ENSURE ALL CONNECTIONS NEW & EXISTING ARE SAME TYPE.
- B. GENERAL CONTRACTOR TO COORDINATE RECEPTION DESK CASH DRAWER INSTALLATION WITH HOSPITAL.

EQUIPMENT PLAN KEYNOTES

- 01 MANUAL (NON MOTORIZED) WINDOW SHADES, BASIS OF DESIGN PRODUCT: MFG: MED-GUARD SYSTEMS, EUROVEL BASKET WEAVE SHADE/CLOTH; 5800 SERIES WITH VALANCE; SHADE COLOR: 5806 SILVER BIRCH; FACIA COLOR: ALABASTER; CONTACT: PAT KENDRICK, PHONE: 317.201.3397, EMAIL: pkendrick@msa.biz / www.medguard.com
- 02 PROVIDE "MOP & BROOM" HOLDER CLAMP ON WALL FOR HOSE (FROM HOSE REEL ABOVE), INSTALL AT 24" A.F.F. (SPECIFICATION WILL BE INCLUDED WITH HOSE REEL CUT SHEET, PROVIDED BY ARCHITECT).
- 03 G.C. TO PROVIDE AND INSTALL THE SUPERA MED VAC. UNITS (SCAVENGER ONLY). INSTALL ON NEW 30" WIDE MELAMINE FIXED SHELF OR MICROSHELF; REFER TO ELEVATION 314.1 FOR MFD.
- 04 GC PROVIDED TV WITH WALL MOUNT. HIDE ALL OUTLETS BEHIND TV. VERIFY MOUNTING HEIGHT AND ANGLE WITH HOSPITAL.

EQUIPMENT SCHEDULE

No.	Type	Furnished By Contractor	Installed By Contractor	Installed By Owner	Blockouts Required	Electrical Required	Water/Sewer Required	Data Required	Medical Gas Required	Comments
1-1.08	FIRE EXTINGUISHER - WALL MOUNTED	X	X							
1-1.09	DOG LEASH CLEAT - COMPACT	X	X							
1-1.22A	30" METRO SHELVING WALL MOUNTED - DOUBLE 12" DEP.	X	X							
COMMUNICATION, SECURITY & AV										
3-1.91	COMPUTER WORKSTATION	X	X	X	X	X				G.C. TO PROVIDE POWER AND DATA BOX & PULL STRING
3-1.98	COMPUTER WORKSTATION - WALL MTD	X	X	X	X	X				
3-2.01	TELEPHONE - WORKSURFACE	X	X	X	X	X				
3-2.02	TELEPHONE - WALL MOUNTED	X	X	X	X	X				
3-2.03	CREDIT CARD MACHINE	X	X	X	X	X				
3-4.01A	46" FLAT SCREEN TELEVISION WALL MOUNTED	X	X	X	X	X				G.C. TO PROVIDE WALL MOUNTING BRACKET, POWER AND DATA BOX, AND PULL STRING. COORDINATE EXACT LOCATION WITH HOSPITAL.
3-6.01A	LASER PRINTER - LARGE UNDER CABINET	X	X	X	X	X				
3-6.02	LABEL PRINTER	X	X	X	X	X				
3-6.05A	ELECTRICAL PANEL	X	X	X	X	X				12" WIDE
APPLIANCES										
4-7.02	REFRIGERATOR/TOP FREEZER - FULL SIZE	X	X	X	X	X				WATERLINE REQD. FOR ICEMAKER; G.C. TO HOOK UP
4-1.02A	FREEZER CHEST	X	X	X	X	X				
MEDICAL EQUIPMENT										
5-0.00	ELECTRIC TRANSPORT TABLE W/ DENT TRAY	X	X	X	X	X				
5-1.01B	FLOOR SCALE - WALL MOUNT	X	X	X	X	X				BATTERY OPERATED
5-1.03A	FELINE SCALE - MOUNTED	X	X	X	X	X				MHS 120 G.C. TO PROVIDE BLOCKING
5-1.03B	CONTROLLED SUBSTANCE CABINET - WALL SURF MTD	X	X	X	X	X				MHS 320 G.C. TO PROVIDE BLOCKING
5-1.10C	CONTROLLED SUBSTANCE CABINET - LARGE	X	X	X	X	X				
5-1.11	IV TRACK	X	X	X	X	X				G.C. TO PROVIDE IV HANGERS FOR EACH TRACK
5-1.12B	IV TRACK - 1/2"	X	X	X	X	X				G.C. TO PROVIDE (1) IV HANGER FOR EACH TRACK
5-1.13	DELIVERY SYSTEM ON CART	X	X	X	X	X				YETPRO 1000
5-1.14	MAX INSTRUMENT STAND	X	X	X	X	X				
5-1.15	MODE INSTRUMENT TABLE	X	X	X	X	X				
5-1.16	WARRANT WARMING COOLING THERAPY - BAIR HUGGERS	X	X	X	X	X				
2-1.85	KICK BUCKET	X	X	X	X	X				
5-1.93	RETRACTABLE POWER REEL	X	X	X	X	X				(TO BE ON GFJ OUTLET); MFR: APC GROUP; MODEL: MR-1015140; MED REEL - CLG MOUNTED; 10' 0" LENGTH
5-2.01A	SS FOLD UP WALL MOUNT EXAM TABLE	X	X	X	X	X				G.C. TO PROVIDE AND INSTALL WALL BUMPER, FULL HEIGHT BLOCKING REQUIRED.
5-2.02	SURGERY TABLE	X	X	X	X	X				
5-2.17C	MIDMARK MOBILE ANIMAL LIFT TABLE	X	X	X	X	X				G.C. TO PROVIDE BLOCKING
5-3.09	EXAM LIGHT - SINGLE SOLEIDIS	X	X	X	X	X				G.C. TO PROVIDE BLOCKING
5-3.11	SURGERY LIGHT - DOUBLE GEN 3 GALAXY	X	X	X	X	X				WEIGHT OF FIXTURE 231 LBS, G.C. TO PROVIDE BLOCKING
5-4.01	CENTRIFUGE	X	X	X	X	X				
5-4.10	MICROSCOPE	X	X	X	X	X				
5-4.20	SNAP PRO ANALYZER	X	X	X	X	X				
5-4.22	LASERCYTE HEMATOLOGY ANALYZER	X	X	X	X	X				
5-4.28	CATALYST ONE CHEMISTRY ANALYZER	X	X	X	X	X				
5-6.01A	ANESTHESIA MACHINE ON CART	X	X	X	X	X				G.C. TO PROVIDE HOSE TO 6" AFF
5-6.06	O2 DROP - CEILING	X	X	X	X	X				G.C. TO PROVIDE HOSE TO 6" AFF
5-6.08	WASTE EVACUATION PUMP - EVC3000	X	X	X	X	X				
5-6.18A	MODEL 201W GAS CYLINDER STORAGE RACKS	X	X	X	X	X				
5-6.30	OXYGEN TANK	X	X	X	X	X				
5-6.10	AUTOClave - ON COUNTER	X	X	X	X	X				
5-6.16B	ULTRASONIC CLEANER 2800 - 75 Gallon	X	X	X	X	X				
5-7.01L	TUB TABLE MIDMARK - 60 INCH - LH	X	X	X	X	X				FINAL PLUMBING BY G.C.
5-8.10	DIPHTHALMOSCOPE/OTOSCOPE WALL MNTD.	X	X	X	X	X				
PLUMBING										
6-1.08	X RAY VIEWER - SINGLE RECESSED	X	X	X	X	X				
6-1.07	WALL MOUNT XRAY MONITOR & KEYBOARD	X	X	X	X	X				
6-1.08B	DIGITAL DENTAL X RAY WALL MTD PROTECTA	X	X	X	X	X				
6-1.11A	DIGITAL X RAY MACHINE - SELECT	X	X	X	X	X				REFER TO SIGNAGE PLAN FOR REQUIRED VINYL SIGNAGE
6-1.15	LEAD GLOVE RACK	X	X	X	X	X				
7-1.30	VSSI CAGE 30"W x 30"H	X	X	X	X	X				G.C. TO PROVIDE CURB
7-1.31	VSSI CAGE 36"W x 30"H	X	X	X	X	X				G.C. TO PROVIDE CURB
7-1.32	VSSI CAGE 48"W x 30"H	X	X	X	X	X				G.C. TO PROVIDE CURB
7-1.33	VSSI CAGE 24"W x 30"H	X	X	X	X	X				
7-2.20	VSSI RUN 36x60	X	X	X	X	X				60" DEEP
7-2.21	VSSI RUN 48x60	X	X	X	X	X				60" DEEP
PLUMBING										
9-1.33A	MOP HANGER SHELF 2' L	X	X	X	X	X				
9-1.01	PAPER TOWEL DISPENSER - PETITE, WALL MOUNTED	X	X	X	X	X				
9-1.04	PAPER TOWEL DISPENSER - RESTROOM - WALL MOUNTED	X	X	X	X	X				
9-1.05	RESTROOM TOILET PAPER DISPENSER	X	X	X	X	X				
9-1.06A	SOAP DISPENSER - WALL MOUNTED	X	X	X	X	X				
9-1.06	RESTROOM SANITARY NAPKIN DISPOSAL RECEPTACLE	X	X	X	X	X				
9-1.10	RESTROOM ADA GRAB BAR	X	X	X	X	X				
9-1.12	RESTROOM ADA GRAB BAR 42"	X	X	X	X	X				
9-1.13	ADA GRAB BAR VERTICAL	X	X	X	X	X				
9-1.28	RESTROOM WALL MIRROR 24" W X 36" H	X	X	X	X	X				
9-1.29	TRASH CAN	X	X	X	X	X				MFR: ACCU BRAND PRODUCTS, MODEL: #018A400 DURA LOOP SADDLE, WITH APPROPRIATE LENGTH, HEAVY DUTY, KINK-FREE GARDEN HOSE
9-6.01	HOSE AND RACK	X	X	X	X	X				

PLUMBING AND UTILITY EQUIPMENT

No.	Type	Furnished By Contractor	Installed By Contractor	Installed By Owner	Blockouts Required	Electrical Required	Water/Sewer Required	Comments
PLUMBING								
7-2.0	SCRUB SINK - SINGLE ELKAY	X	X	X	X	X		
9-1.02	EXTRA LARGE SINK DOUBLE BOWL, S-2	X	X	X	X	X		
9-1.03	BAR SINK (EXAM SINK) S-3	X	X	X	X	X		
9-1.11	WALL MOUNTED SINK L-1	X	X	X	X	X		
9-1.12	WALL MOUNTED SINK S-5	X	X	X	X	X		
9-1.31	MOP SINK MSB-1	X	X	X	X	X		
9-1.40	EEW - EYE WASH - S250 STRINGRAY	X	X	X	X	X		
9-3.00	RUN FLOOR DRAIN	X	X	X	X	X		
9-4.10	A.D.A. TOILET - TANK TYPE	X	X	X	X	X		
9-6.01	COMMERCIAL HOSE BIBB	X	X	X	X	X		

