


GENERAL DEMOLITION NOTES

1. CONTRACTOR SHALL VISIT THE SITE TO VERIFY EXISTING CONDITIONS PRIOR TO SUBMISSION OF BID. NO ADDITIONAL COMPENSATION SHALL BE CONSIDERED FOR FAILURE TO OBSERVE THIS REQUIREMENT.
2. CONTRACTOR SHALL DISCONNECT AND REMOVE ALL ELECTRICAL WIRING AND EQUIPMENT AS REQUIRED WITHIN ALL AREAS TO BE RENOVATED. THIS SHALL INCLUDE BUT NOT BE LIMITED TO FIXTURES, DEVICES, OUTLETS, SWITCHES, RECEPTACLES, STARTERS, DISCONNECTS, PANELS, FEEDERS, ETC.
3. CONTRACTOR SHALL DISCONNECT AND REMOVE ALL EXISTING CIRCUITS TO MECHANICAL EQUIPMENT BEING REMOVED. REFER TO ALL MECHANICAL DEMOLITION DRAWINGS OR NOTES.
4. WHERE ELECTRICAL ITEMS ARE REMOVED, ALL BRANCH DEVICE'S WIRING SHALL BE REMOVED BACK TO PANEL SERVING THE EQUIPMENT. WHERE CIRCUITS SERVE ADDITIONAL DEVICES OR EQUIPMENT REMAINING, WIRING SHALL BE REMOVED BACK TO THE NEAREST ACTIVE JUNCTION BOX.
5. CONTRACTOR SHALL MAINTAIN CONTINUITY OF EXISTING CIRCUITS THAT ARE TO REMAIN IN OPERATION AND SCHEDULE FOR REFEEDING FROM NEW PANELS. FORWARD FINDINGS TO ENGINEER FOR REVIEW AND CORRECTION.
6. ALL UNUSED CIRCUITS REMAINING AFTER REMOVALS SHALL BECOME SPARE IN PANELS, LABELED AS SPARE, AND SWITCHED TO THE OFF POSITION.
7. CONTRACTOR SHALL REFER TO ARCHITECTURAL DEMOLITION DRAWING FOR ADDITIONAL INFORMATION AND SCOPE OF DEMOLITION.
8. ALL MATERIALS AND EQUIPMENT REMOVED SHALL BE DISPOSED OF AS DIRECTED BY THE OWNER OR THE ARCHITECT.
9. ALL EMPTY CONDUITS MUST HAVE PULLWIRES AND BE TAGGED PROPERLY.
10. ELECTRICAL CONTRACTOR SHALL TIE BACK ALL LOOSE WIRING (INCLUDING LOW VOLTAGE) IN AN ORDERLY FASHION.
11. CONTRACTOR SHALL VERIFY ALL EXISTING CIRCUITS AND RELABEL PANEL SCHEDULED IN FIELD AS REQUIRED.
12. CONTRACTOR TO VERIFY ALL EXISTING PANEL LOADING IN FIELD AS REQUIRED PRIOR TO ANY NEW WORK.

CEILING DEMOLITION LEGEND



CEILING FIXTURE SCHEDULE

SYMBOL	DESCRIPTION
	2X4 LIGHT FIXTURES
	2X4 LIGHT FIXTURES WITH EMERGENCY BACK UP
	SURFACE MOUNTED EMERGENCY LIGHT FIXTURE
	SURFACE MOUNTED COMBO EXIT SIGN/EMERGENCY EGRESS FIXTURE LIGHT
	1X4 LIGHT FIXTURE
	STRIP LIGHT FIXTURE
	WALLWASHER LIGHT FIXTURE
NO LABEL	EXISTING TO REMAIN
R	EXISTING TO BE RELOCATED
D	EXISTING TO BE DEMOLISHED - REMOVE ABANDONED WIRING

KEY NOTES - DEMOLITION

- 1 ALL LIGHT FIXTURES IN THIS AREA ARE EXISTING TO REMAIN, UNLESS NOTED OTHERWISE.
- 2 REPLACE EXISTING MANUAL LIGHT SWITCH WITH NEW WALL-MOUNTED OCCUPANCY SENSOR LIGHT SWITCH, IF REQUIRED, RELOCATE SWITCH TO NEW WALL TO ACCOMMODATE NEW CONSTRUCTION.



HEALTH HUB/Rx CONSULTATION

STORE NUMBER: 4176

11 RIVER RIDGE DRIVE, OAKLEY PLAZA
ASHEVILLE, NC 28803

CAP CODE: 90

CS PROJECT NUMBER: 146740

ARCHITECT OF RECORD:



115 S. College St. Ste 800 Charlotte, NC 28217
T: 704.525.8380 F: 704.561.6700

www.littleonline.com

This drawing and the design shown are the property of Little Architectural Consulting. The reproduction, copying or other use of this drawing without their written consent is prohibited and any infringement will be subject to legal action.



222 N. McDowell St. Suite 204
Charlotte, NC 28204
(P) 704.334.7363 (F) 704.347.0093
www.shultzeng.com 1569 - 20-200
NC FIRM LICENSE NUMBER: C-0688
M:ZM E:WC P:ZM

DEVELOPER:



SEAL:



REVISIONS:

DRAWING BY: WC

CVS PROJECT MANAGER: RJ

DATE: 11-02-2020

JOB NUMBER: 121-14217-08

TITLE: LIGHTING PLAN - DEMOLITION

SHEET NUMBER:

ED1

COMMENTS:

1 OVERALL CEILING DEMOLITION PLAN
ED1 SCALE: 1/8" = 1'-0"