GENERAL NOTES:

GENERAL:
ALL WORK SHALL BE IN ACCORDANCE WITH APPLICABLE CODES. COORDINATION OF ALL DISCIPLINES IS THE RESPONSIBILITY OF THE GENERAL CONTRACTOR. IF THE CONTRACTOR FINDS ANY DISCREPANCIES IN THE DOCUMENTS SUCH THAT MUST BE REPORTED IMMEDIATELY TO THE ARCHITECT. TYPICALLY DOCUMENTS INCLUDE A SPECIFICATION MANUAL. CONTRACTOR TO REVIEW THE SPECIFICATIONS FOR THE PROJECT.

CONTRACTOR MUST FIELD VERIFY ALL DIMENSIONS AT PROJECT. CONTRACTOR SHOULD NOT SCALE OFF OF DRAWINGS. CONTRACTOR NEEDS TO FIELD VERIFY EXISTING CONDITIONS TO CONFIRM DRAWINGS ARE ACCURATE. IF THE CONTRACTOR FINDS DISCREPANCIES BETWEEN FIELD CONDITIONS AND DOCUMENTS THE CONTRACTOR MUST IMMEDIATELY CONTACT THE ARCHITECT.

ALL CONCEALED WOOD TO BE FIRE RETARDANT UNLESS IT MEETS WOOD BLOCKING EXCEPTION IN CODE.

CONTRACTOR SHALL INSTALL WOOD BLOCKING FOR ALL WALL HUNG DEVICES SUFFICIENT TO MEET LOCAL CODES.

INSULATING MATERIALS INSTALLED IN BUILDING OF ANY TYPE OF CONSTRUCTION SHALL HAVE A FLAME SPREAD INDEX OF NOT MORE THAN 25 AND A SMOKE DEVELOPED INDEX OF NOT MORE THAN 450 AS DETERMINED IN ACCORDANCE WITH ASTM E84.

SIGNAGE IS NOT PERMITTED WITH THESE DOCUMENTS. A SEPARATE PERMIT FOR SIGNS MUST BE SUBMITTED.

FIREWALL & FIRE BARRIER LABELING & FIRE CALUKING
CONTRACTOR TO INSTALL LABELING OR STENCILING AT 12'-0" ON CENTER ABOVE SUSPENDED OR FIXED CEILING SYSTEMS STATING:
"1 HOUR RATED FIRE OR SMOKE BARRIER PROTECT ALL OPENINGS."
COORDINATE WITH LOCAL FIRE MARSHAL.

BEAMS AND COLUMNS THAT ARE PART OF A FIRE RATED WALL OR CEILING ASSEMBLY SHALL BE PROTECTED TO ACHIEVE THE FIRE RATING OF THE WALL OR CEILING ASSEMBLY PER NFPA 101 LIFE SAFETY CODE, CHAPTER 8.

OCCUPANCY SEPARATIONS SHALL BE PROVIDED PER THE INTERNATIONAL BUILDING CODE, THE LATEST EDITION.

CONTRACTOR SHALL FIRE CAULK ALL FIRE RATED WALLS PER LOCAL FIRE MARSHAL REQUIREMENTS.

SPRINKLER SYSTEM NOTES:
THIS BUILDING IS FULLY PROTECTED BY A HYDRAULICALLY CALCULATED WET PIPE FIRE SPRINKLER SYSTEM. APPROPRIATE SECTIONS OF CHAPTER 36 OF THE STANDARD FIRE PREVENTION CODE WILL BE ADDRESSED ACCORDINGLY. A PROPER HOLDER OF A TENNESSEE CERTIFICATE OF COMPETENCY SHALL BE RESPONSIBLE FOR THE DESIGN INSTALLATION OF THE UNDERGROUND SUPPLY PIPING, STARTING AT THE POINT WHERE THE PIPING IS SOLELY DEDICATED TO FIRE PROTECTION. SPRINKLER SYSTEM DESIGN MUST BE SUBMITTED TO THE ARCHITECT AND LOCAL FIRE MARSHAL FOR APPROVAL.

AN UNDERGROUND AND ABOVEGROUND MATERIALS & TESTING CERTIFICATE WILL BE REQUIRED FOR EACH FIRE SPRINKLER SYSTEM. CERTIFIED SIGNED BY A TENNESSEE CERTIFICATE HOLDER FOR UNDERGROUND PORTIONS AND CERTIFICATES DULY SIGNED BY A LICENSED FIRE SPRINKLER SYSTEMS SERVING EACH PARTICULAR BUILDING OR TENANT. TENANT SHALL NOT ARRANGE OR POSITION FIXTURES, SHELVING, GONDOLAS, ETC. IN SUCH A MANNER TO PREVENT SAFE EXIT FROM THE BUILDING. FIXTURE AND SHELVING ARRANGEMENTS SHALL BE SO POSITIONED THAT MINIMUM REQUIRED AISLE AND EGRESS WIDTHS ARE MAINTAINED IN ACCORDANCE WITH NFPA 101.

FIRE SPRINKLER CONTRACTOR SHALL OBTAIN A FIRE SPRINKLER SYSTEM PERMIT FROM THE FIRE MARSHAL'S OFFICE PRIOR TO INSTALLATION. ANY FIRE SPRINKLER PLANS INCLUDED IN THIS SET OF PLANS ARE FOR REFERENCE ONLY. NOT FOR PERMIT. SPRINKLER PLANS SHALL BE SUBMITTED BY SPRINKLER CONTRACTOR FOR ALL NEW OR RENOVATED SYSTEMS WITH THE FOLLOWING EXCEPTIONS: (1) ALL RENOVATED SYSTEMS RELOCATION 10 SPRINKLER HEADS OR LESS, (2) ALL RENOVATED SYSTEMS ADDING 6 SPRINKLER HEADS OR LESS.

FIRE SPRINKLER CHANGES:
IF MODIFICATIONS TO THE EXISTING FIRE SPRINKLER SYSTEM ARE REQUIRED AS A RESULT OF THE ARRANGEMENT OR CONSTRUCTION OF WALLS OR EQUIPMENT, SUCH MODIFICATIONS (INCLUDING RELOCATING OR ADDING SPRINKLER HEADS) SHALL BE PERFORMED BY A LICENSED FIRE SPRINKLER CONTRACTOR.

FIRE EXTINGUISHERS REQUIRED!
PORTABLE FIRE EXTINGUISHERS SHALL BE PROVIDED PER NFPA STANDARD NO. 10. ABC. LOCATION AND ARRANGEMENT OF THE FIRE EXTINGUISHERS WILL BE DETERMINED BY AN INSPECTOR OF THE FIRE MARSHAL'S OFFICE PRIOR TO FINAL INSPECTION.

FIRE EXTINGUISHERS IN BUSINESS & MERCANTILE OCCUPANCIES SHALL BE LOCATED PER REQUIREMENTS OF NFPA 10. THE SIZE SHALL BE A MINIMUM OF TWO (2) A 10 TW0 (2) ARE REQUIRED AND SHALL BE INSTALLED AT A MAXIMUM OF 48" ABOVE THE FINISHED FLOOR TO THE TOP OF THE HANDLE.

EGRESS LIGHTING:
EMERGENCY EGRESS LIGHTING MUST PROVIDE A MINIMUM 1-FOOT CANDLE UNINTERRUPTED LIGHT SOURCE ALONG THE PATH OF EGRESS.

IF LESS THAN 3 SEPARATE LIGHTING CIRCUITS ARE PROVIDED, DEDICATED CIRCUITS FOR EMERGENCY LIGHTING ARE NOT PERMITTED. THEY SHALL BE CONNECTED TO THE LIGHTING CIRCUIT BREAKER THE AREA THEY SERVE. NFPA 70, CHAPTER 7, SECTION 700-12(E). DEDICATED CIRCUITS FOR EXIT LIGHTING ARE NOT PERMITTED. THEY SHALL BE CONNECTED TO THE LIGHTING CIRCUIT BREAKER IN THE AREA THEY SERVE. NFPA 70, CHAPTER 7.

EXIT LIGHTING
ALL EXIT LIGHTS & EMERGENCY LIGHTS SHALL HAVE A MINIMUM 90 MINUTE BATTERY LIFE.

FIREWALL OUTLETS
ELECTRICAL OUTLETS ARE NOT PERMITTED ADJACENT TO EACH OTHER IN RATED FIREWALL ASSEMBLIES. BOXES MUST BE SPACED A MINIMUM TWO FEET (2') LATERALLY APART OR PROVIDED WITH PUTTY PADS EQUIVALENT TO THE FIREWALL RATING. VERIFY WITH LOCAL FIRE MARSHAL.

LABELING
ALL UTILITY METERS, DISCONNECT SWITCHES, FRONT & REAR DOORS MUST BE MARKED WITH CONTRASTING LETTERS & NUMBERS TO INDICATE THE TENANT SPACE THEY SERVE.

SMOKE DETECTORS
ANY HVAC EQUIPMENT PRODUCING MORE THAN 2000 CFM AIR VOLUME MUST BE EQUIPPED WITH AN AUTOMATIC SMOKE DETECTOR WITHIN THE DUCTWORK THAT IS CAPABLE OF SHUTTING DOWN THE UNIT IN THE EVENT OF FIRE. SMOKE DETECTORS MUST BE WIRED TO A VISUAL STROBE, AS WELL AS PRODUCE AN AUDIBLE ALARM SO AS TO ALERT THE BUILDING OCCUPANTS OF FIRE OR SMOKE DETECTED.

DOORS AND ACCESSIBILITY:
CONTRACTOR SHALL FOLLOW THE 2010 ADA STANDARDS FOR ACCESSIBLE DESIGN. CONTRACTOR SHALL VERIFY ALL DIMENSIONS, CLEAR AREAS AND ANY A.D.A. REQUIREMENTS BEFORE BEGINNING WORK. CONTRACTOR MUST IMMEDIATELY CONTACT THE ARCHITECT IF DISCREPANCIES ARE FOUND.

DOORS SHALL MEET THE REQUIREMENTS OF THE NFPA 101 LIFE SAFETY CODE, CHAPTER 7.

THE FLOOR LEVEL SHALL BE THE SAME ON BOTH SIDES OF THE DOOR. THE ELEVATION SHALL BE MAINTAINED FOR A DISTANCE AT LEAST EQUAL TO THE WIDTH OF THE WIDEST LEAF OF THE DOORS. NFPA 101 LIFE SAFETY CODE, CHAPTER 7.

EXIT DOORS SHALL NOT BE SUBJECT TO THE USE OF A KEY OR REQUIRE SPECIAL KNOWLEDGE TO OPERATE, NFPA 101 LIFE SAFETY CODE, CHAPTER 7, 2018 EDITION.

DOORS/HARDWARE, HANDLES, PULLS, LATCHES, LOCKS, AND OTHER OPERATING DEVICES ON ACCESSIBLE DOORS SHALL HAVE A SHAPE THAT IS EASY TO GRASP WITH ONE HAND AND DOES NOT REQUIRE TIGHT GRASPING, TIGHT PINCHING, OR TWISTING OF THE WRIST TO OPERATE. LEVER-OPERATED MECHANISMS, PUSH-TYPE MECHANISMS, AND U-SHAPED HANDLES ARE ACCEPTABLE DESIGNS. THESE TYPES SHALL BE SUPPLIED PER THE ADA STANDARDS FOR ACCESSIBLE DESIGN. TO THE BEST OF OUR KNOWLEDGE THIS INFORMATION ON THESE DRAWINGS COMPLY WITH ADA. CONTRACTOR MUST VERIFY BEFORE PURCHASE OF DEVICES.

TYPICAL MINIMUM MANEUVERING CLEARANCES ON THE PULL SIDE OF DOOR SHALL BE A MINIMUM OF 18". PER THE ADA STANDARDS FOR ACCESSIBLE DESIGN.

MINIMUM MANEUVERING CLEARANCES IN THE PUSH SIDE OF THE DOOR SHALL BE A MINIMUM OF 12" IF THE DOOR HAS A CLOSER AND A LATCH. PER THE ADA STANDARDS FOR ACCESSIBLE DESIGN.
THE TOPS OF ACCESSIBLE TABLES AND COUNTERS SHALL BE FROM 28 INCHES TO 34 INCHES ABOVE THE FINISHED FLOOR OR GROUND PER ADA STANDARDS FOR ACCESSIBLE DESIGN.

DRINKING FOUNTAINS:
IF APPLICABLE, WHERE ONLY ONE DRINKING FOUNTAIN IS PROVIDED ON A FLOOR, THERE SHALL BE A DRINKING FOUNTAIN WHICH IS ACCESSIBLE TO INDIVIDUALS WHO USE WHEEL CHAIRS IN ACCORDANCE WITH 2010 ADA, AND ONE ACCESSIBLE TO THOSE WHO HAVE DIFFICULTY BENDING OR STOOPING. THIS CAN BE ACCOMMODATED BY USE OF A "HI-LO" FOUNTAIN. ADVISORY 602.6 WATER FLOW. THE PURPOSE OF REQUIRING THE DRINKING FOUNTAIN SPOUT TO PRODUCE A FLOW OF WATER 4 INCHES (100 MM) HIGH MINIMUM IS SO THAT A CUP CAN BE INSERTED UNDER THE FLOW OF WATER TO PROVIDE A DRINK OF WATER FOR AN INDIVIDUAL WHO, BECAUSE OF A DISABILITY, WOULD OTHERWISE BE INCAPABLE OF USING THE DRINKING FOUNTAIN.

STREET AND TENANT NUMBERS:
THE STREET NUMBERS MUST BE VISIBLE FROM THE STREET THAT PROVIDES DRIVEWAY ACCESS TO THE PROPERTY AND PLACES ON A CONTRASTING BACKGROUND THAT PROVIDES 24 HOUR VISIBILITY. THE STREET NUMBERS MUST ALSO MEET ONE OF THE FOLLOWING SIZE REQUIREMENTS (1) IF THE STREET NUMBER IS PLACED WITHIN 15 FEET OF THE CURB OR EDGE OF PAVEMENT OF THE STREET, THE STREET NUMBER SHALL BE POSTED IN FIGURES AT LEAST 4 INCHES IN HEIGHT. (2) IF THE STREET NUMBER IS PLACED MORE THAN 15 FEET FROM THE CURB OR EDGE OF PAVEMENT OF THE STREET, THE STREET NUMBER SHALL BE POSTED IN FIGURES AT LEAST 6 INCHES IN HEIGHT. INTERNATIONAL FIRE CODE CHAPTER 5, 2018 EDITION.

A SIGN CLEARLY STATING THAT SMOKING IS PROHIBITED SHALL BE CONSPICUOUSLY POSTED BY THE BUILDING OWNER, AGENT, OPERATOR, PERSON IN CHARGE OR PROPRIETOR AT EACH ENTRANCE OR IN A POSITION CLEARLY VISIBLE UPON ENTRY INTO THE BUILDING IN ACCORDANCE WITH TENNESSEE REQUIREMENTS. ACCEPTABLE SIGNS SHALL DISPLAY EITHER "NO SMOKING" OR THE INTERNATIONAL "NO SMOKING" SYMBOL (CONSISTING OF A PICTORIAL REPRESENTATION OF A BURNING CIGARETTE ENCLOSED IN A RED CIRCLE WITH A RED BAR ACROSS IT).

PROVIDE SHOP DESIGNATIONS ON ALL EXTERIOR DOORS: MINIMUM SIZE OF 4".

STORAGE RACKING, IF REQUIRED:
PROVIDE A STORAGE RACKING PLAN FOR ANY STORAGE AREA WHERE RACKING IS INSTALLED AND COMBUSTIBLE MATERIALS ARE TO BE STORED OVER 12 FEET. THE STORAGE RACKING PLAN SHALL BE SUBMITTED AND APPROVED BEFORE RACKS ARE INSTALLED. PER THE INTERNATIONAL FIRE CODE, 2018 EDITION. ADDITIONAL EXIT AND EMERGENCY LIGHTING MY BE REQUIRED UPON THE INSTALLATION OF STORAGE RACKS. THE FOLLOWING INFORMATION IS REQUIRED TO OBTAIN A RACKING PERMIT (A) A COMMODITY AFFIDAVIT ON COMPANY LETTERHEAD DESCRIBING THE COMMODITY THAT IS BEING STORED. PROVIDE INFORMATION ON PLASTICS AND HAZARDOUS MATERIALS (SEE ATTACHED SHEET TO DETERMINE THE COMMODITY CLASS) (B) SCALED FLOOR PLANS OF THE BUILDING HIGHLIGHTING THE DESIGNATED STORAGE AREA AND LABEL ALL AREAS AS TO THEIR USE (C) ELEVATIONS OF THE RACKS WITH THE STORAGE HEIGHT DIMENSIONS. NOTE: FOUR FEET WILL AUTOMATICALLY BE ADDED TO THE TOP SHELF TO DETERMINE STORAGE HEIGHT (D) INFORMATION ON HOW PRODUCT IS STORED (I.E. WOOD CARTONS, PLASTIC PALLETS, SHELVES, WIRE MESH.) (E) INFORMATION ON HOW PRODUCT IS PACKED (I.E. BOXES, CARTONS, CONTAINERS). ARE PALLET LOADS SHRINK WRAPPED? (F) IF THE BUILDING HAS A SPRINKLER SYSTEM, PROVIDE THE DENSITY.

SEALANT COLORS:
CONTRACTOR SHALL SUBMIT SEALANT COLOR SAMPLES TO ARCHITECT FOR SELECTION (TYP.)

ARCHITECTURAL ABBREVIATIONS

PLEASE REFER TO ENGINEERING DRAWINGS FOR ENGINEERING ABBREVIATIONS

Abbreviation	Meaning
A	
A.C.T.	ACOUSTICAL CEILING TILE
A.F.F.	ABOVE FINISH FLOOR
A.H.U.	AIR HANDLING UNIT
ALT.	ALTERNATE
ALUM.	ALUMINUM
ANOD	ANODIZED
APPROX.	APPROXIMATELY
ARCH.	ARCHITECTURAL
ASTM	AMERICAN SOCIETY FOR TESTING MATERIAL
AUX.	AUXILIARY
B	
B/O	BOTTOM OF
B.F.F.	BOTTOM OF FINISH FLOOR
BKBD	BACKBOARD
BLDG.	BUILDING
C	
C.I.P.	CAST IN PLACE
C.J.	CONTROL JOINT
C/L	CENTERLINE
CLG.	CEILING
CLR.	CLEAR
C.M.	COFFEE MAKER
CMU	CONCRETE MASONRY UNIT
CNT.	COUNTER
C.O.	CASED OPENING
CONC.	CONCRETE
CONT.	CONTINUOUS
CPT.	CARPET
C.T.	CERAMIC TILE
D	
DBL.	DOUBLE
DFS	DIRECT APPLIED FINISH STUCCO
DIA.	DIAMETER
DIV.	DIVISION
DN.	DOWN
DR.	DOOR
D.S.	DOWNSPOUT
DW.	DISHWASHER
D.W.	DOMESTIC WATER
DWG.	DRAWING
DWGS.	DRAWINGS
E	
EA	EACH
EF.	EXHAUST FAN
ELEC.	ELECTRIC, ELECTRICAL
ELEV., EL	ELEVATION
EMS	ENERGY MANAGEMENT SYSTEM
EPDM	ETHYLENE PROPYLENE DIENE MONOMER
EQ.	EQUAL
EQUIP.	EQUIPMENT
E.W.	EACH WAY
E.W.H.	ELECTRIC WATER HEATER
EX. EXIST.	EXISTING
EXP.	EXPANSION
EXT.	EXTERIOR
F	
*F	FAHRENHEIT
F.D.	FLOOR DRAIN
F.D.C.	FIRE DEPARTMENT CONNECTOR
F.E.	FIRE EXTINGUISHER
F.E.C.	FIRE EXTINGUISHER CABINET
F.F.	FINISH FLOOR
F.J.B.	FRONT JOIST BEARING
F.O.F.	FACE OF FINISH
F.O.S.	FACE OF STUD
FT.	FEET
G	
GA.	GAUGE
GALV.	GALVANIZED
GFCI.	GROUND FAULT CURRENT INTERRUPTER
GL	GLASS, GLAZING
GWB, GYP. BD.	GYPSUM WALL BOARD
H	
HC.	HANDICAP
HDWR.	HARDWARE
HM	HOLLOW METAL
HORIZ.	HORIZONTAL
HR.	HOUR
I	
ID.	INSIDE DIMENSION
I.M.	ICE MAKER
IN.	INCHES
INCAND.	INCANDESCENT
INSUL.	INSULATION
J	
JT.	JOIST
K	
K.	KIP
KO.	KNOCK OUT
KW	KILOWATT
L	
LAM.	LAMINATE
LAV.	LAVATORY
LB.	POUND
LF.	LINEAR FOOT
L.S.D. DISPENSER	LIQUID SOAP
M	
MAX.	MAXIMUM
MECH.	MECHANICAL
MFR.	MANUFACTURER
MICRO.	MICROWAVE
MIN.	MINIMUM
MISC.	MISCELLANEOUS
MM.	MILLIMETER
M.O.	MASONRY OPENING
MTD.	MOUNTED
MTL.	METAL
N	
N/A	NOT APPLICABLE
NE	NORTHEAST
NEG.	NEGATIVE
N.F.W.H.	NON-FREEZE WALL HYDRANT
N.I.C.	NOT IN CONTRACT
NO.	NUMBER
NW	NORTHWEST
O	
O.A.	OVERALL
O.C.	ON CENTER
O.D.	OUTSIDE DIMENSION
O.H.	OVERHEAD
OPNG.	OPENING
OPP.	OPPOSITE
OPP. HD.	OPPOSITE HAND
P	
P.A.	PUBLIC ADDRESS
PAR.	PARALLEL
PERP.	PERPENDICULAR
PL.	PLATE
P.LAM	PLASTIC LAMINATE
PLY.WD.	PLYWOOD
PNL.	PANEL
POS.	POSITIVE
PREFAB.	PRE-FABRICATED
PREFIN.	PRE-FINISHED
P.S.I.	POUND PER SQUARE INCH
P.S.F.	POUND PER SQUARE FOOT
P.T.	PRESSURE TREATED
PVC.	POLYVINYL CHLORIDE
PVMT.	PAVEMENT
Q	
-	-
R	
R.	RADIUS
R.D.	ROOF DRAIN
REF.	REFRIGERATOR
REINF.	REINFORCE, REINFORCING
REQD.	REQUIRED
R.J.B.	REAR JOIST BEARING
R.L.	RAIN LEADER
R.O.	ROUGH OPENING
RTU	ROOF TOP UNIT
R.V.	ROOF VENT
S	
SCH.	SCHEDULE
S.E.	SOUTHEAST
SGL.	SINGLE
SH. ROD	SHOWER ROD
SHT.	SHEET
SIM.	SIMILAR
S.O.G.	SLAB ON GRADE
S.S.	STAINLESS STEEL
STD.	STANDARD
STL.	STEEL
STRUCT.	STRUCTURE, STRUCTURAL
SW	SOUTHWEST
T	
T/C	TOP OF CURB
TECH	TECHNICAL
TEL	TELEPHONE
TEMP.	TEMPERATURE
T.O.	TOP OF
T/O	TOP OF
TR.	TRANSITION STRIP
TSTAT.	THERMOSTAT
TYP.	TYPICAL
U	
U.N.O.	UNLESS NOTED OTHERWISE
UTIL.	UTILITY
V	
V.C.T.	VINYL COMPOSITION TILE
VEND.	VENDING MACHINE
VERT.	VERTICAL
V.T.R.	VENT THROUGH ROOF
V.W.C.	VINYL WALL COVERING
V.I.F.	VERIFY IN FIELD
W	
W/	WITH
W.C.	WATER CLOSET / WATER COOLER
WD.	WOOD
W.H.	WATER HEATER
WHSE.	WAREHOUSE
WP.	WEATHER PROOF
W.R.	WATER RESISTANT
W.W.F.	WELDED WIRE FABRIC

MATERIAL INDEX

EARTH	STEEL
GRAVEL	PLYWOOD
GROUT OR SURFACE CONCRETE	GYPSUM
CAST-IN-PLACE CONCRETE	INSULATION - BATT OR LOOSE
CUT STONE	RIGID INSULATION
WOOD - ROUGH	EXTERIOR INSULATION FINISH SYSTEM
WOOD - FINISH	BRICK
WOOD BLOCKING	CULTURED STONE

		EXITS & PASSAGEWAYS	EXIT ACCESS CORRIDORS	ROOMS
FINISH RATINGS	MINIMUM WALL FINISH CLASS "M"	A or B	A or B	A or B
	MINIMUM ROOF FINISH CLASS USE GROUP	A or B	A or B	A or B

GENERAL LEGEND



COLUMN LINE INDICATOR
FACE OF WALL INDICATOR
DETAIL INDICATOR
DETAIL NUMBER
SHEET NUMBER
DOOR NUMBER, REFER TO SCHEDULE
CEILING MATERIAL FINISH
CEILING HEIGHT
EXTERIOR ELEVATION INDICATOR
DETAIL NUMBER
SHEET NUMBER
INTERIOR ELEVATION INDICATOR
DETAIL NUMBER
SHEET NUMBER
PARTITION TYPE
WINDOW TYPE, REFER TO SCHEDULE
ENLARGED PLAN INDICATOR
DETAIL NUMBER
SHEET NUMBER
ROOM NAME
ROOM NUMBER
EXTERIOR FINISH MATERIAL
DIMENSION LINE
NOTE: DIMENSIONS ARE TAKEN FROM FINISHED FACE UNLESS OTHERWISE NOTED.

MaxDesignGroup
Architecture · Planning · Interiors
2862 Buford Highway
Suite 106
Duluth, Georgia 30096

Tel: 770-910-9740
Cell: 770-530-5245
Email: rmaxian@maxdesigngp.com

THIS DRAWING IS THE PROPERTY OF MAXDESIGN GROUP, AND IS NOT TO BE REPRODUCED IN WHOLE OR IN PART. IT IS NOT TO BE USED ON ANOTHER PROJECT AND SHALL BE RETURNED UPON REQUEST.

PROFESSIONAL SEAL:



PROJECT TITLE:

MARKET PLACE AT LOCUST GROVE SHOPS PHASE 2

LOCUST GROVE, GEORGIA

PROJECT INFO:
4959 BILL GARDNER PARKWAY
LOCUST GROVE, GA 30248

OWNER:
IP ILG, LLC

JACOB LANG
912.655.3438

PRINT RECORD	
Description	Date
ISSUED FOR PERMIT	11.23.2020

REVISION		
No.	Description	Date

GENERAL NOTES

Project number	D20-101
Date	10/26/2020
Drawn by	B.C.R.
Checked by	R.M.M.

G-002

Scale	1 1/2" = 1'-0"

ISSUED FOR CONSTRUCTION

Order Plans @ WWW.LDILine.com