DEMOLITION LEGEND

- EXISTING TO REMAIN
- DEMOLISH/REMOVE/RELOCATE
- AREA TO BE DEMOLISHED

SHEET NOTES

1. SALES FLOOR TO BE ACCESSIBLE TO CUSTOMERS DURING NON-CONSTRUCTION HOURS. PROVIDE TEMPORARY COVERS CAPABLE OF WITHSTANDING SHOPPING CART TRAFFIC AND OCCUPANTS FOR PITS AND TUNNELS. REMOVE CONSTRUCTION FENCING AND DUST WALLS INTERFERING WITH CUSTOMER CIRCULATION OR ACCESS.
2. DEMOLITION INCLUDES BUT IS NOT LIMITED TO ITEMS SHOWN DASHED. REF DEMOLITION REQUIREMENT NOTE ON N1 SHEET.
3. REMOVE ALL DOORS SHOWN DASHED. REFER TO ENLARGED PLANS AND DOOR SCHEDULE FOR DOOR AND FRAME REPLACEMENT.
4. NOT USED.
5. COORDINATE REMOVAL AND DISPOSAL OF EXISTING REFRIGERATED CASES AND FIXTURES WITH MECHANICAL SERVICES CONSTRUCTION MANAGER
6. REMOVE EXISTING FITTING ROOMS

REMOVE RACKING SHOWN DASHED

DEMO COUNTERS

REMOVE EXISTING PHOTOLAB

RESTROOM DEMOLITION TO INCLUDE BUT IS NOT LIMITED TO:
- REMOVAL OF ALL PARTITIONS
- WALL FINISHES TO FACE OF STUDS
- FLOOR FINISHES TO BARE CONCRETE
- LAVATORIES
- ALL ACCESSORIES
- TEMPORARY REMOVAL OF WATER CLOSETS AND URINALS
- REF 2 - D1.1 FOR SECURITY ENCLOSURE

REF SHEET SA1 FOR BID ALLOWANCE OF DUST WALLS

REMOVE DEPARTMENT SIGNAGE ATTACHED TO GROCERY BULKHEAD. PATCH AND REPAIR BULKHEAD TO MATCH ADJACENT

REMOVE EXISTING SUSPENDED PERIMETER SIGN RAILING

DEMO EXISTING FITTING ROOMS

REMOVE PORTION OF WALL FOR NEW DOOR, REF 1 - A1 AND REF STRUCTRAL

REMOVE DOOR AND FRAME AND PORTION OF WALL FOR NEW DOOR, REF 1 - A1 AND REF STRUCTRAL

REMOVE PORTION OF WALL FOR NEW SLIDERS, REF 1 - A1 AND REF STRUCTRAL

REMOVE SLIDER, INFILL TO MATCH EXISTING

DEMO DOORS, INFILL TO MATCH EXISTING, REF STRUC

DEMO DOOR AND PORTION OF WALL FOR NEW SLIDER, REF STRUCTURAL

REMOVE DOOR AND FRAME FOR NEW WINDOW

RELOCATE ORNAMENTAL FENCE, POST, DOOR, AND PROPANE TANKS, REF 1 - A1

DEMO EXISTING ORNAMENTAL FENCE

RESTROOM DEMOLITION TO INCLUDE BUT IS NOT LIMITED TO:
- REMOVAL OF ALL PARTITIONS
- WALL FINISHES TO FACE OF STUDS
- FLOOR FINISHES TO BARE CONCRETE
- LAVATORIES
- ALL ACCESSORIES
- TEMPORARY REMOVAL OF WATER CLOSETS AND URINALS
- REF 2 - D1.1 FOR SECURITY ENCLOSURE

REMOVE MONEY CENTER DESKS AND EQUIPMENT SHOWN DASHED

REMOVE EXISTING VISION CENTER TABLES AND COUNTERTOPS SHOWN DASHED AFTER NEW VISION CENTER HAS BEEN COMPLETED. CONTINUE TO USE EXISTING VISION CENTER WHILE NEW IS UNDER CONSTRUCTION.

1 DEMOLITION PLAN
1" = 20'-0"

Order Plans @ WWW.DTLine.com

brr
ARCHITECT OF RECORD:
JOHN F. FRANK
8131 METCALF AVE
OVERLAND PARK, KS 66204
www.brrarch.com
TEL: 913-262-9095
FAX: 913-262-9044

STIPULATION FOR REUSE
THIS DRAWING HAS BEEN PREPARED FOR USE ON THE SPECIFIC PROJECT AND SITE DESCRIBED HEREIN. IT IS NOT TO BE USED IN WHOLE OR IN PART FOR ANY OTHER PROJECT OR SITE WITHOUT THE EXPRESS WRITTEN PERMISSION OF BRR ARCHITECTURE, INC. ANY UNAUTHORIZED USE OF THESE PLANS AND SPECIFICATIONS WILL BE AT THE SOLE RISK OF THE PARTY USING OR PERMITTING SUCH USE AND WITHOUT LIABILITY OR LEGAL EXPOSURE TO BRR ARCHITECTURE, INC. THE USE OF THESE PLANS AND SPECIFICATIONS ON ANY PROJECT WITHOUT THE WRITTEN PERMISSION OF BRR ARCHITECTURE, INC. IS AGREEMENT BY SUCH USER TO INDEMNIFY AND HOLD HARMLESS BRR ARCHITECTURE, INC. FROM ANY AND ALL LIABILITY ARISING FROM SUCH USE, AND FURTHER AGREEMENT BY USER TO PAY BRR ARCHITECTURE, INC. ALL COSTS AND EXPENSES, INCLUDING LEGAL FEES AND COURT COSTS, INCURRED BY BRR ARCHITECTURE, INC. IN ENFORCING THIS AGREEMENT.

CONSULTANTS

Walmart
ATLANTA (GRESHAM), GA
2427 GRESHAM RD
STORE NO. 03 709 25S
2021 SPRB-R
JOB NUMBER: 99645809 | PROTO
185

ISSUE BLOCK

CHECKED BY:	
DRAWN BY:	MED
PROTO CYCLE:	10/30/20
DOCUMENT DATE:	11/20/20

NOT FOR CONSTRUCTION

DEMOLITION PLAN

SHEET: D1

12/8/2020 2:55:08 PM
C:\Users\mdavis\Documents\Walmart_AtlantaGresham_GA_185_D_ARCH_mdavis.rvt