

STIPULATION FOR REUSE:
 THIS IS A PRELIMINARY SET OF PLANS. IT IS NOT TO BE USED FOR CONSTRUCTION. ALL RIGHTS ARE RESERVED BY THE ARCHITECT AND SHALL REMAIN HIS PROPERTY. NO PART OF THIS SET OF PLANS IS TO BE REPRODUCED, COPIED, OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, WITHOUT THE WRITTEN PERMISSION OF THE ARCHITECT. ANY REUSE OF THIS SET OF PLANS WITHOUT THE WRITTEN PERMISSION OF THE ARCHITECT SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO THE ARCHITECT.

CONSULTANTS

Walmart
 ATLANTA (GRESHAM), GA
 2427 GRESHAM RD SE 30316
 STORE NO. 03709-233
 JOB NUMBER: 9645888 | PHOTO:
 2021 SPRB-R

ISSUE BLOCK

NO.	DATE	DESCRIPTION

CHECKED BY:

DRAWN BY: MED

PROTO CYCLE: 10/30/20

DOCUMENT DATE: 11/20/20

NOT FOR CONSTRUCTION

ENLARGED PLANS, ELEVATIONS, AND DETAILS

SHEET: A5

SHEET NOTES


- REF AS FOR SCHEDULE FINISH KEY AND GENERAL FINISH NOTES.
- PAINT STRUCTURE AS INDICATED ON 4-A1 AND PAINT GYP BOARD WALLS TO 6" BEHIND TOP AND SIDES OF REFRIGERATED CASES.
- NOT USED.

KEYNOTES

- 6.27 4" HIGH WANSOT WITH OUTSIDE CORNER TRIM
- 10.44 PROVIDE TACTILE "EXIT" SIGN, REF N1.


REMOVE INTERIOR TENANT SIGNAGE AS INDICATED BELOW:

- ALL TENANT SPACES EXCLUDING FULL SERVICE FOOD TENANTS:-
 REMOVE ALL SIGNS, INCLUDING BLACK PLACARDS AND LIT SIGNS. RETURN TO TENANT
 1. THE ELECTRICAL FOR REMOVED LIT SIGNS TO BE TERMINATED BACK TO NEAREST JUNCTION BOX.
 2. PATCH, REPAIR AND PAINT BULKHEAD WALL AT REMOVED SIGN AND ASSOCIATED ELECTRICAL, WALLPAPER AND/OR ORNAMENTATION TO MATCH ADJACENT CONSTRUCTION AND FINISHES.
 3. REMOVE ALL WALLPAPER AND/OR ORNAMENTATION ON THE BULKHEAD AND WALL BELOW UNO.
- ALL FULL SERVICE FOOD TENANTS:-
 EXISTING LIT TENANT SIGNS ON LOWER BULKHEADS AND AWNINGS TO REMAIN, DO NOT REMOVE, PAINT AROUND THE SIGN. TREAT TENANTS (I.E. PRETZEL COMPANIES) THAT ARE OCCUPYING FULL SERVICE FOOD TENANT SPACES MAY CONTINUE TO USE LIT SIGNAGE.
 REMOVE BLACK PLACARD TENANT SIGNS.
 REMOVE MCDONALD'S ARCHES ON UPPER BULKHEAD.
 LIT SIGNAGE CAN HAVE THE TENANT BRANDED BULKHEAD WITH THE EXCEPTION OF WALMART BLUE. USE OF WALMART BLUE ACCENTS WILL REQUIRE APPROVAL BY WALMART SERVICES.
 PATCH, REPAIR AND PAINT BULKHEAD WALL AT REMOVED ELECTRICAL, WALLPAPER AND/OR ORNAMENTATION TO MATCH ADJACENT CONSTRUCTION AND FINISHES. THE ELECTRICAL FOR REMOVED LIT SIGNS TO BE TERMINATED BACK TO NEAREST JUNCTION BOX.
- WALMART OWNED TENANT SIGNS AND ORNAMENTATION ARE TO BE RETURNED TO THE FIELD PROJECT SUPERVISOR. THIRD-PARTY TENANT SIGNS AND ORNAMENTATION ARE TO BE RETURNED TO THE TENANT. IF A THIRD-PARTY TENANT REQUESTS THEIR SIGN, WALLPAPER OR ORNAMENTATION NOT TO BE REMOVED, CONTACT THE WALMART CONSTRUCTION MANAGER.




6 VESTIBULE CART CURB

7 BASE CABINET SECTION




3 BASE CABINET SECTION


2 COURTESY DESK FLOOR PLAN




9 INTERIOR ELEVATION



8 AUTO CENTER ELEVATION



5 GR SIDE TENANT WALL



4 GM SIDE TENANT WALL

105 COURTESY DESK, 106 RETURNS STORAGE


- WALLS
 REF 2-A5 FOR FINISH DETAILS.
- FLOOR
 ETR.
- CEILING
 LAY-IN. REF SHEET SA1 FOR CEILING SCHEDULE.

107 CASH, 108 COUNTING

- WALLS
 ETR.
- FLOOR
 ETR.
- CEILING
 REF SHEET SA1 FOR CEILING SCHEDULE.

101 VESTIBULE-GM, 103 GM ENTRY, 104 CART STORAGE-GM, 115 VESTIBULE-GR, 117 GR ENTRY, 118 CART STORAGE-GR

- WALLS
 GYP BD. PAINT P131 TO CEILING OR EXPOSED STRUCTURE UNO. INSTALL PS7 WANSOT AND DB5 BASE UNO.
 CMU. PAINT P164 WANSOT TO 4'-0" AFF AND P131 ABOVE 4'-0" AFF TO CEILING OR EXPOSED STRUCTURE. WHERE BASE OR WANSOT IS EXISTING, REPLACE WITH PS7 WANSOT AND DB5 BASE.
 PAINT COLUMNS ADJACENT TO WALLS P131.
 CART STORAGE ONLY. ADD 3/4" PLYWOOD TO 4'-0" AFF WITH TOP EDGE EASED TO ALL GYP BD WALLS.
 CART STORAGE WALLS: P164 WANSOT TO 4'-0" AFF.
- FLOOR
 REF FLOOR FINISH PLAN.
- CEILING
 REF SHEET SA1 FOR CEILING SCHEDULE.



1 FRONT TENANT WALL FLOOR PLAN

Order Plans @ www.LDinline.com

www.LDinline.com

www.LDinline.com