PLUMBING CONTRACTOR TO PROVIDE DRAINS FROM BEVERAGE EQUIPMENT TO INDIRECT TERMINATION AT FLOOR SINK

PROVIDE 8" SLOPED UNDERSLAB PVC CHASE WITH LONG SWEEP ELBOWS AT BOTH ENDS FOR REFRIGERATION LINES. AVOID ELBOWS IN HORIZONTAL. SEAL ENDS OF CHASE WITH FOAM AFTER LINES ARE INSTALLED. VERIFY REQUIRED CHASE SIZE WITH MECHANICAL CONTRACTOR

ROUTE FULL SIZE DRAINS FROM BEVERAGE EQUIPMENT AND INTEGRAL CABINET DRAINS TO FS WITH AIR GAP (TYP OF 2)

ROUTE FULL SIZE DRAINS FROM BEVERAGE EQUIPMENT AND S4 TO FS WITH AIR GAP (TYP)

ROUTE CONDENSATE DRAIN FROM EVAPORATORS TO HD WITH AIR GAP

ROUTE FULL SIZE DRAIN FROM ICE MAKER TO FS WITH AIR GAP

ROUTE FULL SIZE DRAINS FROM REFRIGERATED CASES TO FS WITH AIR GAP

ROUTE FULL SIZE DRAINS FROM SANDWICH CASE TO FS WITH AIR GAP

AIR ADMITTANCE VALVE SHALL BE INSTALLED PER FBCP

ROUTE FULL SIZE DRAIN FROM SALAD BAR TO FS WITH AIR GAP

ROUTE FULL SIZE DRAIN FROM COLDWELL & DUMP SINK (S4) TO FS WITH AIR GAP

ROUTE FULL SIZE DRAINS FROM TANKLESS WH'S TO FS WITH AIR GAP

ROUTE FULL SIZE DRAIN FROM DISH WASHER TO FS WITH AIR GAP

S3. ROUTE DRAINS TO FS WITH AIR GAP. REF 3/P2.0

1" CONDENSATE DRAIN LINE. HEAT TRACE REQUIRED IN FREEZERS. REF ELECTRICAL SPECIFICATIONS SECTION 3.5.12 FOR HEAT TRACE REQUIREMENTS.

ROUTE CONDENSATE DRAIN FROM EVAPORATORS TO HD WITH AIR GAP

1" CONDENSATE DRAIN LINE. HEAT TRACE REQUIRED IN FREEZERS. REF ELECTRICAL SPECIFICATIONS SECTION 3.5.12 FOR HEAT TRACE REQUIREMENTS.

2-WAY YCO

4" SEWER. REF: CIVIL FOR CONTINUATION

2"ø VENT BELOW GRADE

GT - REFER TO CIVIL FOR EXACT LOCATION

CORRIDOR 113

UTILITY 111 SC-3

MERCHANDISE 101A SC-1

COOLER VAULT 110 SC-3

ELECTRICAL 107 SC-3

BEER CAVE 112 SC-1

WOMEN 105 SC-2

MEN 106 SC-2

BACKROOM 104 SSP-1

SALES 102 SC-1

OFFICE 103 SC-2

COOLER 109 SC-3

FREEZER 108 SC-3

1 DRAIN PIPING PLAN
1/4"= 1'-0"

SANITARY MINIMUM INVERT ELEVATION = 80.25' BASED ON FINISH FLOOR ELEVATION OF 83.50' AND TOTAL DEVELOPED LENGTH OF 120'-0" AT 1/8" PER FOOT SLOPE. SEE CIVIL DRAWING FOR CONTINUATION.

GREASE MINIMUM INVERT ELEVATION = 80.75' BASED ON FINISH FLOOR ELEVATION OF 83.50' AND TOTAL DEVELOPED LENGTH OF 120'-0" AT 1/8" PER FOOT SLOPE. SEE CIVIL DRAWING FOR CONTINUATION.

DRINKING FOUNTAIN IS TO BE FURNISHED AND INSTALLED BY GENERAL CONTRACTOR.

REFERENCE P0.1 FOR PLUMBING SCHEDULES, NOTES AND SYMBOLS.

Order Plans @ WWW.LDLine.com

Cubaci & Peterson
Architects Engineers Planners
1925 Prospect Ave.
Orlando, FL 32814
P (407) 661-9100
P (407) 661-9101
www.c-p.com
Florida Corporate Certificate #AA C000526

CLIENT NAME
BLACKFIN PARTNERS INVESTMENTS, INC.
4400 PGA BLVD, SUITE 600
PALM BEACH GARDENS, FL 33410

PROJECT NAME
7-ELEVEN #41795 - OCALA, FL
9000 BLOCK OF SE MARICAMP ROAD
OCALA, FL 34470

SHEET TITLE
DRAIN PIPING PLAN

JOSE J. DIAZ-VELAZQUEZ
LICENSE
No. 78474
STATE OF FLORIDA
PROFESSIONAL ENGINEER

RELEASE

PROJECT NO.	DATE	DRAWN	CHECKED
2200355	12/17/2020	MS	JJD

COPYRIGHT © - All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by Cubaci & Peterson, (C & P) as instruments of service shall remain the property of C & P. C & P retains all common law, statutory and other reserved rights, including the copyright thereto. Any reuse or reproduction of this document without written permission from C & P is a violation of Federal copyright laws.

P1.0