

Symbol	Qty	Label	Arrangement	LMF	Lum. Lumens	Lum. Watts	Part Number
	7	E1	WALL MOUNT	1.000	N.A.	1	E-XML1W
	5	P1-INV	SINGLE	1.000	N.A.	59	C-LB-A-RDAC-8L-40K-WH
	4	X1	WALL MOUNT	1.000	N.A.	1	E-XPL2RBW
	5	A2E-EB-ON	SINGLE	1.000	1400	32	ZR22C-40L-40K-10V-FD-EB14
	2	A2ESC-EB-ON	SINGLE	1.000	1400	40	ZR22MT-40L-40K-CMA-EB14-FL
	3	DS4E-ON	SINGLE	1.000	1400	40	CR-LE-40L-40K-S-EB14SMK

Label	Units	Avg	Max	Min	Avg/Min	Max/Min
Beer Cave_Workplane	Fc	0.27	1	0	N.A.	N.A.
Cooler Vault_Workplane	Fc	0.06	1	0	N.A.	N.A.
Kitchen Cooler_Workplane	Fc	0.00	0	0	N.A.	N.A.
Kitchen Freezer_Workplane	Fc	0.00	0	0	N.A.	N.A.
Kitchen_Workplane	Fc	6.33	11	1	6.33	11.00
Main Sales_Workplane	Fc	18.87	57	1	18.87	57.00
Men's Room_Workplane	Fc	6.00	19	1	6.00	19.00
Office_Workplane	Fc	10.77	14	8	1.35	1.75
Storage Room_Workplane	Fc	5.50	12	1	5.50	12.00
Women's Room_Workplane	Fc	6.21	20	0	N.A.	N.A.

FIXTURE MOUNTING HEIGHTS AS SHOWN

REFLECTANCES: 80%-50%-20%

ADDITIONAL EQUIPMENT REQUIRED:

(7) SMK-L-E-C SURFACE MOUNT END CAPS

(7) SMK-L-E-L SURFACE MOUNT KITS

(1) CCT-CWC-1 SMARTCAST CONFIGURATION TOOL


(10) H8-GU24 GU24 Base Housings Recessed Housings, 120V, Architectural new construction

***CUSTOMER TO VERIFY MOUNTING, VOLTAGE, AND COLOR PRIOR TO PLACING ORDER

NOTE: Exterior Wall Packs/Canopy Fixtures shown for Placement ONLY

GENERAL PLAN NOTES

- REFLECTANCES: 80% CEILING, 50% WALL, 20% FLOOR.
- CALCULATION ZONES SET TO WORK PLANE AT 36" A.F.F.
- CALCULATIONS ARE MEASURED IN FOOTCANDLES
- LIGHTS SHOWN IN PLAN ARE FOR PHOTOMETRICS ONLY, AND DOES NOT REPRESENT THE ENTIRE LIGHT FIXTURE SCHEDULE.



WWW.IDLINE.com

Order Plans @

1 EGRESS PHOTOMETRICS
1/4" = 1'-0"


1925 Prospect Ave.
Orlando, FL 32814
P (407) 661-9100
P (407) 661-9101
www.ep.com
Florida Corporate Certificate #AA 008626

4
Cuhaci & Peterson
Architects Engineers Planners

CLIENT NAME
BLACKFIN PARTNERS INVESTMENTS, INC.
4400 PCA BLVD, SUITE 600
PALM BEACH GARDENS, FL 33410

PROJECT NAME
7-ELEVEN #1795 - OCALA, FL
9000 BLOCK OF SE MARICAMP ROAD
OCALA, FL 34170

SHEET TITLE
EGRESS PHOTOMETRICS



PROJECT NO.	220035
DATE	12/17/2020
DRAWN	SP
CHECKED	JS

RELEASE