NOTES

1. REMOVE EXISTING PAVEMENT MARKINGS (PAINT AND THERMOPLASTIC) WITHIN LIMITS OF CONSTRUCTION BY MICRO-MILLING, TYP.
2. LIGHTING PROVIDED BY GEORGIA POWER. COORDINATE WITH OWNER AND GEORGIA POWER FOR REMOVAL.
3.
4. OWNER WILL CONTINUE TO OPERATE THE CHASSIS LOT THROUGHOUT THE DURATION OF THE PROJECT, UP UNTIL TIME TO STRIPE AREA 1.
5. PROTECT ALL OAK TREES WITHIN THE OAK GROVE LIMITS OF CONSTRUCTION. AREA 1 RELATED CONSTRUCTION TRAFFIC AND EQUIPMENT SHALL REMAIN TO THE EAST AND SOUTH OF THE OAK GROVE LIMITS OF CONSTRUCTION.
6. ALL TREE RELATED WORK WITHIN THE OAK GROVE LIMITS OF CONSTRUCTION SHALL BE BY BARTLETT TREE EXPERTS (REQUIRED SUBCONTRACTOR). REMOVE PINE TREES AND GRIND STUMPS A MINIMUM OF 18" BELOW GRADE. REMOVE GRINDINGS AND BACKFILL WITH TOPSOIL AND GRASS, TYP OF NINE PINE TREES.
7. CONCRETE BARRIERS SHOWN ARE FOR ILLUSTRATION ONLY AND MAY NOT REPRESENT THE ACTUAL NUMBER OF BARRIERS TO BE RELOCATED ON THE DRAWING.

LEGEND

EXIST CONC. BARRIERS

EXIST CONC. BARRIERS TO BE RELOCATED

ABBREVIATIONS

CBP US CUSTOMS & BORDER PROTECTION

ISSUED FOR BID
2021/02/03
NOT TO BE USED FOR CONSTRUCTION
DRAWING SCALES SHOWN BASED ON 22"x34" DRAWING

GEORGIA PORTS

Mark	Description	Date	Appr.
0	ISSUE FOR BID	02/03/2021	JHP

GEORGIA PORTS AUTHORITY
GCT CAPACITY IMPROVEMENTS - PHASE 2

DEMOLITION PLAN

Designed by: JHP
Dwn by: JDL
Ckd by:
Reviewed by:
Submitted by: MOFFATT & NICHOL
Date:
Rev. 0
M&N Project No. 5531-264B
GPA Project No.: 1910-1011C
Drawing Scale: AS NOTED
Plot scale: 1:1 (D SHEET)

moffatt & nichol
2 EAST BRYAN ST., STE 501
SAVANNAH, GA 31401
912-231-0044

SEAL

Sheet Reference No.
CD109
INDEX: OF

File: Q:\SV\5531-264 2020 Capacity Improvements\600 CADD_Active_Phase2_2020 Peak_Civil\5531264-CD109 ; Plotted: 2/2/2021 5:34 PM by LEE, JAZMYN ; Saved: 1/23/2021 10:21 AM by JDLEE

Order Plans @ WWW.LDILine.com