

# SUMMARY OF QUANTITIES

LIGHTING ITEMS			
NO.	PAY ITEM	UNIT	QUANTITY
610-6610	REMOVE LUMINAIRE	EA	24
610-6865	REM SERVICE POLE RISER	EA	2
681-4354	LIGHTING STD, 35 FT MH, 12 FT ARM	EA	31
681-6200	LUMINAIRE, TP 2, LED	EA	31
681-6600	LUMINAIRE, TP A, LED	EA	4
682-1505	CABLE, TP RHH/RHW, AWG NO 8	LF	25210
682-1506	CABLE, TP RHH/RHW, AWG NO 6	LF	13145
682-1509	CABLE, TP RHH/RHW, AWG NO 2	LF	17960
682-6120	CONDUIT, RIGID, 2 IN	LF	110
682-6222	CONDUIT, NONMETL, TP 2, 2 IN	LF	13385
682-8500	ELECTRICAL POWER SERVICE ASSEMBLY (AERIAL SERVICE POINT)	LS	2
682-9021	ELECTRICAL JUNCTION BOX, CONC GROUND MOUNTED	EA	15
682-9950	DIRECTIONAL BORE - 2"	LF	1560
683-6675	HIGH LEVEL LUMINAIRE, TP 5, LED	EA	20

TEMPORARY PIPE		
LOCATION	18" PIPE	FLARED END SECTION
STA. 23+43, 70.5' LT	24'	1
STA. 43+00, 68.0' RT	80'	2
STA. 203+66, 42.3' LT	44'	1

<b>GRADING COMPLETE - 0009975</b> ITEM: 210-0100		
<b>TOTAL</b>	1	LS

<b>LANDSCAPE MULCH</b> ITEM: 702-9025		
<b>TOTAL</b>	1300	SO. YD.

<b>CRATAEGUS VIRIDIS</b> ITEM: 702-0212		
<b>TOTAL</b>	9	EA

<b>SAWED JTS IN EXIST PVMTS - PCC</b> ITEM: 444-1000		
<b>TOTAL</b>	325	LF

<b>ILEX VOMITORIA NANA</b> ITEM: 702-0470		
<b>TOTAL</b>	490	EA

<b>FIELD FENCE WOVEN WIRE</b> ITEM: 643-0010		
<b>TOTAL</b>	3000	LF

<b>SPRING APPLICATION FERTILIZER</b> ITEM: 702-9005		
<b>TOTAL</b>	2800	LB

<b>PVMT REF FAB STRIPS, TP2,</b> <b>18 IN WIDTH - ITEM: 446-1100</b>		
<b>TOTAL</b>	4500	LF

<b>LANDSCAPE MULCH</b> ITEM: 702-9025		
<b>TOTAL</b>	1300	SO. YD.

<b>FIELD ENGINEERS OFFICE TP 3</b> ITEM: 153-1300		
<b>TOTAL</b>	1	LS

<b>GPS DATA COLLECTION AND SUBMITTAL</b> ITEM: 156-0100		
<b>TOTAL</b>	1	LS

Order Plans @ [WWW.WWEDILING.COM](http://WWW.WWEDILING.COM)

**Kimley»Horn**

Engineering, Planning, and Environmental Consultants  
Suite 350, 3930 East Jones Bridge Road  
Peachtree Corners, Georgia 30092

REVISION DATES	

**SUMMARY QUANTITIES**  
**1-85 @ SR 18 & SR 18 @ SR 103**

CHECKED:	DATE:	DRAWING No.
BACKCHECKED:	DATE:	06-0002
CORRECTED:	DATE:	
VERIFIED:	DATE:	