SUMMARY OF QUANTITIES

DRAINAGE ITEMS CONTINUED

Structure ID	Catch Basin			Drop Inlet			Manhole	9031s	Flared End Section, Side Drain	Flared End Section, Storm Drain				Safety End Section, Side Drain	Outlet Headwall (class A conc including reinf steel)			Headwall (Class B conc)					Side Drain Pipe	Remove Pipe	
	668-1100	668-1200	668-1110	668-2100	668-2200	668-2110	668-4300	668-2100	550-4118	550-4218	550-4224	550-4236	550-4230	550-3318	500-3800			500-3900	550-1180	550-1240	550-1300	550-1360	550-2180	610-0959	
	GP 1	GP 2	Addl Depth	GP 1	GP 2	Addl Depth			18"	18"	24"	36"	30"	18"	18"	24"	30"	36"	18"	24"	30"	36"	18"	18"	30"	36"
D-01	1		2.75																101.8							
D-02	1		0.50																58.5							
D-03				1															47.1							
D-04				1															58.5							
D-05				1															34.6						105.77	
D-06				1																45.00						
D-07											1															
D-08													1								65.2					
D-09				2		0.80															100.3					
D-10				2																	94.7					
D-11	1		0.20																		37.4					
D-12	1		0.40																		19.6					
D-13	1		0.60																		19.8					
D-14	1		0.85																		19.9					
D-15	1		1.80																		64.9					
D-16				1		2.60																53.6				
D-17	1		3.90																			106.4				106.81
D-18													1													
D-19													1									55.3				
D-21										1										44.2						
D-24				1		5.20																60.6				
D-25				2															12.3							
D-26				1															12.1							
D-27				1		6.00																44.7				
D-28												1														
D-29				1															12.4							
D-30				2															15.0							
D-31				1															52.0							
D-32	1																		86.0							
D-33	1		3.70																37.0							
D-34										1																
Sheet Total	10	0	14.7	18	0	14.60	0	0	0	1	1	1	3	0	0			0.00	527.3	89.2	428.8	320.6	0.00	0.00	105.77	106.81

RIP RAP		
STRUCTURE NUMBER	603-2024 24" TP. 1 SQ. YD.	603-2181 18" TP. 3 SQ. YD.
A-04		8
A-06		4
B-08		4
B-10		4
B-12		4
C-02		4
C-04		4
C-06		4

RIP RAP		
STRUCTURE NUMBER	603-2024 24" TP. 1 SQ. YD.	603-2181 18" TP. 3 SQ. YD.
C-07		4
D-07		10
D-18		15
D-21		4
D-28		36
D-29		4
E-18		17
F-15		23
F-24		4
F-25		8
5X6 BC	76	
TOTAL	76	161

BOX CULVERT

STATION	SKEW	LENGTH (LF)	SIZE (FT X FT)	BARREL		WINGWALLS		APRON GA STD 2406		FOUNDATION BACKFILL MAT'L TP II (CY)	GEORGIA STANDARD
				CLASS "AA" CONCRETE (CY)	BAR REINF. STEEL (LB)	CLASS "AA" CONCRETE (CY)	BAR REINF. STEEL (LB)	CLASS "AA" CONCRETE (CY)	BAR REINF. STEEL (LB)		GA STD 2401-1 GA STD 2401-2-C GA STD 2401-3 GA STD 2317 GA STD 2406
SB ENTRANCE RAMP STA 301+50	85°	28.70	5' X 6'	18.3	2537.08	2.8	533.0	3.4	259.0	5.0	
TOTALS				18.3	2537.08	2.8	533.0	3.4	259.0	5.0	
				500-3101	511-1000	500-3101	511-1000	500-3101	511-1000	207-0203	

CAPPING MINOR STRUCTURE ITEM: 611-9000		
TOTAL	4	EA

CONST. & REM. TEMP PIPE SLOPE DRAIN ITEM: 163-0520		
TOTAL	150	LF

Order Plans @ www.LDLine.com

Kimley»Horn
Engineering, Planning, and Environmental Consultants
Suite 350, 3930 East Jones Bridge Road
Peachtree Corners, Georgia 30092

REVISION DATES

SUMMARY QUANTITIES
I-85 @ SR 18 & SR 18 @ SR 103

CHECKED: DATE:
BACKCHECKED: DATE:
CORRECTED: DATE:
VERIFIED: DATE:

DRAWING No. 06-0005