

SUMMARY OF QUANTITIES

STATION	LOCATION	INSTL. NO.	SIGN CODE	HIGHWAY SIGNS (REFLECTIVE SHEETING TYPE IX)						HIGHWAY SIGNS (REFLECTIVE SHEETING TYPE XI)						SQUARE TUBE POST						BREAKAWAY SIGN SUPPORT (EACH)			
				TP 1 MATL. REFL SHEETING TP 9			TP 2 MATL. REFL SHEETING TP 9			TP 1 MATL. REFL SHEETING TP 11			TP 2 MATL. REFL SHEETING TP 11			TYPE 7			TYPE 8				TYPE 9 INSERT		
				SIZE	QUAN	SQ FT	SIZE	QUAN	SQ FT	SIZE	QUAN	SQ FT	SIZE	QUAN	SQ FT	LENGTH (FT)	QUAN	TOTAL (FT)	LENGTH (FT)	QUAN	TOTAL (FT)		LENGTH (FT)	QUAN	TOTAL (FT)
STA 15+01	SR 18 EB OVERHEAD	1	M-SPECIAL R3-5A	30" X 36"	1	7.50																			
STA 15+01	SR 18 EB OVERHEAD	2	M-SPECIAL R3-5A	30" X 36"	1	7.50																			
STA 15+01	SR 18 EB ENTRY OVERHEAD	3	M-SPECIAL R3-5R	30" X 36"	1	7.50																			
STA 15+44	SR 18 EB SHLDR	4	W12-1																						
STA 15+73	SR 18 EB SHLDR	5	W11-2 W16-7P														14.5	1	14.5						
STA. 15+76		6	W11-2 W16-7P														14.5	1	14.5						
STA 15+91	SR 18 EB SHLDR	7	W11-2 W16-7P														14.5	1	14.5						
STA 305+29	SR 18 WB SHLDR	8	W11-2 W16-7P														14.5	1	14.5						
STA 16+16	SR 18 EB MEDIAN	9	R1-2																						
STA 16+16	SR 18 BYPASS ISLAND	10	R1-2														13	1	13						
STA 305+24	SB ON RAMP	11	M3-3 M1-1 M6-2	24" X 12"	1	2.00																			
STA 17+05	SR 18 CENTRAL ISLAND	12	R6-4B				60" X 24"	1	10.00								12	2	24						
STA 17+77	SR 18 MEDIAN	13	M4-5 M3-1 M1-1 M3-2 M1-5 M6-2	24" X 12"	1	2.00											18	1	18						
STA 18+52	SR 18 EB EXIT OVERHEAD	14	R3-5A M-SPECIAL	30" X 36"	1	7.50																			
STA 18+52	SR 18 EB EXIT OVERHEAD	15	M-SPECIAL R3-6L MOD	30" X 36"	1	7.50																			
STA. 18+52	SR 18 WB OVERHEAD	16	M-SPECIAL R3-6L MOD	30" X 36"	1	7.50																			
STA. 18+52	SR 18 WB OVERHEAD	17	M-SPECIAL R3-5A	30" X 36"	1	7.50																			
STA 16+25	SR 18 WB SHLDR	18	M3-4 M1-5 M6-2	24" X 12"	1	2.00											15	1	15						
TOTAL						158			10			78				63		106				0		0	

Order Plans @ WWW.LDILine.com

Kimley»Horn
Engineering, Planning, and Environmental Consultants
Suite 350, 3930 East Jones Bridge Road
Peachtree Corners, Georgia 30092

REVISION DATES

SUMMARY QUANTITIES
1-85 @ SR 18 & SR 18 @ SR 103

CHECKED:	DATE:	DRAWING No.
BACKCHECKED:	DATE:	06-0007
CORRECTED:	DATE:	
VERIFIED:	DATE:	