

SUMMARY OF QUANTITIES

STATION	LOCATION	INSTL. NO.	SIGN CODE	HIGHWAY SIGNS (REFLECTIVE SHEETING TYPE IX)						HIGHWAY SIGNS (REFLECTIVE SHEETING TYPE XI)						SQUARE TUBE POST									BREAKAWAY SIGN SUPPORT (EACH)
				TP 1 MATL. REFL SHEETING TP 9			TP 2 MATL. REFL SHEETING TP 9			TP 1 MATL. REFL SHEETING TP 11			TP 2 MATL. REFL SHEETING TP 11			TYPE 7			TYPE 8			TYPE 9			
				SIZE	QUAN	SQ FT	SIZE	QUAN	SQ FT	SIZE	QUAN	SQ FT	SIZE	QUAN	SQ FT	LENGTH (FT)	QUAN	TOTAL (FT)	LENGTH (FT)	QUAN	TOTAL (FT)	LENGTH (FT)	QUAN	TOTAL (FT)	
STA 400+99	SB EXIT RAMP	19	R1-2							36" TRI	1	9.00				13	1	13							
STA 400+87	SB EXIT RAMP	20	R1-2							36" TRI	1	9.00				13	1	13							
STA 401+31	SB EXIT RAMP BYPASS ISLAND	21	R1-2							36" TRI	1	9.00				13	1	13							
STA 401+25	SB EXIT RAMP BYPASS ISLAND	22	R1-2							36" TRI	1	9.00				13	1	13							
STA 401+59	SB EXIT RAMP	23	W11-2							36" X 36"	1	9.00							14.5	1	14.5				
			W16-7P							30" X 18"	1	3.75													
STA 401+10	SB EXIT RAMP	24	W11-2							36" X 36"	1	9.00							14.5	1	14.5				
			W16-7P							30" X 18"	1	3.75													
STA 401+25	SB EXIT RAMP	25	R5-1							36" X 36"	1	9.00				13	1	13							
STA 401+27	SB EXIT RAMP BYPASS ISLAND	26	R5-1							36" X 36"	1	9.00				13	1	13							
STA 401+32	SR 18 WB SHLDR	27	R3-1	24" X 24"	1	4.00										12	1	12							
STA 17+02	SR 18 CENTRAL ISLAND	28	R6-4B				60" X 24"	1	10.00							12	2	24							
STA 17+36	SR 18 CENTRAL ISLAND	29	R6-4B				60" X 24"	1	10.00							12	2	24							
STA 17+83	SR 18 WB MEDIAN	30	R1-2							36" TRI	1	9.00				13	1	13							
STA 17+83	SR 18 SHLDR	31	R1-2							36" TRI	1	9.00				13	1	13							
STA 304+83	SB ENTRANCE RAMP	32	W4-1										48" X 48"	1	16.00				14	1	14				
STA 20+70	SR 18 EB ENTRY OVERHEAD	33	R3-5A	30" X 36"	1	7.50																			
			M-SPECIAL	30" X 36"	1	7.50																			
STA 20+70	SR 18 EB ENTRY OVERHEAD	34	M-SPECIAL	30" X 36"	1	7.50																			
			R3-6L MOD	30" X 36"	1	7.50																			
			M-SPECIAL	30" X 36"	1	7.50																			
STA 21+06	SR 18 EB SHLDR	35	R1-2							36" TRI	1	9.00				13	1	13							
STA 20+98	SR 18 EB MEDIAN	36	R1-2							36" TRI	1	9.00				13	1	13							
STA 21+42	SR 18 EB SHLDR	37	R3-1	24" X 24"	1	4.00										12	1	12							
STA 21+54	SR 18 EB SHLDR	38	R5-1							36" X 36"	1	9.00				13	1	13							
STA 21+62	NB EXIT RAMP	39	R1-2							36" TRI	1	9.00				13	1	13							
STA 22+02	NB EXIT RAMP BYPASS ISLAND	40	R1-2							36" TRI	1	9.00				13	1	13							
STA 511+91	NB EXIT RAMP	41	W11-2							36" X 36"	1	9.00							14.5	1	14.5				
			W16-7P							30" X 18"	1	3.75													
STA 520+00	NB EXIT RAMP	42	W11-2							36" X 36"	1	9.00							14.5	1	14.5				
			W16-7P							30" X 18"	1	3.75													
STA 21+60	SR 18 CENTRAL ISLAND	43	R6-4B				60" X 24"	1	10.00							12	2	24							
STA 21+97	SR 18 CENTRAL ISLAND	44	R6-4B				60" X 24"	1	10.00							12	2	24							
STA 21+92	SR 18 CENTRAL ISLAND	45	R6-4B				60" X 24"	1	10.00							12	2	24							
STA 22+15	NB EXIT RAMP BYPASS ISLAND	46	R5-1							36" X 36"	1	9.00				13	1	13							
STA 22+35	NB EXIT RAMP BYPASS ISLAND	47	R1-2							36" TRI	1	9.00				13	1	13							
STA 22+61	NB EXIT RAMP BYPASS ISLAND	48	R1-2							36" TRI	1	9.00				13	1	13							
STA 23+30	SR 18 EB SHLDR	49	W11-2							36" X 36"	1	9.00							14.5	1	14.5				
			W16-7P							30" X 18"	1	3.75													
STA 22+60	SR 18 EB MEDIAN	50	M3-2	24" X 12"	1	2.00													15	1	15				
			M1-5	24" X 24"	1	4.00																			
			M6-2	24" X 24"	1	4.00																			
STA 24+54	SR 18 EB SHLDR	51	R3-9B	24" X 36"	1	6.00										13	1	13							
TOTAL						62			50			208						365			102			0	0

Order Plans @ www.lidline.com

Kimley»Horn

Engineering, Planning, and Environmental Consultants
Suite 350, 3930 East Jones Bridge Road
Peachtree Corners, Georgia 30092

REVISION DATES

SUMMARY QUANTITIES
1-85 @ SR 18 & SR 18 @ SR 103

CHECKED:	DATE:	DRAWING No.
BACKCHECKED:	DATE:	06-0008
CORRECTED:	DATE:	
VERIFIED:	DATE:	