

SUMMARY OF QUANTITIES

STATION	LOCATION	INSTL. NO.	SIGN CODE	HIGHWAY SIGNS (REFLECTIVE SHEETING TYPE IX)						HIGHWAY SIGNS (REFLECTIVE SHEETING TYPE XI)						SQUARE TUBE POST									BREAKAWAY SIGN SUPPORT (EACH)
				TP 1 MATL. REFL SHEETING TP 9			TP 2 MATL. REFL SHEETING TP 9			TP 1 MATL. REFL SHEETING TP 11			TP 2 MATL. REFL SHEETING TP 11			TYPE 7			TYPE 8			TYPE 9			
				SIZE	QUAN	SQ FT	SIZE	QUAN	SQ FT	SIZE	QUAN	SQ FT	SIZE	QUAN	SQ FT	LENGTH (FT)	QUAN	TOTAL (FT)	LENGTH (FT)	QUAN	TOTAL (FT)	LENGTH (FT)	QUAN	TOTAL (FT)	
STA 23+82	SR 18 WB SHLDR	52	M3-2	36" X 18"	1	4.50											14.5	1	14.5						
			M1-5	36" X 36"	1	9.00																			
STA 25+15	SR 18 MEDIAN NOSE	53	R4-7				36"X48"	1	12								17	1	17						
			OM3-R							12" X 36"	1	2.25													
STA 20+70	SR 18 EB EXIT OVERHEAD	54	R3-5A	30" X 36"	1	7.50																			
			M-SPECIAL	30" X 36"	1	7.50																			
STA 20+70	SR 18 EB EXIT OVERHEAD	55	M-SPECIAL	30" X 36"	1	7.50																			
			R3-6L MOD	30" X 36"	1	7.50																			
			M-SPECIAL	30" X 36"	1	7.50																			
STA 21+01	SR 18 MEDIAN	56	M4-5	24" X 12"	1	2.00											18	1	18						
			M3-3	24" X 12"	1	2.00																			
			M1-1	24" X 24"	1	4.00																			
			M3-4	24" X 12"	1	2.00																			
			M1-5	24" X 24"	1	4.00																			
			M6-2	24" X 24"	1	4.00																			
STA 600+86	NB ENTRANCE RAMP	57	M3-1	24" X 12"	1	2.00											16	1	16						
			M1-1	24" X 24"	1	4.00																			
			M6-2	24" X 24"	1	4.00																			
STA 22+67	SR 18 WB MEDIAN	58	R1-2							36" TRI	1	9.00				13	1	13							
STA 22+79	SR 18 WB BYPASS ISLAND	59	R1-2							36" TRI	1	9.00				13	1	13							
STA 600+73	SR 18 WB BYPASS ISLAND	60	R1-2							36" TRI	1	9.00				13	1	13							
STA 601+08	SR 18 WB SHLDR	61	R1-2							36" TRI	1	9.00				13	1	13					1		
STA 22+80	SR 18 WB BYPASS ISLAND	62	W11-2							30" X 18"	1	3.75					14.5	1	14.5						
			W16-7P							30" X 18"	1	3.75													
STA 23+72	SR 18 WB BYPASS ISLAND	63	W11-2							36" X 36"	1	9.00					14.5	1	14.5						
			W16-7P							30" X 18"	1	3.75													
STA 23+10	SR 18 WB BYPASS ISLAND	64	W11-2							36" X 36"	1	9.00					14.5	1	14.5						
			W16-7P							30" X 18"	1	3.75													
STA 23+93	SR 18 BYPASS ISLAND	65	W12-1							36" X 36"	1	9.00				13	1	13							
STA 24+54	SR 18 WB ENTRY OVERHEAD	66	R3-5R	30" X 36"	1	7.50																			
			M-SPECIAL	30" X 36"	1	7.50																			
STA 24+54	SR 18 WB ENTRY OVERHEAD	67	R3-5A	30" X 36"	1	7.50																			
			M-SPECIAL	30" X 36"	1	7.50																			
STA 24+54	SR 18 WB ENTRY OVERHEAD	68	R3-5A	30" X 36"	1	7.50																			
			M-SPECIAL	30" X 36"	1	7.50																			
			M-SPECIAL	30" X 36"	1	7.50																			
STA 24+53		69	W2-6							36" X 36"	1	9.00					15	1	15						
			W2-1							24" X 24"	1	4.00													
STA 27+18	SR 18 EB SHLDR	70	R2-7				36"X48"	1	12							14	2	28							
STA 29+65	SR 18 EB SHLDR	71	R3-9B	24" X 36"	1	6.00										13	1	13							
STA 25+50	SR 18 WB SHLDR	72	R3-9B	24" X 36"	1	6.00										13	1	13							
STA 30+50	SR 18 WB SHLDR	73	R3-9B	24" X 36"	1	6.00										13	1	13							
STA 32+00	SR 18 WB SHLDR	74	M2-1	30" X 21"	1	4.38											15	1	15						
			M1-1	36" X 36"	1	9.00																			
STA 37+00	SR 18 EB SHLDR	75	M1-5				45"X36"	1	11.25							15	2	30							
			M2-1	30" X 21"	1	4.38																			
STA 37+00	SR 18 EB SHLDR	76	R3-7R	36" X 36"	1	9.00										13	1	13							
STA 39+80	SR 18 WB SHLDR	77	W2-6							36" X 36"	1	9.00					15	1	15						
			W13-1							24" X 24"	1	4.00													
TOTAL						176			35			112				175		154			0		1		

Order Plans @ WWW.LDILINE.COM

Kimley»Horn
Engineering, Planning, and Environmental Consultants
Suite 350, 3930 East Jones Bridge Road
Peachtree Corners, Georgia 30092

REVISION DATES		SUMMARY QUANTITIES	
		1-85 @ SR 18 & SR 18 @ SR 103	
CHECKED:	DATE:	DRAWING No.	
BACKCHECKED:	DATE:	06-0009	
CORRECTED:	DATE:		
VERIFIED:	DATE:		