

# SUMMARY OF QUANTITIES

STATION	LOCATION	INSTL. NO.	SIGN CODE	HIGHWAY SIGNS (REFLECTIVE SHEETING TYPE IX)						HIGHWAY SIGNS (REFLECTIVE SHEETING TYPE XI)						SQUARE TUBE POST									BREAKAWAY SIGN SUPPORT (EACH)
				TP 1 MATL. REFL SHEETING TP 9			TP 2 MATL. REFL SHEETING TP 9			TP 1 MATL. REFL SHEETING TP 11			TP 2 MATL. REFL SHEETING TP 11			TYPE 7			TYPE 8			TYPE 9			
				SIZE	QUAN	SQ FT	SIZE	QUAN	SQ FT	SIZE	QUAN	SQ FT	SIZE	QUAN	SQ FT	LENGTH (FT)	QUAN	TOTAL (FT)	LENGTH (FT)	QUAN	TOTAL (FT)	LENGTH (FT)	QUAN	TOTAL (FT)	
STA 40+90	SR 18 WB SHLDR	78	R2-1				36" X 48"	1	12.00							14	2	28							
STA. 42+00		79	R3-9B	24" X 36"	1	6.00										13	1	13							
STA 42+45	SR 18 MEDIAN NOSE	80	R4-7 OM3-R				36" X 48"	1	12.00										17	1	17				
STA. 42+90		81	R6-2R	24" X 36"	1	6.00										13	1	13							
STA 43+00	SR 18 WB SHLDR	82	M3-4 M1-5	36" X 18"	1	4.50													14.5	1	14.5				
STA 42+25	SR 18 EB SHLDR	83	R3-7R	36" X 36"	1	9.00										13	1	13							
STA 43+60	SR 18 EB SHLDR	84	W12-1							36" X 36"	1	9.00				13	1	13							
STA 44+10	SR 18 BYPASS ISLAND	85	W11-2 W16-7P							36" X 36"	1	9.00							14.5	1	14.5				
STA 44+16	SR 18 EB SHLDR	86	W11-2 W16-7P							30" X 18"	1	3.75							14.5	1	14.5				
STA 44+35	SR 18 WB SHLDR	87	W11-2 W16-7P							36" X 36"	1	9.00							14.5	1	14.5				
STA 44+74	SR 18 MEDIAN	88	R1-2							30" X 18"	1	3.75													
STA 44+79	SR 18 BYPASS ISLAND	89	R1-2							36" TRI	1	9.00				13	1	13							
STA 205+55	SR 103 MEDIAN	90	M3-3 M1-5	24" X 12"	1	2.00													14.5	1	14.5				
			M6-2R	24" X 24"	1	4.00																			
STA 205+05	SR 103 NB SHLDR	91	W11-2 W16-7P	21" X 15"	1	2.19				36" X 36"	1	9.00							14.5	1	14.5				
STA 205+29	SR 103 MEDIAN	92	W11-2 W16-7P							30" X 18"	1	3.75							14.5	1	14.5				
STA 205+51	SR 103 MEDIAN	93	R1-2							30" X 18"	1	3.75													
STA 205+52	SR 103 NB SHLDR	94	R1-2							36" TRI	1	9.00				13	1	13							
STA 44+80	SR 18 MEDIAN	95	M3-4 M1-5 M6-2	24" X 12"	1	2.00													15	1	15				
				24" X 24"	1	4.00																			
STA 45+25	SR 18 CENTRAL ISLAND	96	R6-4B				60" X 24"	1	10.00							12	2	24							
STA 45+46	SR 18 CENTRAL ISLAND	97	R6-4B				60" X 24"	1	10.00							12	2	24							
STA 206+00	SR 18 CENTRAL ISLAND	98	R6-4B				60" X 24"	1	10.00							12	2	24							
STA 46+14	SR 18 WB SHLDR	99	R1-2							36" TRI	1	9.00				13	1	13							
STA 46+21	SR 18 MEDIAN	100	R1-2							36" TRI	1	9.00				13	1	13							
STA 46+19	SR 18 MEDIAN	101	M3-2 M1-5 M6-2	24" X 12"	1	2.00													15	1	15				
				24" X 24"	1	4.00																			
				21" X 15"	1	2.19																			
STA 48+00	SR 18 EB SHLDR		M3-2 M1-5	36" X 18"	1	4.50													14.5	1	14.5				
				36" X 36"	1	9.00																			
STA 50+00	SR 18 EB SHLDR	103	R2-1				36" X 48"	1	12.00							14	2	28							
STA 49+72	SR 18 WB SHLDR	104	W2-6 W13-1							36" X 36"	1	9.00							15	1	15				
										24" X 24"	1	4.00													
STA 48+18	SR 18 MEDIAN NOSE	105	R4-7 OM3-R				36" X 48"	1	12.00										17	1	17				
										12" X 36"	1	2.25													
STA 53+00	SR 18 WB SHLDR	106	M2-1 M1-5	30" X 21"	1	4.38										15	2	30							
							45" X 36"	1	11.25																
STA 199+50	SR 103 NB SHLDR	107	M2-1 M1-5	30" X 21"	1	4.38													15	1	15				
				36" X 36"	1	9.00																			
<b>TOTAL</b>						<b>92</b>			<b>89</b>			<b>144</b>						<b>288</b>			<b>210</b>			<b>0</b>	

Order Plans @ [www.lidilinc.com](http://www.lidilinc.com)

**Kimley»Horn**  
Engineering, Planning, and Environmental Consultants  
Suite 350, 3930 East Jones Bridge Road  
Peachtree Corners, Georgia 30092

**REVISION DATES**


**SUMMARY QUANTITIES**  
**1-85 @ SR 18 & SR 18 @ SR 103**

CHECKED:	DATE:	DRAWING No.
BACKCHECKED:	DATE:	06-0010
CORRECTED:	DATE:	
VERIFIED:	DATE:	