


STATE	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.			



- GENERAL NOTES:**
- SPECIFICATIONS: GA. STANDARD CURRENT EDITION & SUPPLEMENTS THERETO
 - DIMENSIONS ARE SUBJECT TO MANUFACTURING TOLERANCES.
 - NET LENGTH OF RAIL ELEMENTS MAY BE EITHER 12'-6" OR 25'-0".
 - RAIL ELEMENTS ON CURVES OF RADII LESS THAN 150' WILL BE PRECURVED.
 - PAYMENT FOR GUARDRAIL (TYPE "T") WILL INCLUDE ALL POSTS, BLOCKS, HARDWARE ACCESSORIES AND WHERE REQUIRED ALL ADDITIONAL POSTS, END SHOES, TERMINAL SECTIONS, TRANSITION SECTIONS, BACK-UP PLATES AND REMOVAL AND REPLACEMENT OF PORTIONS OF MEDIAN PAVING, SPILLWAYS OR CATCH BASINS WHERE NECESSARY.
 - ALL GUARDRAIL TERMINALS SHALL REQUIRE AN APPROVED ANCHORAGE AS SPECIFIED IN THE PLANS OR APPROVED BY THE ENGINEER EXCEPT WHERE CONNECTED TO A BRIDGE END OR OTHER CONCRETE FACE.
 - NUTS, BOLTS AND WASHERS WHICH ARE NOT DETAILED ON THIS STANDARD, SHALL BE AS SHOWN FOR W BEAM GUARDRAIL ON STANDARD 4380.
 - SEE SEPARATE STANDARDS AS APPLICABLE FOR ANCHORAGES, POSTS, OFFSET BLOCKS, CONNECTIONS TO CONCRETE FACE, W BEAM GUARDRAIL, ETC.
 - SEE STANDARD 4381 FOR DETAILS AND REQUIREMENTS OF BACK-UP PLATES, WHERE STEEL OFFSET BLOCKS ARE ALLOWED OR SPECIFIED.
 - OFFSET BLOCKS SHALL BE PLASTIC UNLESS OTHERWISE APPROVED OR SPECIFIED.

DATE	DEPARTMENT OF TRANSPORTATION STATE OF GEORGIA		NUMBER
REVISION	STANDARD "T" BEAM GUARDRAIL CONNECTION TO 31 INCH HEIGHT "W" BEAM		4385
	NO SCALE	AUGUST 2011	
DES. G.L.O. (SUBMITTED)	BY STATE DESIGN POLICY ENGINEER		
DRW. G.L.O.	CHK. B.R.E. (APPROVED)		
REVIEW B.A.S.	CHIEF ENGINEER		

Order plans @ WWW.DLINE.COM