




Facilities Management
1161 West Samford Avenue
Auburn University, AL 36849
Phone: (334) 844-4810
Fax: (334) 844-9458
Safety is our first priority.
Think Safety. Act Safely.

No.	Revision	Date
-	-	00/00/00



JMR-H Architecture, P.C.
440 Geneva Avenue
Montgomery, AL 36104
Phone: (334) 420-5672
Fax: (334) 420-5692
JMR-H Project Number: 19-968
Drawn By: DT

Auburn University Building
Ham Wilson Arena Renovations
Project Number 19-451

SHEET TITLE:
FINISH &
DOOR
SCHEDULES

DRAWN BY:
LC

CHECKED BY:

DATE:
JANUARY 21, 2021

FILE NUMBER:
-

PROJECT NUMBER:
19-451

SHEET NUMBER:
A2.1

23 of 61

DOOR SCHEDULE									
NO.	TYPE	SIZE	FRAME TYPE	HDW SET	LABEL	GLASS TYPE	REMARKS		
LOWER FLOOR									
101	C	8'-0"X8'-0"	----	04	----	----	3		
102	C	7'-0"X7'-0"	----	04	----	----	3		
103	A	PR. 3'-0"X7'-0"X1 3/4"	----	08	----	----	3		
104	C	9'-0"X8'-0"	----	04	----	----	3		
105	EXIST	EXISTING	N/A	EX-02	----	----	1,2,4		
106	A	3'-0"X4'-6"X1 3/4"	3	09	----	----	5		
UPPER FLOOR									
201	D	3'-0"X7'-0"X1 3/4"	1	03	----	----	1		
202	D	3'-0"X7'-0"X1 3/4"	1	03	----	----	1		
203	E	3'-0"X7'-0"X1 3/4"	1	02	----	----	1		
204	B	3'-0"X7'-0"X1 3/4"	S2	AL-01	----	----	1		
205	A	3'-0"X7'-0"X1 3/4"	1	01	----	----	1		
206	B	PR. 3'-0"X7'-0"X1 3/4"	S4	AL-01	----	----	1	6	
207	EXIST	EXISTING	N/A	EX-07	----	----	4		
208	B	PR. 3'-0"X7'-0"X1 3/4"	N/A	AL-01	----	----	1	7	
209	D	3'-0"X7'-0"X1 3/4"	1	X-01	----	----	4		
210	EXIST	EXISTING	N/A	EX-02	----	----	4		
211	EXIST	EXISTING	N/A	EX-02.1	----	----	4		
212	EXIST	EXISTING	N/A	EX-06	----	----	4		
213	EXIST	EXISTING	N/A	EX-06	----	----	4		
214	EXIST	EXISTING	N/A	EX-04	----	----	4		
215	EXIST	EXISTING	N/A	EX-05	----	----	4		
216	EXIST	EXISTING	N/A	EX-08	----	----	4		
217	EXIST	EXISTING	N/A	EX-08	----	----	4		
218	EXIST	EXISTING	N/A	EX-02	----	----	4		
219	A	3'-6"X7'-0"X1 3/4"	1	07	----	----	4		
220	A	PR. 3'-6"X7'-0"X1 3/4"	2	06	----	----	4		
UPPER FLOOR - ALTERNATE									
01A	E	3'-0"X7'-0"X1 3/4"	1	05	----	----	1		
02A	E	3'-0"X7'-0"X1 3/4"	1	05	----	----	1		
03A	A	3'-6"X7'-0"X1 3/4"	1	07A	----	----	1		
04A	A	PR. 3'-6"X7'-0"X1 3/4"	2	06A	----	----	1		
REMARKS									
1	EXISTING DOOR AND FRAME TO BE PAINTED								
2	NEW HARDWARE ON EXISTING DOOR								
3	INSULATED ROLL UP DOOR - MANUAL OPERATION								
4	WHERE NEW HARDWARE IS INSTALLED IN EXISTING FRAMES, CONTRACTOR SHALL FILL, SAND, PRIME AND PAINT ALL EXISTING HOLES NOT COVERED BY NEW HARDWARE								
5	THIS IS A NEW DOOR AND FRAME IN AN EXISTING OPENING. VERIFY SIZE IN FIELD								
6	THIS IS AN EXISTING OPENING WITH NEW DOOR, FRAME AND HARDWARE. VERIFY SIZE IN FIELD. DOOR TO HAVE ACCESS CONTROL AND ADA OPERATION								
7	THIS IS AN EXISTING OPENING WITH NEW DOOR, FRAME AND HARDWARE. VERIFY SIZE IN FIELD. DOOR TO HAVE ADA OPERATION								
MARK GLAZING LEGEND									
1	1/2" CLEAR TEMPERED INSULATED								

