

SUMMARY OF QUANTITIES

SILT FENCE TYPE A (NON-SENSITIVE)		
TOTAL	10930	LF

MAINTENANCE OF TEMPORARY SILT FENCE TYPE A (NON-SENSITIVE)		
TOTAL	5465	LF

ORANGE BARRIER FENCE		
TOTAL	21675	LF

INLET SEDIMENT TRAPS		
TOTAL	99	EACH

MAINTENANCE OF INLET SEDIMENT TRAP		
TOTAL	99	LF

TRAFFIC SIGNAL INSTALLATION NO. 1	
LUMP	

TRAFFIC SIGNAL INSTALLATION NO. 2	
LUMP	

TRAFFIC SIGNAL INSTALLATION NO. 3	
LUMP	

TRAFFIC SIGNAL INSTALLATION NO. 4	
LUMP	

TESTING - (TRAFFIC SIGNAL)	
LUMP	

WATER QUALITY MONITORING AND SAMPLING		
TOTAL	2	EACH

WATER QUALITY INSPECTION		
TOTAL	18	MONTH

GRASSING		
ITEM	UNIT	TOTAL
SOD	SY	13165
TEMPORARY GRASSING	ACRES	11
AGRICULTURAL LIME	TONS	6
FERTILIZED NITROGEN CONTENT	LBS	284
FERTILIZER MIXED GRADE	TONS	1
MULCH	TONS	17

CONSTRUCTION EXIT		
TOTAL	2	EACH

MAINTENANCE OF CONSTRUCTION EXIT		
TOTAL	4	EACH

DIRECTIONAL BORE, 3"		
QUANTITY	225	LIN FT

CONDUIT, NONMETAL TP 5, 1/2 IN		
QUANTITY	225	LIN FT

TRAFFIC SIGNAL TRAINING (PI 0010028)	
LUMP	

TRAINING - (TRAFFIC SIGNAL)	
LUMP	

WATER UTILITY RELOCATION ITEMS				
Pay Item & Description	Description	Qty	Unit	
670-1020 WATER MAIN, 2 IN (PVC, ASTM D-2241, SDR21)	Water Main, 2" (PVC, ASTM D-2241, SDR21)	66.0	LF	
670-1060 WATER MAIN, 6 IN (PVC, AWWA C900, DR18)	Water Main, 6" (PVC, AWWA C900 DR 18)	861.0	LF	
670-1060 WATER MAIN, 6 IN (D.I., AWWA C-151, PC 350)	Water Main 6" (D.I., AWWA C-151, PC 350)	285.0	LF	
670-1080 WATER MAIN, 8 IN (D.I., AWWA C-151, PC 350)	Water Main 8" (D.I., AWWA C-151, PC 350)	66.0	LF	
670-2003 AIR RELEASE VALVE ASSEMBLY, 2 IN	2" Air Release Valve in Manhole	1.0	EA	
670-2500 INSERTION VALVE - 2 IN	2" Inserted Valve in Manhole	4.0	EA	
670-7215 INSERTION VALVE, 6 IN	6" Inserted Valve in Manhole	25.0	EA	
670-7220 INSERTION VALVE, 8 IN	8" Inserted Valve in Manhole	2.0	EA	
670-3023 TAPPING SLEEVE & VALVE ASSEMBLY, 2 IN X 2 IN	2X2 Tapping Saddle and Valve in Manhole	3.0	EA	
670-3015 TAPPING SLEEVE & VALVE ASSEMBLY, 4 IN X 2 IN	4X2 Tapping Saddle and Valve in Manhole	15.0	EA	
670-3066 TAPPING SLEEVE & VALVE ASSEMBLY, 6 IN X 6 IN	6X6 Tapping Sleeve and Valve in Manhole	25.0	EA	
670-3087 TAPPING SLEEVE & VALVE ASSEMBLY, 8 IN X 8 IN	8X8 Tapping Sleeve and Valve in Manhole	2.0	EA	
670-2060 GATE VALVE, 6 IN	6" Gate Valve in Manhole	4.0	EA	
670-4000 FIRE HYDRANT	Fire Hydrant	2.0	EA	
670-9730 RELOCATE EXIST WATER METER, INCL BOX	Service Laterals	48.0	EA	
670-0203 FOUND BK FILL MATL, TP II	Stone Bedding/Sand Backfill	500.0	CY	
604-0000 FLOWABLE FILL - INCL ABANDON EXISTING PIPE IN PLACE	Abandon Existing 6" Water Main in Place and Fill Completely with Flowable Fill	1,099.00	AC	
610-2383 REMOVE WATER MAIN, 12 INCHES OR LESS (2")	Remove and Dispose of Existing 2" Water Main	28.00	LF	
610-2365 REMOVE WATER MAIN, 6 IN	Remove and Dispose of Existing 6" Water Main	185.00	LF	
610-2370 REMOVE WATER MAIN, 8 IN	Remove and Dispose of Existing 8" Water Main	38.00	LF	
670-9910 REMOVE EXIST WATER VALVE	Remove and Dispose of Existing 6" Valve in Manhole	2.00	EA	
660-3275 ABANDON MANHOLE	Abandon Existing Manhole	1	EA	
670-5850 RELOCATE WATER SAMPLING STATION	Relocate Water Quality Sampling Station	1	EA	
670-9710 RELOCATE EXIST FIRE HYDRANT	Remove and Relocate of Existing Fire Hydrant	5.00	EA	

Order Plans @ www.thomshut.com

THOMAS & HUTTON
Engineering | Surveying | Planning | GIS | Consulting
50 Park of Commerce Way • PO Box 2727
Savannah, GA 31402-2727 • 912.234.5300
www.thomasandhutton.com
Charleston, SC | Columbia, SC | Myrtle Beach, SC
Savannah, GA | Wilmington, NC

REVISION DATES

SUMMARY QUANTITIES
DELESSEPS/LA ROCHE AVE FM
WATERS AVE TO SKIDAWAY RD

CHECKED:	DATE:	DRAWING No.
BACKCHECKED:	DATE:	06-0003
CORRECTED:	DATE:	
VERIFIED:	DATE:	