SUMMARY OF QUANTITIES

STATION TO STATION	SECTION 654-RAISED PVMT MARKERS TYPE 1-10 (EA) Ty 1 Yel	Ty 2 Clr	Ty 3 Clr/red	Ty 10 Wht	SECTION 653-THERMOPLASTIC PAVEMENT MARKINGS: SYMBOLS Hndcp (ea)	RR (ea)	Bike Share Lane	Ty 4	ARROWS Ty I (ea)	Ty 2 (ea)	Ty 3 (ea)	Ty 4 (ea)	Ty 5 (ea)	Ty 6 (ea)	Ty 7 (ea)	Ty 8 (ea)
99+99.92 TO 102+00	3		4													
102+00 TO 108+00	15															
108+00 TO 114+00	26						1									
114+00 TO 120+00	24		15				5									
120+00 to 126+00	15		20				6									
126+00 to 132+00	20		5				4	1	1							
132+00 to 138+00	15							2	2							
138+00 to 144+00	15							2	3							
144+00 to 150+00	15							4	3							
150+00 to 155+50	15							2	2							
155+50 to 160+50	14							2	2							
160+50 to 166+50	15							2	2							
166+50 to 171+00	12		2					3	3							
171+00 to 173+19.33	4		8					1	1							
TOTAL	208	0	54	0	0	0	16	19	19	0	0	0	0	0	0	0

STATION TO STATION	SECTION 653 (cont.): SOLID WHITE TRAFFIC STRIPE (LF) 4"	5"	6"	8"	10"	12"	18"	24"	SOLID YELLOW TRAFFIC STRIPE (LF) 6"	8"	10"	18"	24"	SKIP WHITE TRAFFIC STRIPE (GLF) 5"	6"	8"	10"	18"	SKIP YELLOW TRAFFIC (GLF) 5"	TRAFFIC STRIPING (SY) Wht (sy)	Yel (sy)
99+99.92 TO 102+00				228																22	
102+00 TO 108+00				800																	
108+00 TO 114+00				400																	
114+00 TO 120+00				790																	
120+00 to 126+00																					
126+00 to 132+00		150		950																	176
132+00 to 138+00		1200		600											100						
138+00 to 144+00		1200																			
144+00 to 150+00		1200		800											300						
150+00 to 155+50		1200																			
155+50 to 160+50		1000		800											240						
160+50 to 166+50		1200		400											140						
166+50 to 171+00		900		800											470						
171+00 to 173+19.33		100		400											60					36	
TOTAL	0	8150	0	6968	0	0	0	0	0	0	0	0	0	0	1310	0	0	0	0	58	176

STATION TO STATION	SECTION 657-PREFORMED PLASTIC PAVEMENT MARKINGS: SYMBOLS Hnd	RR	WRONG WA	ARROWS Ty I (ea)	Ty 2 (ea)	Ty 3 (ea)	Ty 4 (ea)	Ty 5 (ea)	Ty 6 (ea)	Ty 7 (ea)	Ty 8 (ea)	12"	Ty 15	SOLID TRAFFIC STRIPE W/CONTRAST(LF) 8" Sd Bl-Wht	8" Sd Bl-Yel	11" Sd Wht	SKIP TRAFFIC STRIPE W /CONTRAST (LF) 24" SKIP WHT	TRAFFIC STRIPE Wht (sy)
99+99.92 TO 102+00					5								1					
102+00 TO 108+00																		
108+00 TO 114+00																		
114+00 TO 120+00					4								1					
120+00 to 126+00					3								2					
126+00 to 132+00					3													
132+00 to 138+00																		
138+00 to 144+00																		
144+00 to 150+00																		
150+00 to 155+50																		
155+50 to 160+50																		
160+50 to 166+50																		
166+50 to 171+00																		
171+00 to 173+19.33					2	2												
TOTAL	0	0	0	0	17	2	0	0	0	0	0	0	4	0	0	0	0	0

STATION TO STATION	SECTION 657 (cont.): SOLID WHITE STRIPE 4"	5"	10"	12"	18"	[illegible]	SOLID YELLOW STRIPE 5"	6"	8"	10"	18"	SKIP WHITE TRAFFIC STRIPING 24"	5"	6"	18"
99+99.92 TO 102+00		500				5[illegible]	400						50		
102+00 TO 108+00		1200				48	1340								
108+00 TO 114+00		1200				48	1200								
114+00 TO 120+00		1565				72	1200						50		
120+00 to 126+00		1080					1200						240		
126+00 to 132+00		1615				96	1475						100		
132+00 to 138+00		1200				24	1200								
138+00 to 144+00		1200					1200								
144+00 to 150+00		[illegible]				48	1200								
150+00 to 155+50		1200					1200								
155+50 to 160+50		1200				36	1200								
160+50 to 166+50		1200				24	1200								
166+50 to 171+00		900				36	900								
171+00 to 173+19.33		600				36	300								
TOTAL	0	15860	0	0	0	527	15215	0	0	0	0	0	440	0	0

Order Plans @ WWW.LDILine.com

THOMAS & HUTTON
Engineering | Surveying | Planning | GIS | Consulting
50 Park of Commerce Way • PO Box 2727
Savannah, GA 31402-2727 • 912.234.5300
www.thomasandhutton.com
Charleston, SC | Columbia, SC | Myrtle Beach, SC
Savannah, GA | Wilmington, NC

REVISION DATES

SUMMARY QUANTITIES

DELESSEPS/LA ROCHE AVE FM

WATERS AVE TO SKIDAWAY RD

CHECKED: DATE:
BACKCHECKED: DATE:
CORRECTED: DATE:
VERIFIED: DATE:

DRAWING No. 06-0011