









NOTES:
1. CATCH BASIN SHALL BE PRECAST CONCRETE. DESIGNED FOR HS20-44 VEHICULAR LOADING AND 25% IMPACT.
2. FRAME AND COVER SHALL BE DESIGNED FOR HS20-44 VEHICULAR LOADING & 25% IMPACT.
3. CONCRETE CATCH BASIN LID CLEAR OPENING DIMENSION MUST MATCH FRAME AND GRATE CLEAR OPENING DIMENSION.
4. CATCH BASINS HAVING A DEPTH GREATER THAN 48" FROM FINISHED SURFACE TO THE FLOOR OF THE CONCRETE BASE SHALL BE PROVIDED WITH STEPS.
5. BACKFILL USING TRENCH BACKFILL, COMPACTED IN 6" LIFTS.
6. SUMPS FOR CATCH BASINS SHALL BE 12".
7. ECCENTRIC CONC TOP CAN BE USED FOR MANHOLE'S DEPTH GREATER THAN 7 FEET.
8. SEE CHART FOR REQUIRED MANHOLES / CATCH BASINS DIAMETERS.
9. ALL PRECAST CONSTRUCTION IN ACCORDANCE W/ASTM C478

2 PRECAST CONCRETE CATCH BASIN/MANHOLE DETAIL
SCALE: NOT TO SCALE



NOTES:
1. SEWER PIPE FITTINGS TO BE ASTM D-3033 OR D-3034 SDR-35 PVC.
2. TO BE USED FOR GRAVITY PORTION OF SANITARY SYSTEM AS WELL AS THE STORM ROOF DRAINAGE SYSTEM.

12 CLEAN OUT - TRAFFIC AREAS
SCALE: NOT TO SCALE

ACCEPTABLE MANHOLE STEPS

MANUFACTURER	PATTERN NUMBER	A STEP WIDTH	B LEG LENGTH	C RUNG CLEAR	D EMBEDMENT	E RUNG CLEAR
M.A. INDUSTRIES INC*	PS2-PF	14 3/4	9 1/4	13 3/4	3 3/8	5 7/8
M.A. INDUSTRIES INC*	PS2-PFS	14 3/4	8 1/4	13 3/4	3 3/8	4 7/8

* OR EQUIVALENT
MH STEP DESIGN AND INSTALLATION SHALL COMPLY WITH ALL OSHA REGULATIONS

3 COPOLYMER POLYPROPYLENE MH STEP
SCALE: NOT TO SCALE



4 48" ROUND STRUCTURE PLACEMENT AT CURB
SCALE: NOT TO SCALE



NOTES:
1. NO DEVIATION IN THE SEPARATION ARRANGEMENTS WILL BE ALLOWED WITHOUT THE EXPRESS APPROVAL OF TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION, DIVISION OF WATERLINE SHALL BE REQUIRED WHERE SEPARATION OBJECTS CANNOT BE MAINTAINED.
2. WHEN IT IS IMPOSSIBLE TO OBTAIN VERTICAL SEPARATION AS INDICATED ABOVE, BOTH THE WATER MAIN AND THE SEWER MAIN SHALL BE CONSTRUCTED OF MECHANICAL JOINT DUCTILE IRON PIPE OR PVC WATER WORKS GRADE PRESSURE PIPE FOR 10' EACH SIDE OF CROSSING AND SHALL BE PRESSURE TESTED TO 150psi TO ASSURE WATER TIGHTNESS.

13 SANITARY/STORM SEWER AND WATERMAIN SEPARATION DETAIL
SCALE: NOT TO SCALE



NOTES:
1. BACKFILL USING TRENCH BACKFILL, COMPACTED IN 6" LIFTS.
2. CONTRACTOR SHALL CONSULT ADS NYLOPLAST MANUFACTURER FOR SIZING AND ORDERING BASINS.
3. BASINS SHALL BE A MINIMUM OF 18-INCH DIAMETER.
4. SHALLOW PRE-CAST CATCH BASIN MAY BE USED AS ALTERNATE WHERE APPROVED BY OWNER AND ENGINEER.
5. MANUFACTURER SHALL BE ADVANCED DRAINAGE SYSTEMS (ADS) OR APPROVED EQUAL.

17 NYOPLAST YARD DRAIN BASIN
SCALE: NOT TO SCALE





5 PIPE CONNECTION TO DRAINAGE STRUCTURE-CMP OR HDPE CEMENT GROUT SEAL JOINT
SCALE: NOT TO SCALE

STORM SEWER NOTES:
1. ALL STORM WATER MANAGEMENT STRUCTURES (I.E. CATCH BASIN, ETC.) SHALL BE REGULARLY INSPECTED FOR SEDIMENT ACCUMULATIONS. CATCH BASINS SHALL BE CLEANED WHEN SEDIMENT DEPTH REACHES A MAXIMUM OF 1/2 THE AVAILABLE SUMP DEPTH.
2. IF GROUNDWATER IS ENCOUNTERED DURING CONSTRUCTION ACTIVITIES, THE CONTRACTOR SHALL CONSTRUCT A DEWATERING PIT (A.K.A. SUMP PIT) TO TRAP AND FILTER WATER FOR PUMPING TO A SUITABLE DISCHARGE AREA. THE DEWATERING PIT SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE NPDES STATE GUIDELINES FOR URBAN EROSION AND SEDIMENT CONTROL, LATEST EDITION.
3. ALL EROSION CONTROL MEASURES EMPLOYED DURING THE CONSTRUCTION PROCESS SHALL BE AS OUTLINED IN THE EROSION AND SEDIMENT CONTROL PLANS, DETAILS AND NOTES.



NOTES:
1. SEWER PIPE FITTINGS TO BE ASTM D-3033 OR D-3034 SDR-35.
2. TO BE USED FOR GRAVITY PORTION OF SANITARY SYSTEM AS WELL AS THE STORM ROOF DRAINAGE SYSTEM.

11 CLEAN OUT - NON TRAFFIC AREA
SCALE: NOT TO SCALE

NOTES:
1. WHEN THE ELEVATION OF THE SEWER CAN NOT BE VARIED TO MEET THE ABOVE REQUIREMENTS, THE WATER MAIN SHALL BE RELOCATED TO PROVIDE THIS REQUIRED SEPARATION.
2. WHEN IT IS IMPOSSIBLE TO OBTAIN VERTICAL SEPARATION AS INDICATED ABOVE, BOTH THE WATER MAIN AND THE SEWER MAIN SHALL BE CONSTRUCTED OF MECHANICAL JOINT DUCTILE IRON PIPE OR PVC WATER WORKS GRADE PRESSURE PIPE FOR 10' EACH SIDE OF CROSSING AND SHALL BE PRESSURE TESTED TO 150psi TO ASSURE WATER TIGHTNESS.

14 WATERLINE OFFSET DETAIL
SCALE: NOT TO SCALE



NOTES:
1. CATCH BASIN INLET BASINS SHALL BE PRECAST CONCRETE. DESIGNED FOR HS20-44 VEHICULAR LOADING + 25% IMPACT AS MANUFACTURED BY FORT MILLER OR APPROVED EQUAL.
2. CATCH BASIN SHALL NOT HAVE A DEPTH GREATER THAN 60" FROM FINISHED SURFACE.
3. BACKFILL USING TRENCH BACKFILL, COMPACTED IN 6" LIFTS.
4. MAX STORM SEWER PIPE FOR STANDARD CATCH BASIN IS 15".
5. ALL PRECAST CONSTRUCTION IN ACCORDANCE W/ ASTM C478

6 PRECAST CONCRETE SHALLOW CATCH BASIN DETAIL
SCALE: NOT TO SCALE

IN-LINE DRAIN DIMENSIONS

BODY	ADAPTOR	B	C	E	MIN INV DEPTH
8"	6"	5.25"	4.21"	12.75"	2'-0"
8"	8"	7.25"	5.25"	13.25"	2'-2"
10"	8"	8.75"	4.21"	12.75"	2'-4"
10"	8"	6.50"	5.25"	13.25"	2'-2"
10"	10"	7.75"	6.06"	13.75"	2'-4"
12"	8"	11.50"	4.21"	12.75"	2'-6"
12"	8"	11.50"	5.25"	13.25"	3'-0"
12"	10"	11.25"	6.06"	21.75"	3'-0"
12"	12"	6.00"	6.45"	23.50"	3'-6"



15 YARD IN-LINE DRAIN
SCALE: NOT TO SCALE



NOTE:
1. CASTINGS RATED STANDARD HS20-44 LOADING
2. MATERIAL SHALL CONFORM TO ASTM A48-CLASS 30B
3. PAINT: CASTINGS TO BE FURNISHED WITH A BLACK PAINT
4. IN-LINE DRAIN BY NYLOPLAST OR APPROVED EQUIVALENT
5. DRAIN AREA = 52.7 SQ. INCH

16 12" IN-LINE DRAIN & GRATE
SCALE: NOT TO SCALE



NOTES:
1. CATCH BASIN SHALL BE PRECAST CONCRETE. DESIGNED FOR HS20-44 VEHICULAR LOADING AND 25% IMPACT.
2. FRAME AND COVER SHALL BE DESIGNED FOR HS20-44 VEHICULAR LOADING & 25% IMPACT.
3. CONCRETE CATCH BASIN CASTING CLEAR OPENING DIMENSION MUST MATCH FRAME AND GRATE CLEAR OPENING DIMENSION.
4. CATCH BASINS HAVING A DEPTH GREATER THAN 48" FROM FINISHED SURFACE TO THE TOP OF THE CONCRETE BASE SHALL BE PROVIDED WITH STEPS.
5. BACKFILL USING TRENCH BACKFILL, COMPACTED IN 6" LIFTS.
6. SUMPS FOR CATCH BASINS SHALL BE 12".
7. EJ GROUP GRATE & FRAME OR EQUIVALENT.

CATCH BASIN, FRAME AND GRATE SIZES:

STRUCTURE INSIDE DIMENSIONS:	FRAME & GRATE:
30"x30"	V5630 ASSEMBLY BY EJ GROUP/JB SONS 4315 F&G
30"x48"	7588Z1 W/7589M3 GRATE BY EJ GROUP
36"x36"	V5636 ASSEMBLY BY EJ GROUP
48"X48"	V5648 DUAL GRATE ASSEMBLY BY EJ GROUP

18 PRECAST CONCRETE RECTANGULAR CATCH BASIN DETAIL
SCALE: NOT TO SCALE

Order Plans @ WILDLine.com

PETER NORMANDIN
LICENSED PROFESSIONAL ENGINEER
STATE OF TENNESSEE
No. 120944
5/11/20
DEPT. OF ENGINEERING

ALL APPROPRIATE COPYRIGHTS RESERVED BY CHAZEN ENGINEERING CONSULTANTS, LLC. ANY UNAUTHORIZED USE, REPRODUCTION OF THIS PLAN, OR PORTION OF IT, OR DESIGNS, SHOWN, OR IMPLIED, WITHOUT THE WRITTEN PERMISSION OF CHAZEN ENGINEERING CONSULTANTS, LLC IS STRICTLY PROHIBITED AND SHALL BE ACTIONABLE AT LAW. THE APPROVAL OF THIS PLAN DOES NOT CONSTITUTE OR IMPLY THE ASSUMPTION OF RESPONSIBILITY FOR THE DESIGN, ACCURACY, SUFFICIENCY OR PROPRIETY OF THE PLAN AND THE METHODS OF CONSTRUCTION, AND WE, THE APPROVING ENTITY, SHALL NOT BE MADE RESPONSIBLE FOR ANY OF THE SAME.

CHAZEN ENGINEERING CONSULTANTS, LLC
2415 21st Ave South (Suite 103) Nashville, TN 37212 Phone: (615) 320-7203
1426 Williams Street (Suite 12) Chattanooga, TN 37408 Phone: (423) 541-3570
Knoxville Office: 9111 Cross Park Drive, Suite D200 Knoxville, TN 37923 Phone: (865) 357-4010
Memphis Office: 6000 Poplar Avenue, Suite 160 Memphis, TN 38119 Phone: (901) 767-6510
Nashville Office: 2121 First Tennessee Plaza 800 S. Gay Street Knoxville, TN 37929 Phone: (865) 544-5266
Capital Area Office: 547 Mt. Lebanon Road Suite 108 Bldg. 1, Unit 6 Phone: (615) 933-0000

rev.	date	description

ISSUED FOR CITY OF CHATTANOOGA LAND DISTURBANCE PERMIT

FOUNDRY33 - RESIDENTIAL DEVELOPMENT

STORM AND SANITARY SEWER DETAILS

CITY OF CHATTANOOGA, HAMILTON COUNTY, TN

drawn	checked
TCC	TCC
date	scale
5/11/2020	NTS
project no.	
11916.01	
sheet no.	
C540	

Drawing Name: Z:\projects\11900-11999\11916-01 - 33rd & Brood Neyland\DWG\03_C540_11916-01_STORM SEWER & SANITARY DETAILS.dwg
Xref's Attached: X16_11916-01_30x42
Date Printed: May 12, 2020, 4:15pm